

Tree Survey Schedule

Site Land off Lake Lane, Barnham
 Project schedule ref: JSL2477_750A
 Drawing reference: JSL2477_700, 701 & 703
 Survey date: 24th April 2015 - Re-survey 15/5/17

Surveyor: CC
 Status: For Info
 Revision: A
 Notes:



Ref. no.	Species	Height (m)	Crown spread (m)				Stem dia. (m)	Stem no. at 1.5m	Height of crown clearance (m)	Dir/ height	Age class	Structural Physiological condition	General observations Management recommendations	Estimated remaining contribution (years)	Tree Quality Category (BS5837)
			N	E	S	W									
T1	Cupressocyparis leylandii Leyland Cypress	9.0	2.0	4.0	7.0	7.0	0.40	1.00	2.50	W	EM	Fair	Stem wounds are present, asymmetric formed crown. Heavily suppressed crown. General poor form to tree.	10-20	C2
T2	Acer platanoides Norway Maple	6.0	8.0	5.0	7.0	4.0	0.55	1.00	2.00	S	EM	Poor	Stem wounds are present, asymmetric formed crown. Suppressed crown.	10-20	C2
T3	Acer platanoides Norway Maple	6.0	9.0	5.0	4.5	6.5	0.59	1.00	2.50	S	EM	Poor	Stem wounds are present, asymmetric formed crown. Suppressed crown.	10-20	C2
T4	Ilex aquifolium Common Holly	3.0	3.0	1.0	1.0	1.0	0.50	10+	0.25	N/E	EM	Good	Small scrubby.	-10	C2
T5	Ilex aquifolium Common Holly	3.0	1.0	1.5	1.5	1.5	0.24	2.00	0.25	-	EM	Poor	Limited crown spread.	-10	C2
T6	Ilex aquifolium Variegated Holly	2.0	1.5	1	1	1.0	0.15	3.00	0.25	S/E	EM	Poor	Limited crown spread.	-10	C2
T7	Ilex aquifolium Variegated Holly	4.0	1.0	1.0	1.0	1.0	0.24	1.00	0.25	N	EM	Poor	Limited crown spread.	-10	C2
T8	Ilex aquifolium Variegated Holly	4.0	1.5	1.5	1.5	1.5	0.24	1.00	0.25	S/E	EM	Poor	Limited crown spread.	-10	C2
T9	Amelanchier lamarckii Snowy Mespils	4.5	4.0	3.0	1.5	3.0	0.10	1.00	1.25	N	EM	Fair	Fair	10-20	C2
T10	Acer platanoides 'crimson glow' Norway Maple (purple)	6.0	3.5	3.5	3.5	3.5	0.32	1.00	2.50	S/E	EM	Fair	Fair. Dead wood noted. Red foliated form.	10-20	C2
T11	Acer platanoides Norway Maple (variegated cultivar)	6.0	3.5	3.5	3.5	3.5	0.38	1.00	0.25	N	EM	Good	Fair. Variegated foliage reverting, tree is growing into overhead cable. Dead wood.	10-20	C2

Note: This survey is based on a brief visual inspection from the ground.
 It is not intended as a full arboricultural inspection.
 # - Indicates estimated / offsite tree

Tree Survey Schedule

Site Land off Lake Lane, Barnham
 Project schedule ref: JSL2477_750A
 Drawing reference: JSL2477_700, 701 & 703
 Survey date: 24th April 2015 - Re-survey 15/5/17

Surveyor: CC
 Status: For Info
 Revision: A
 Notes:



Ref. no.	Species	Height (m)	Crown spread (m)				Stem dia. (m)	Stem no. at 1.5m	Height of crown clearance (m)	Dir/ height	Age class	Structural Physiological condition	General observations Management recommendations	Estimated remaining contribution (years)	Tree Quality Category (BS5837)
			N	E	S	W									
T12	Populus alba White Poplar	21.0	7.0	7.0	7.0	7.0	0.39	1.00	4.50	N	M	Good	Large boundary tree, part of the linear group.	+ 20	C2
T13	Pinus sylvestris Scots Pine	17.0	7.0	7.0	5.0	4.0	0.66	1.00	2.00	N	M	Good	Large mature tree, crown has been suppressed due to adjacent trees. Dead wood snags. Defects noted in northern limb. Crossing/contacted limbs and acute angle attachment.	+ 40	B2
T14	Acer pseudoplatanus Sycamore	8.0	3.0	1.0	2.0	3.0	0.25	1.00	1.25	N	EM	Fair/Poor	Suppressed, located on ditch side. Forks at 2.5m. Ivy.	+ 15	C2
T15	Acer platanoides Norway Maple	9.0	5.0	1.5		2.0	0.27	1.00	1.25	N	M	Poor	Leaning west. Ivy on bole.	+ 15	C2
T16	Acer pseudoplatanus Sycamore	10.0	1.0	1.5	4.5	2.0	0.26	1.00	4.00	S	EM	fair	Tight on bank side. Bias to the north.	+ 15	C2
T17	Acer pseudoplatanus Sycamore	16.0	4.0	2.0	4.0	2.0	0.27	1.00	2.00	E	EM	Fair	Established tight to bank side.	+ 15	C2
T18	Cupressus macrocarpa Monterey Cypress	16.0	5.0	4.0	2.5	4.0	0.41	1.00	0.75	NW	M	Fair	Bias to the north-west. Lower dead wood.	+ 20	C2
T19	Cupressus macrocarpa Monterey Cypress	14.0	4.0	2.0	2.0	2.0	0.29	1.00	0.50	N	EM	Fair	Unremarkable.	+ 15	C2
T20	Cupressus macrocarpa Monterey Cypress	9.0	3.5	3.5	3.5	3.5	0.42	1.00	0.50	W	M	Fair	Trunk formed of a sweeping bough.	+ 15	C2
T21	Cupressus macrocarpa Monterey Cypress	11.0	3.5	1.5	5.0	3.0	0.29	1.00	0.50	N	EM	Fair	Unremarkable.	+ 15	C2
T22	Cupressus macrocarpa Monterey Cypress	16.0	3.5	2.0	3.5	2.0	0.28	1.00	0.50	N	M	Fair	Lost limbs hanging, storm blown.	+ 15	C2

Note: This survey is based on a brief visual inspection from the ground.
 It is not intended as a full arboricultural inspection.
 # - Indicates estimated / offsite tree

Tree Survey Schedule

Site Land off Lake Lane, Barnham
 Project schedule ref: JSL2477_750A
 Drawing reference: JSL2477_700, 701 & 703
 Survey date: 24th April 2015 - Re-survey 15/5/17

Surveyor: CC
 Status: For Info
 Revision: A
 Notes:



Ref. no.	Species	Height (m)	Crown spread (m)				Stem dia. (m)	Stem no. at 1.5m	Height of crown clearance (m)	Dir/ height	Age class	Structural Physiological condition	General observations Management recommendations	Estimated remaining contribution (years)	Tree Quality Category (BS5837)
			N	E	S	W									
T23	Cupressus macrocarpa Monterey Cypress	15.0	3.5	2.5	3.5	2.5	0.28	1.00	0.50	N	M	Fair	Within group of trees bounding the ditch.	+ 15	C2
T24	Cupressus macrocarpa Monterey Cypress	15.0	3.5	2.5	3.5	2.5	0.23	1.00	0.50	N	M	Fair	Within group of trees bounding the ditch.	+ 15	C2
T25	Cupressus macrocarpa Monterey Cypress	15.0	3.5	2.5	3.5	2.5	0.24	1.00	0.50	N	M	Fair	Within group of trees bounding the ditch.	+ 15	C2
T26	Cupressus macrocarpa Monterey Cypress	15.0	3.5	2.5	3.5	2.5	0.29	1.00	0.50	N	M	Fair	Within group of trees bounding the ditch.	+ 15	C2
T27	Cupressus macrocarpa Monterey Cypress	15.0	3.5	2.5	3.5	2.5	0.33	1.00	0.50	N	M	Fair	Within group of trees bounding the ditch.	+ 15	C2
T28	Cupressus macrocarpa Monterey Cypress	15.0	3.5	2.5	3.5	2.5	0.31	1.00	0.50	N	M	Fair	Within group of trees bounding the ditch.	+ 15	C2
G1	Cupressocyparis leylandii Leyland Cypress	17.0	As shown				-	-	-	-	M	Fair	These have asymmetrical formed crowns. This group consists of fairly grown out individuals	+ 20	C2
G2	Cupressocyparis leylandii Leyland Cypress	4.0	As shown				-	-	-	-	M	Fair	All along eastern boundary Part of linear group along road. Some snapped branches but good overall condition.	+ 20	C2
G3	Alnus glutinosa Common Alder	18.0	As shown				-	-	-	-	EM	Good	There are asymmetrical formed crowns, and the trees have a heavily suppressed form, but good overall condition. Well suited to ground conditions.	+ 40	B2
G4	Cupressocyparis leylandii, Populus alba Leyland Cypress, White Poplar	4.0	As shown				-	-	-	-	M	Fair	Buffer/ shelter belt group	+ 20	C2

Note: This survey is based on a brief visual inspection from the ground.
 It is not intended as a full arboricultural inspection.

- Indicates estimated / offsite tree

Tree Survey Schedule

Site Land off Lake Lane, Barnham
 Project schedule ref: JSL2477_750A
 Drawing reference: JSL2477_700, 701 & 703
 Survey date: 24th April 2015 - Re-survey 15/5/17

Surveyor: CC
 Status: For Info
 Revision: A
 Notes:



Ref. no.	Species	Height (m)	Crown spread (m)				Stem dia. (m)	Stem no. at 1.5m	Height of crown clearance (m)	Dir/ height	Age class	Structural Physiological condition	General observations Management recommendations	Estimated remaining contribution (years)	Tree Quality Category (BS5837)
			N	E	S	W									
G5	Cupressocyparis leylandii, Thuja plicata Leyland Cypress, Western Red Cedar	9.0	As shown				-	-	-	-	EM	Fair	Two distinct linear groups . These have asymmetrical formed crowns. The lesser bounding group to the north and running east-west has been managed as a lower 6m hedge. The to the west buffer group is greater in height and provides enclosure to the car parking area, little else.	+ 20	C2
G6	Acer pseudoplatanus, Cupressocyparis leylandii, Thuja plicata Sycamore, Leyland Cypress, Western Red Cedar	16.0	As shown				-	-	-	-	EM	Fair	Part of linear group along road and the northern boundary	+ 20	C2
G7	Tilia sp, Acer pseudoplatanus, Quercus robur Lime sp. Sycamore, English Oak	12.0	As shown				-	-	-	-	EM	Fair	A group of lime and other broadleaf trees of moderate value, together with the vegetation bounding the public footpath.	+ 20	B2
H1	Crataegus monogyna, Ligustrum ovalifolium Hawthorn, Privet	1.8	As shown				-	-	-	-	EM	Fair	Hawthorn- rich hedge	+ 20	C2
H2	Crataegus monogyna, Corylus avellana Hawthorn, Hazel	2.25	As shown				-	-	-	-	EM	Fair	Mixed species agricultural hedge at foot of the nursery site	+ 20	C2

Note: This survey is based on a brief visual inspection from the ground.
 It is not intended as a full arboricultural inspection.

- Indicates estimated / offsite tree