

Ecological Enhancement Specification
To be installed in conjunction with Ecological Enhancement Plan

Item	Extent	Installation/Specification	Example Image
Vivara Pro Seville 32mm Woodstone Bird Nest Box https://www.nhbs.com	1no. box	To be installed to the northern aspect of a mature tree at a height of 2.0 – 3.0m.	
'Hedgehog Friendly' Gravel Board	All new fencing erected on site	13cm x 13cm gaps at the base of fencing or, specifically bought gravel boards with readymade gaps, to be installed between gardens to allow free movement of hedgehogs around the site.	
Igloo Hedgehog Home or equal https://www.nhbs.com	1no. hedgehog home	Hedgehog homes are to be installed within areas of vegetation to the boundaries of the site.	
Log Pile	2no. log piles	Log pile created with minimum 10cm diameter logs. Piles to be formed either horizontally or vertically.	
Integrated Bat Box (produced by Bird Brick Houses) https://www.birdbrickhouses.co.uk	1no. box	Installed on south east to south west facing walls to the buildings. Box can be clad to match proposed. Avoid positions above windows and doors.	B 

Integrated Swift Box (produced by Bird Brick Houses) https://www.birdbrickhouses.co.uk	1no. box	2no. installed to the northern wall of the new building with minimum of 5m clear drop beneath. Box to match proposed wall finish. Avoid positions above windows and doors.	
Integrated Sparrow Terrace (produced by Bird Brick Houses) https://www.birdbrickhouses.co.uk	1no. box	3no. installed to north facing walls. Boxes can be clad to match proposed.	