



LEGEND:

Proposed Dwelling Houses

Proposed 'Red Carpet' Feature Road Surface
Red brick.

Primary Access Roads
Tarmacadam surface.

Secondary Access Roads
Blockwork surface.

Raised Junctions
Blockwork surface.

Car Parking Spaces
Surface treatment varies.

Parking Spaces to Private Drives
Blockwork surface.

Grassed Areas/ Lawns
Proposed grass areas to residential gardens to provide opportunities for recreation and privacy.
Proposed Lindum 'Festival Landscape Turf' Mix

Residential Frontages
Evergreen hedge planting to residential frontages.

Proposed Signature Tree
Semi-mature Tree
30-35 cm Girth Size; 6.0 - 6.5 m Height;
Underground Guying System

Proposed Entrance Avenue Trees
Standard Extra Heavy Tree Planting
14-16 cm Girth Size; 4.0 - 4.5 m Height;
Clear Stem Height;
Long Double Staking

Proposed Car Park Trees
Standard Selected Tree Planting
10-12 cm Girth Size; 3.0 - 3.5 m Height; min. 220 cm Clear Stem;
Long Single Staking

Proposed Street Trees
Standard Selected Tree Planting
10-12 cm Girth Size; 3.0 - 3.5 m Height; min. 220 cm Clear Stem Height;
Long Single Staking

Proposed Trees to Public Spaces
Standard Selected Tree Planting
10-12 cm Girth Size; 3.0 - 3.5 m Height;
Long Single Staking

Proposed Roadside Boundary Treatment
Proposed mixed-species native and ornamental planting with swathes of wildflower meadow to area between public footpath and the proposed development.

Proposed Planting to Public Spaces
Proposed mixed-species native and ornamental planting to enhance visual amenity and ecological opportunities within open public spaces

Proposed Ecological Boundary Treatment
Proposed native hedge and understorey planting to enhance and reinforce the existing hedgerows and provide ecological corridors along site boundary.

Proposed Ecological Buffer Zone
Proposed native planting with shrubs, wildflower grassland and piles of brash and logs to provide diverse habitat and forage opportunity for local fauna.
An unobstructed maintenance access zone shall be provided to ditches within 3 metres from any ditch.

Water Body
Proposed SUDS with a retention basin within Ecological Buffer Zone.

Draft Issue			
Rev	Description	Date	Initials
00	Draft Issue	21.06.16	MZ

Lizard Landscape Design

34 South Street
Tarring
Worthing
West Sussex
BN14 7LH
Tel: 01903 216033
Email: lizard.landscape@btconnect.com

Project Title

Angel's Nursery
Barnham, West Sussex

Drawing Title

Landscape Masterplan

Scale
1:500@A1

Drawn
MZ
Approved

Date
21/06/16

Drawing No
LLD1006/ 01

Revision
00

Filepath
LLD1006 /InDesign

Landscape Masterplan

Angel's Nursery, Barnham, West Sussex