

All dimensions are in millimetres.

For dimensions of soakaways refer to schedules on contract specific drawings.

HR400 B125 covers are suitable for the following locations :


- A) Verges
- B) Footways / Pedestrian Areas
- C) Car Parks

Units shall be Charcon Permavoid 150, or equivalent contact Charcon Tel : 01509 615100

Units shall be laid fully in accordance with manufacturers instructions

All details shall otherwise be in accordance with The Department of Transport Specification For Highway Works, 7th Edition.

Soakaways shall be 5m away from any buildings or structures.



Soakaway Serving 120m² (Garage) : Length (L) = 7.81m. Width (W) = 3.55m

REV	DESCRIPTION	DATE
 Archibald Shaw Consulting Civil & Structural Engineers One Little London Chichester West Sussex PO19 1PP Telephone: 01243 786471 Facsimile: 01243 779346 mail@archibaldshaw.co.uk www.archibaldshaw.co.uk		
PROJECT Standard Detail High Storage Soakaway : Permavoid 150 Units Meadow View, Barnham		
DRAWN BY	CHECKED BY	DESIGNED BY
RJL	PEF	RJL
SCALE	DATE	
N.T.S.	Mar. 2019	
STD NO.		REVISION
30253-STD.01.63		-