

Woods Hardwick		Page 1
15-17 Goldington Road Bedford MK40 3NH	SWS Net 1 17748 Yapton Road Barnham	
Date 07/05/2020 10:20	Designed by C.Smith	
File SWS BARNHAM 31072019 test.MDX	Checked by	
Micro Drainage		Network 2018.1.1

STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.000	7.249	0.072	100.7	0.027	6.00	0.0	0.600	o	150	Pipe/Conduit	
1.001	4.810	0.054	89.1	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
2.000	8.832	0.088	100.4	0.038	6.00	0.0	0.600	o	150	Pipe/Conduit	
2.001	12.200	0.128	95.3	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.002	45.400	0.184	246.7	0.017	0.00	0.0	0.600	o	300	Pipe/Conduit	
3.000	8.814	0.088	100.2	0.116	6.00	0.0	0.600	o	225	Pipe/Conduit	
3.001	7.104	0.071	100.1	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.003	41.039	0.171	240.0	0.036	0.00	0.0	0.600	o	300	Pipe/Conduit	
4.000	6.964	0.070	99.5	0.080	6.00	0.0	0.600	o	150	Pipe/Conduit	
4.001	6.700	0.155	43.2	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.004	32.806	0.134	244.8	0.042	0.00	0.0	0.600	o	300	Pipe/Conduit	
5.000	6.272	0.063	99.6	0.025	6.00	0.0	0.600	o	150	Pipe/Conduit	
5.001	4.928	0.095	51.9	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
5.002	12.000	0.074	162.2	0.011	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.005	10.462	0.033	317.0	0.000	0.00	0.0	0.600	o	375	Pipe/Conduit	
6.000	5.288	0.053	99.8	0.054	6.00	0.0	0.600	o	150	Pipe/Conduit	
6.001	7.275	0.072	101.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	I.Area (ha)	Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	50.00	6.12	8.056	0.027	0.0	0.0	0.0	1.00	17.7	3.7
1.001	50.00	6.20	7.984	0.027	0.0	0.0	0.0	1.07	18.8	3.7
2.000	50.00	6.15	8.146	0.038	0.0	0.0	0.0	1.00	17.7	5.1
2.001	50.00	6.34	8.058	0.038	0.0	0.0	0.0	1.03	18.2	5.1
1.002	47.05	7.10	7.780	0.082	0.0	0.0	0.0	1.00	70.4	10.4
3.000	50.00	6.11	7.905	0.116	0.0	0.0	0.0	1.31	51.9	15.7
3.001	50.00	6.20	7.817	0.116	0.0	0.0	0.0	1.31	52.0	15.7
1.003	44.50	7.78	7.596	0.234	0.0	0.0	0.0	1.01	71.4	28.2
4.000	50.00	6.12	7.800	0.080	0.0	0.0	0.0	1.01	17.8	10.8
4.001	50.00	6.19	7.730	0.080	0.0	0.0	0.0	1.53	27.1	10.8
1.004	42.68	8.33	7.425	0.356	0.0	0.0	0.0	1.00	70.7	41.1
5.000	50.00	6.10	7.673	0.025	0.0	0.0	0.0	1.01	17.8	3.4
5.001	50.00	6.16	7.610	0.025	0.0	0.0	0.0	1.40	24.7	3.4
5.002	50.00	6.36	7.440	0.036	0.0	0.0	0.0	1.02	40.7	4.9
1.005	42.14	8.50	7.216	0.392	0.0	0.0	0.0	1.01	111.8	44.7
6.000	50.00	6.09	7.650	0.054	0.0	0.0	0.0	1.01	17.8	7.3
6.001	50.00	6.21	7.597	0.054	0.0	0.0	0.0	1.00	17.7	7.3

Woods Hardwick		Page 2
15-17 Goldington Road	SWS Net 1	
Bedford	17748 Yapton Road	
MK40 3NH	Barnham	
Date 07/05/2020 10:20	Designed by C.Smith	
File SWS BARNHAM 31072019 test.MDX	Checked by	
Micro Drainage	Network 2018.1.1	

STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
6.002	28.500	0.117	243.6	0.021	0.00	0.0	0.600	o	300	Pipe/Conduit	
7.000	8.164	0.082	99.6	0.027	6.00	0.0	0.600	o	150	Pipe/Conduit	
7.001	6.467	0.065	99.5	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.006	30.532	0.075	407.1	0.016	0.00	0.0	0.600	o	450	Pipe/Conduit	
8.000	20.088	0.057	352.4	0.000	6.00	0.0	0.600	o	450	Pipe/Conduit	
1.007	3.548	0.033	107.0	0.032	0.00	0.0	0.600	o	150	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
6.002	48.85	6.68	7.375	0.075	0.0	0.0	0.0	1.00	70.9	9.9
7.000	50.00	6.14	7.555	0.027	0.0	0.0	0.0	1.01	17.8	3.7
7.001	50.00	6.24	7.473	0.027	0.0	0.0	0.0	1.01	17.8	3.7
1.006	40.67	9.01	7.108	0.510	0.0	0.0	0.0	1.00	159.3	56.2
8.000	50.00	6.31	7.090	0.000	0.0	0.0	0.0	1.08	171.3	0.0
1.007	50.00	6.06	7.033	0.000	5.0	0.0	0.0	0.97	17.2	5.0

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.000	o	150	1	8.900	8.056	0.694	Open Manhole	600
1.001	o	150	2	8.900	7.984	0.766	Open Manhole	600
2.000	o	150	10	8.750	8.146	0.454	Open Manhole	600
2.001	o	150	11	8.750	8.058	0.542	Open Manhole	600
1.002	o	300	3	9.088	7.780	1.008	Open Manhole	1200
3.000	o	225	20	8.900	7.905	0.770	Open Manhole	600
3.001	o	225	21	8.900	7.817	0.858	Open Manhole	600
1.003	o	300	4	8.898	7.596	1.002	Open Manhole	1500
4.000	o	150	9	8.850	7.800	0.900	Open Manhole	1200
4.001	o	150	10	8.850	7.730	0.970	Open Manhole	1200
1.004	o	300	5	8.736	7.425	1.011	Open Manhole	1500
5.000	o	150	30	8.400	7.673	0.577	Open Manhole	600
5.001	o	150	31	8.400	7.610	0.640	Open Manhole	600
5.002	o	225	32	8.612	7.440	0.947	Open Manhole	1200
1.005	o	375	6	8.790	7.216	1.199	Open Manhole	1500
6.000	o	150	40	8.600	7.650	0.800	Open Manhole	600
6.001	o	150	41	8.600	7.597	0.853	Open Manhole	600

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.000	7.249	100.7	2	8.900	7.984	0.766	Open Manhole	600
1.001	4.810	89.1	3	9.088	7.930	1.008	Open Manhole	1200
2.000	8.832	100.4	11	8.750	8.058	0.542	Open Manhole	600
2.001	12.200	95.3	3	9.088	7.930	1.008	Open Manhole	1200
1.002	45.400	246.7	4	8.898	7.596	1.002	Open Manhole	1500
3.000	8.814	100.2	21	8.900	7.817	0.858	Open Manhole	600
3.001	7.104	100.1	4	8.898	7.746	0.927	Open Manhole	1500
1.003	41.039	240.0	5	8.736	7.425	1.011	Open Manhole	1500
4.000	6.964	99.5	10	8.850	7.730	0.970	Open Manhole	1200
4.001	6.700	43.2	5	8.736	7.575	1.011	Open Manhole	1500
1.004	32.806	244.8	6	8.790	7.291	1.199	Open Manhole	1500
5.000	6.272	99.6	31	8.400	7.610	0.640	Open Manhole	600
5.001	4.928	51.9	32	8.612	7.515	0.947	Open Manhole	1200
5.002	12.000	162.2	6	8.790	7.366	1.199	Open Manhole	1500
1.005	10.462	317.0	7	8.641	7.183	1.083	Open Manhole	1800
6.000	5.288	99.8	41	8.600	7.597	0.853	Open Manhole	600
6.001	7.275	101.0	42	8.577	7.525	0.902	Open Manhole	1500

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
6.002	o	300	42	8.577	7.375	0.902	Open Manhole	1500
7.000	o	150	50	8.400	7.555	0.695	Open Manhole	600
7.001	o	150	51	8.400	7.473	0.777	Open Manhole	600
1.006	o	450	7	8.641	7.108	1.083	Open Manhole	1800
8.000	o	450	8A	8.250	7.090	0.710	Open Manhole	1500
1.007	o	150	8	8.250	7.033	1.067	Open Manhole	1800

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
6.002	28.500	243.6	7	8.641	7.258	1.083	Open Manhole	1800
7.000	8.164	99.6	51	8.400	7.473	0.777	Open Manhole	600
7.001	6.467	99.5	7	8.641	7.408	1.083	Open Manhole	1800
1.006	30.532	407.1	8	8.250	7.033	0.767	Open Manhole	1800
8.000	20.088	352.4	8	8.250	7.033	0.767	Open Manhole	1800
1.007	3.548	107.0		7.820	7.000	0.670	Open Manhole	0

Free Flowing Outfall Details for Storm

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D,L (mm)	W (mm)
1.007		7.820	7.000	0.000	0	0

Simulation Criteria for Storm

Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m³/ha Storage	1.000
Hot Start (mins)	0	Inlet Coeffiecient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1

Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0
 Number of Online Controls 7 Number of Storage Structures 8 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model	FEH	D3 (1km)	0.396
Return Period (years)	2	E (1km)	0.308
FEH Rainfall Version	1999	F (1km)	2.327
Site Location	GB 495800 104050 SU 95800 04050	Summer Storms	Yes
C (1km)	-0.025	Winter Storms	No
D1 (1km)	0.403	Cv (Summer)	0.750
D2 (1km)	0.246	Cv (Winter)	0.840

Woods Hardwick		Page 5
15-17 Goldington Road Bedford MK40 3NH	SWS Net 1 17748 Yapton Road Barnham	
Date 07/05/2020 10:20 File SWS BARNHAM 31072019 test.MDX	Designed by C.Smith Checked by	
Micro Drainage	Network 2018.1.1	

Synthetic Rainfall Details

Storm Duration (mins) 30

Online Controls for Storm

Orifice Manhole: 2, DS/PN: 1.001, Volume (m³): 0.4

Diameter (m) 0.050 Discharge Coefficient 0.600 Invert Level (m) 7.984

Orifice Manhole: 11, DS/PN: 2.001, Volume (m³): 0.3

Diameter (m) 0.050 Discharge Coefficient 0.600 Invert Level (m) 8.058

Orifice Manhole: 10, DS/PN: 4.001, Volume (m³): 1.4

Diameter (m) 0.100 Discharge Coefficient 0.600 Invert Level (m) 7.730

Orifice Manhole: 31, DS/PN: 5.001, Volume (m³): 0.3

Diameter (m) 0.050 Discharge Coefficient 0.600 Invert Level (m) 7.610

Orifice Manhole: 41, DS/PN: 6.001, Volume (m³): 0.4

Diameter (m) 0.050 Discharge Coefficient 0.600 Invert Level (m) 7.597

Orifice Manhole: 51, DS/PN: 7.001, Volume (m³): 0.4

Diameter (m) 0.050 Discharge Coefficient 0.600 Invert Level (m) 7.473

Hydro-Brake® Optimum Manhole: 8, DS/PN: 1.007, Volume (m³): 10.6

Unit Reference	MD-SHE-0103-5000-1200-5000
Design Head (m)	1.200
Design Flow (l/s)	5.0
Flush-Flo™	Calculated
Objective	Minimise upstream storage
Application	Surface
Sump Available	Yes
Diameter (mm)	103
Invert Level (m)	7.033
Minimum Outlet Pipe Diameter (mm)	150
Suggested Manhole Diameter (mm)	1200

Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	1.200	5.0	Kick-Flo®	0.745	4.0
Flush-Flo™	0.354	5.0	Mean Flow over Head Range	-	4.4

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	3.4	0.800	4.1	2.000	6.3	4.000	8.8	7.000	11.5
0.200	4.7	1.000	4.6	2.200	6.6	4.500	9.3	7.500	11.8
0.300	5.0	1.200	5.0	2.400	6.9	5.000	9.8	8.000	12.2
0.400	5.0	1.400	5.4	2.600	7.2	5.500	10.2	8.500	12.6
0.500	4.9	1.600	5.7	3.000	7.7	6.000	10.7	9.000	12.9
0.600	4.7	1.800	6.0	3.500	8.3	6.500	11.1	9.500	13.3

Woods Hardwick		Page 7
15-17 Goldington Road	SWS Net 1	
Bedford	17748 Yapton Road	
MK40 3NH	Barnham	
Date 07/05/2020 10:20	Designed by C.Smith	
File SWS BARNHAM 31072019 test.MDX	Checked by	
Micro Drainage	Network 2018.1.1	

Storage Structures for Storm

Porous Car Park Manhole: 2, DS/PN: 1.001

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	10.0
Membrane Percolation (mm/hr)	1000	Length (m)	12.5
Max Percolation (l/s)	34.7	Slope (1:X)	100.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	7.984	Cap Volume Depth (m)	0.430

Porous Car Park Manhole: 11, DS/PN: 2.001

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	25.0
Membrane Percolation (mm/hr)	1000	Length (m)	8.0
Max Percolation (l/s)	55.6	Slope (1:X)	100.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	8.058	Cap Volume Depth (m)	0.450

Porous Car Park Manhole: 21, DS/PN: 3.001

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	20.0
Membrane Percolation (mm/hr)	1000	Length (m)	20.0
Max Percolation (l/s)	111.1	Slope (1:X)	250.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	7.925	Cap Volume Depth (m)	0.540

Porous Car Park Manhole: 10, DS/PN: 4.001

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	6.0
Membrane Percolation (mm/hr)	1000	Length (m)	24.0
Max Percolation (l/s)	40.0	Slope (1:X)	100.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	7.730	Cap Volume Depth (m)	0.400

Porous Car Park Manhole: 31, DS/PN: 5.001

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	9.5
Membrane Percolation (mm/hr)	1000	Length (m)	20.0
Max Percolation (l/s)	52.8	Slope (1:X)	100.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	7.610	Cap Volume Depth (m)	0.300

Porous Car Park Manhole: 41, DS/PN: 6.001

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	9.0
Membrane Percolation (mm/hr)	1000	Length (m)	20.0
Max Percolation (l/s)	50.0	Slope (1:X)	100.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	7.596	Cap Volume Depth (m)	0.600

Porous Car Park Manhole: 51, DS/PN: 7.001

Infiltration Coefficient Base (m/hr)	0.00000	Max Percolation (l/s)	27.8
Membrane Percolation (mm/hr)	1000	Safety Factor	2.0

Woods Hardwick		Page 8
15-17 Goldington Road	SWS Net 1	
Bedford	17748 Yapton Road	
MK40 3NH	Barnham	
Date 07/05/2020 10:20	Designed by C.Smith	
File SWS BARNHAM 31072019 test.MDX	Checked by	
Micro Drainage	Network 2018.1.1	

Porous Car Park Manhole: 51, DS/PN: 7.001

Porosity	0.30	Slope (1:X)	100.0
Invert Level (m)	7.473	Depression Storage (mm)	5
Width (m)	5.0	Evaporation (mm/day)	3
Length (m)	20.0	Cap Volume Depth (m)	0.400

Complex Manhole: 8, DS/PN: 1.007

Porous Car Park

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	3.0
Membrane Percolation (mm/hr)	1000	Length (m)	12.0
Max Percolation (l/s)	10.0	Slope (1:X)	200.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	7.033	Cap Volume Depth (m)	0.450

Tank or Pond

Invert Level (m) 7.120

Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)
0.000	95.0	1.130	248.2	1.132	248.6

Woods Hardwick		Page 9
15-17 Goldington Road Bedford MK40 3NH	SWS Net 1 17748 Yapton Road Barnham	
Date 07/05/2020 10:20	Designed by C.Smith	
File SWS BARNHAM 31072019 test.MDX	Checked by	
Micro Drainage		Network 2018.1.1

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000

Additional Flow - % of Total Flow 0.000

Hot Start (mins) 0

MADD Factor * 10m³/ha Storage 1.000

Hot Start Level (mm) 0

Inlet Coeffiecient 0.800

Manhole Headloss Coeff (Global) 0.500

Flow per Person per Day (l/per/day) 0.000

Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0

Number of Offline Controls 0

Number of Time/Area Diagrams 0

Number of Online Controls 7

Number of Storage Structures 8

Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH

D3 (1km) 0.396

FEH Rainfall Version 1999

E (1km) 0.308

Site Location GB 495800 104050 SU 95800 04050

F (1km) 2.327

C (1km) -0.025

Cv (Summer) 0.750

D1 (1km) 0.403

Cv (Winter) 0.840

D2 (1km) 0.246

Margin for Flood Risk Warning (mm) 450.0

Analysis Timestep 2.5 Second Increment (Extended)

DTS Status ON

DVD Status ON

Inertia Status ON

Profile(s) Summer and Winter

Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440

Return Period(s) (years) 1, 30, 100

Climate Change (%) 0, 0, 30

					Water Surcharged Flooded							
PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Level (m)	Depth (m)	Volume (m³)	Flow / Cap.
1.000	1	15 Winter	1	+0%	100/15 Summer				8.098	-0.108	0.000	0.17
1.001	2	30 Winter	1	+0%	100/15 Summer				8.056	-0.078	0.000	0.08
2.000	10	15 Winter	1	+0%	100/15 Summer				8.195	-0.101	0.000	0.24
2.001	11	60 Winter	1	+0%	100/15 Summer				8.123	-0.085	0.000	0.06
1.002	3	30 Winter	1	+0%	100/120 Winter				7.821	-0.259	0.000	0.05
3.000	20	15 Winter	1	+0%	100/15 Summer				7.984	-0.146	0.000	0.27
3.001	21	15 Winter	1	+0%	100/15 Summer				7.901	-0.141	0.000	0.30
1.003	4	15 Winter	1	+0%	100/15 Summer				7.699	-0.197	0.000	0.25
4.000	9	15 Winter	1	+0%	30/15 Summer				7.876	-0.074	0.000	0.51
4.001	10	15 Winter	1	+0%	30/15 Summer				7.853	-0.027	0.000	0.22
1.004	5	15 Winter	1	+0%	30/120 Winter				7.553	-0.172	0.000	0.38
5.000	30	15 Winter	1	+0%	100/15 Summer				7.713	-0.110	0.000	0.16
5.001	31	30 Winter	1	+0%	30/240 Winter				7.679	-0.081	0.000	0.06
5.002	32	15 Winter	1	+0%	30/60 Winter				7.473	-0.192	0.000	0.05
1.005	6	15 Winter	1	+0%	30/30 Winter				7.362	-0.229	0.000	0.32
6.000	40	30 Winter	1	+0%	30/15 Summer				7.716	-0.084	0.000	0.30
6.001	41	30 Winter	1	+0%	30/15 Summer				7.712	-0.035	0.000	0.10
6.002	42	15 Winter	1	+0%	30/60 Winter				7.417	-0.258	0.000	0.05
7.000	50	15 Winter	1	+0%	30/120 Winter				7.596	-0.109	0.000	0.17
7.001	51	15 Winter	1	+0%	30/15 Summer				7.561	-0.062	0.000	0.09
1.006	7	240 Winter	1	+0%	30/30 Winter				7.345	-0.213	0.000	0.09
8.000	8A	240 Winter	1	+0%	30/30 Winter				7.343	-0.197	0.000	0.00
1.007	8	240 Winter	1	+0%	1/15 Summer				7.343	0.160	0.000	0.44

Woods Hardwick		Page 10
15-17 Goldington Road Bedford MK40 3NH	SWS Net 1 17748 Yapton Road Barnham	
Date 07/05/2020 10:20	Designed by C.Smith	
File SWS BARNHAM 31072019 test.MDX	Checked by	
Micro Drainage		Network 2018.1.1

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Overflow (l/s)	Pipe Flow (l/s)	Status	Level
					Exceeded
1.000	1		2.6	OK	
1.001	2		1.1	OK	
2.000	10		3.7	OK	
2.001	11		1.0	OK	
1.002	3		3.0	OK	
3.000	20		11.3	OK	
3.001	21		11.3	OK	
1.003	4		16.8	OK	
4.000	9		7.8	OK	
4.001	10		5.1	OK	
1.004	5		24.3	OK	
5.000	30		2.4	OK	
5.001	31		1.1	OK	
5.002	32		1.8	OK	
1.005	6		25.9	OK	
6.000	40		4.4	OK	
6.001	41		1.6	OK	
6.002	42		3.1	OK	
7.000	50		2.6	OK	
7.001	51		1.3	OK	
1.006	7		12.5	OK	
8.000	8A		0.2	OK	
1.007	8		5.0	SURCHARGED	

Woods Hardwick		Page 11
15-17 Goldington Road	SWS Net 1	
Bedford	17748 Yapton Road	
MK40 3NH	Barnham	
Date 07/05/2020 10:20	Designed by C.Smith	
File SWS BARNHAM 31072019 test.MDX	Checked by	
Micro Drainage	Network 2018.1.1	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria	
Areal Reduction Factor	1.000
Hot Start (mins)	0
Hot Start Level (mm)	0
Manhole Headloss Coeff (Global)	0.500
Foul Sewage per hectare (l/s)	0.000
Additional Flow - % of Total Flow	0.000
MADD Factor * 10m³/ha Storage	1.000
Inlet Coeffiecient	0.800
Flow per Person per Day (l/per/day)	0.000
Number of Input Hydrographs	0
Number of Offline Controls	0
Number of Time/Area Diagrams	0
Number of Online Controls	7
Number of Storage Structures	8
Number of Real Time Controls	0

Synthetic Rainfall Details			
Rainfall Model	FEH	D3 (1km)	0.396
FEH Rainfall Version	1999	E (1km)	0.308
Site Location GB 495800 104050 SU 95800 04050		F (1km)	2.327
C (1km)	-0.025	Cv (Summer)	0.750
D1 (1km)	0.403	Cv (Winter)	0.840
D2 (1km)	0.246		

Margin for Flood Risk Warning (mm)	450.0
Analysis Timestep	2.5 Second Increment (Extended)
DTS Status	ON
DVD Status	ON
Inertia Status	ON

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 240, 360, 480, 960, 1440
Return Period(s) (years)	1, 30, 100
Climate Change (%)	0, 0, 30

					Water Surcharged Flooded							
PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Level (m)	Depth (m)	Volume (m³)	Flow / Cap.
1.000	1	30 Winter	30	+0%	100/15 Summer				8.136	-0.070	0.000	0.43
1.001	2	30 Winter	30	+0%	100/15 Summer				8.130	-0.004	0.000	0.12
2.000	10	15 Winter	30	+0%	100/15 Summer				8.244	-0.052	0.000	0.76
2.001	11	60 Winter	30	+0%	100/15 Summer				8.192	-0.016	0.000	0.10
1.002	3	15 Winter	30	+0%	100/120 Winter				7.853	-0.227	0.000	0.12
3.000	20	15 Winter	30	+0%	100/15 Summer				8.066	-0.064	0.000	0.86
3.001	21	15 Winter	30	+0%	100/15 Summer				7.973	-0.069	0.000	0.82
1.003	4	360 Winter	30	+0%	100/15 Summer				7.825	-0.071	0.000	0.17
4.000	9	15 Winter	30	+0%	30/15 Summer				8.122	0.172	0.000	1.57
4.001	10	15 Winter	30	+0%	30/15 Summer				7.995	0.115	0.000	0.42
1.004	5	360 Winter	30	+0%	30/120 Winter				7.822	0.097	0.000	0.26
5.000	30	360 Winter	30	+0%	100/15 Summer				7.818	-0.005	0.000	0.08
5.001	31	360 Winter	30	+0%	30/240 Winter				7.818	0.058	0.000	0.06
5.002	32	360 Winter	30	+0%	30/60 Winter				7.818	0.153	0.000	0.05
1.005	6	360 Winter	30	+0%	30/30 Winter				7.818	0.227	0.000	0.23
6.000	40	15 Winter	30	+0%	30/15 Summer				7.845	0.045	0.000	1.14
6.001	41	360 Winter	30	+0%	30/15 Summer				7.838	0.091	0.000	0.13
6.002	42	360 Winter	30	+0%	30/60 Winter				7.817	0.142	0.000	0.05
7.000	50	360 Winter	30	+0%	30/120 Winter				7.826	0.121	0.000	0.09
7.001	51	360 Winter	30	+0%	30/15 Summer				7.825	0.202	0.000	0.08
1.006	7	360 Winter	30	+0%	30/30 Winter				7.816	0.258	0.000	0.17
8.000	8A	360 Winter	30	+0%	30/30 Winter				7.815	0.275	0.000	0.00
1.007	8	360 Winter	30	+0%	1/15 Summer				7.815	0.632	0.000	0.44

Woods Hardwick		Page 12
15-17 Goldington Road Bedford MK40 3NH	SWS Net 1 17748 Yapton Road Barnham	
Date 07/05/2020 10:20	Designed by C.Smith	
File SWS BARNHAM 31072019 test.MDX	Checked by	
Micro Drainage		Network 2018.1.1

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Overflow (l/s)	Pipe Flow (l/s)	Status	Level Exceeded
1.000	1		6.6	OK	
1.001	2		1.8	OK	
2.000	10		11.8	OK	
2.001	11		1.7	OK	
1.002	3		8.2	OK	
3.000	20		36.0	OK	
3.001	21		30.9	OK	
1.003	4		11.0	OK	
4.000	9		23.8	SURCHARGED	
4.001	10		9.7	SURCHARGED	
1.004	5		17.1	SURCHARGED	
5.000	30		1.3	OK	
5.001	31		1.2	SURCHARGED	
5.002	32		1.7	SURCHARGED	
1.005	6		18.8	SURCHARGED	
6.000	40		16.4	SURCHARGED	
6.001	41		1.9	SURCHARGED	
6.002	42		2.9	SURCHARGED	
7.000	50		1.3	SURCHARGED	
7.001	51		1.2	SURCHARGED	
1.006	7		22.7	SURCHARGED	
8.000	8A		0.1	FLOOD RISK	
1.007	8		5.0	FLOOD RISK	

Woods Hardwick		Page 13
15-17 Goldington Road	SWS Net 1	
Bedford	17748 Yapton Road	
MK40 3NH	Barnham	
Date 07/05/2020 10:20	Designed by C.Smith	
File SWS BARNHAM 31072019 test.MDX	Checked by	
Micro Drainage	Network 2018.1.1	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	1.000
Hot Start Level (mm)	0	Inlet Coeffiecient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		
Number of Input Hydrographs	0	Number of Offline Controls	0
Number of Online Controls	7	Number of Storage Structures	8
		Number of Time/Area Diagrams	0
		Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FEH	D3 (1km)	0.396
FEH Rainfall Version	1999	E (1km)	0.308
Site Location GB 495800 104050 SU 95800 04050		F (1km)	2.327
C (1km)	-0.025	Cv (Summer)	0.750
D1 (1km)	0.403	Cv (Winter)	0.840
D2 (1km)	0.246		

Margin for Flood Risk Warning (mm)	450.0
Analysis Timestep 2.5 Second Increment (Extended)	
DTS Status	ON
DVD Status	ON
Inertia Status	ON

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 240, 360, 480, 960, 1440
Return Period(s) (years)	1, 30, 100
Climate Change (%)	0, 0, 30

PN	US/MH		Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Surcharged Flooded			
	Name	Storm							Level (m)	Depth (m)	Volume (m³)	Flow / Cap.
1.000	1	15 Winter	100	+30%	100/15 Summer				8.249	0.043	0.000	1.07
1.001	2	60 Winter	100	+30%	100/15 Summer				8.234	0.100	0.000	0.16
2.000	10	15 Winter	100	+30%	100/15 Summer				8.400	0.104	0.000	1.50
2.001	11	60 Winter	100	+30%	100/15 Summer				8.294	0.086	0.000	0.15
1.002	3	480 Winter	100	+30%	100/120 Winter				8.196	0.116	0.000	0.07
3.000	20	15 Winter	100	+30%	100/15 Summer				8.289	0.159	0.000	1.70
3.001	21	480 Winter	100	+30%	100/15 Summer				8.196	0.154	0.000	0.23
1.003	4	480 Winter	100	+30%	100/15 Summer				8.195	0.299	0.000	0.23
4.000	9	15 Winter	100	+30%	30/15 Summer				8.724	0.774	0.000	3.01
4.001	10	15 Winter	100	+30%	30/15 Summer				8.228	0.348	0.000	0.60
1.004	5	480 Winter	100	+30%	30/120 Winter				8.191	0.466	0.000	0.32
5.000	30	480 Winter	100	+30%	100/15 Summer				8.207	0.384	0.000	0.12
5.001	31	480 Winter	100	+30%	30/240 Winter				8.211	0.451	0.000	0.06
5.002	32	480 Winter	100	+30%	30/60 Winter				8.188	0.523	0.000	0.05
1.005	6	480 Winter	100	+30%	30/30 Winter				8.187	0.596	0.000	0.26
6.000	40	480 Winter	100	+30%	30/15 Summer				8.215	0.415	0.000	0.27
6.001	41	480 Winter	100	+30%	30/15 Summer				8.214	0.467	0.000	0.12
6.002	42	480 Winter	100	+30%	30/60 Winter				8.186	0.511	0.000	0.05
7.000	50	480 Winter	100	+30%	30/120 Winter				8.207	0.502	0.000	0.12
7.001	51	480 Winter	100	+30%	30/15 Summer				8.206	0.583	0.000	0.10
1.006	7	480 Winter	100	+30%	30/30 Winter				8.186	0.628	0.000	0.17
8.000	8A	480 Winter	100	+30%	30/30 Winter				8.183	0.643	0.000	0.00
1.007	8	480 Winter	100	+30%	1/15 Summer				8.183	1.000	0.000	0.44

Woods Hardwick		Page 14
15-17 Goldington Road Bedford MK40 3NH	SWS Net 1 17748 Yapton Road Barnham	
Date 07/05/2020 10:20	Designed by C.Smith	
File SWS BARNHAM 31072019 test.MDX	Checked by	
Micro Drainage		Network 2018.1.1

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Overflow (l/s)	Pipe	Status	Level
			Flow (l/s)		Exceeded
1.000	1		16.3	SURCHARGED	
1.001	2		2.4	SURCHARGED	
2.000	10		23.3	FLOOD RISK	
2.001	11		2.4	SURCHARGED	
1.002	3		4.5	SURCHARGED	
3.000	20		71.1	SURCHARGED	
3.001	21		8.5	SURCHARGED	
1.003	4		15.0	SURCHARGED	
4.000	9		45.6	FLOOD RISK	
4.001	10		13.8	SURCHARGED	
1.004	5		20.6	SURCHARGED	
5.000	30		1.8	FLOOD RISK	
5.001	31		1.2	FLOOD RISK	
5.002	32		1.8	FLOOD RISK	
1.005	6		20.9	SURCHARGED	
6.000	40		3.9	FLOOD RISK	
6.001	41		1.9	FLOOD RISK	
6.002	42		3.0	FLOOD RISK	
7.000	50		1.9	FLOOD RISK	
7.001	51		1.4	FLOOD RISK	
1.006	7		24.0	SURCHARGED	
8.000	8A		0.1	FLOOD RISK	
1.007	8		5.0	FLOOD RISK	