




From: Laura Gibbons
Sent: 05 September 2019 11:58
To: Planning.Responses <Planning.Responses@arun.gov.uk>
Cc: Michael Eastham <Michael.Eastham@arun.gov.uk>
Subject: RE: Planning Consultation on: BN/65/19/OUT

Engineers Comments Regarding Surface Water Drainage

There is little space within the proposed layout for surface water drainage. Surface water drainage must be considered at the earliest opportunity. Open features should be provided where possible due to the wider benefits they provide, such as amenity and ecological. Surface water drainage must be considered with the natural topography of the site, land raising or pumping are not sustainable solutions and are not supported by us.

The hierarchy for sustainable drainage must be followed with infiltration fully investigated.

PCENG D2

“Development shall not commence, other than works of site survey and investigation, until full details of the proposed surface water drainage scheme have been submitted to and approved in writing by the Local Planning Authority. The design should follow the hierarchy of preference for different types of surface water drainage disposal systems as set out in Approved Document H of the Building Regulations, and the recommendations of the SuDS Manual produced by CIRIA. Winter groundwater monitoring to establish highest annual ground water levels and winter Percolation testing to BRE 365, or similar approved, will be required to support the design of any Infiltration drainage. No building / No part of the extended building shall be occupied until the complete surface water drainage system serving the property has been implemented in accordance with the agreed details and the details so agreed shall be maintained in good working order in perpetuity.”

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W SP1, W DM1, W DM2 and W DM3 of the Arun Local Plan. This is required to be a pre-commencement condition because it is necessary to implement the surface water drainage system prior to commencing any building works.

And the accompanying informative:

INFORM D

“Infiltration rates for soakage structures are to be based on percolation tests undertaken in the winter period and at the location and depth of the proposed structures. The percolation tests must be carried out in accordance with BRE365, CIRIA R156 or a similar approved method and cater for the 1 in 10 year storm between the invert of the entry pipe to the soakaway, and the base of the structure. It must also have provision to ensure that there is capacity in the system to contain below ground level the 1 in 100 year event plus 40% on stored volumes, as an allowance for climate change. Adequate freeboard must be provided between the base of the soakaway structure and the highest

recorded annual groundwater level identified in that location. Any SuDS or soakaway design must include adequate groundwater monitoring data to determine the highest winter groundwater table in support of the design. The applicant is advised to discuss the extent of groundwater monitoring with the Council's Engineers. Supplementary guidance notes regarding surface water drainage are located here <https://www.arun.gov.uk/surfacewater> on Arun District Councils website. A surface water drainage checklist is available here <https://www.arun.gov.uk/drainagechecklist> on Arun District Councils website, this should be submitted with a Discharge of Conditions Application."

PCENG4

"Development shall not commence until full details of the maintenance and management of the surface water drainage system is set out in a site-specific maintenance manual and submitted to, and approved in writing, by the Local Planning Authority. The manual is to include details of financial management and arrangements for the replacement of major components at the end of the manufacturer's recommended design life. Upon completed construction of the surface water drainage system, the owner or management company shall strictly adhere to and implement the recommendations contained within the manual."

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W DM1, W DM2 and W DM3 of the Arun Local Plan. It is considered necessary for this to be a pre-commencement condition to ensure that the future maintenance and funding arrangements for the surface water disposal scheme are agreed before construction commences.

ENG1

"Immediately following implementation of the approved surface water drainage system and prior to occupation of any part of the development, the developer/applicant shall provide the local planning authority with as-built drawings of the implemented scheme together with a completion report prepared by an independent engineer that confirms that the scheme was built in accordance with the approved drawing/s and is fit for purpose. The scheme shall thereafter be maintained in perpetuity."

Reason : To ensure that the proposed development is satisfactorily drained in accordance with policies W SP1, W DM1, W DM2 and W DM3 of the Arun Local Plan.

Regards,

Laura Gibbons, MEng, GMICE
Engineer (Drainage & Coastal)

Laura Gibbons | Engineer (Drainage & Coastal), Engineering Services, Arun District Council | Location: First Floor, Arun Civic Centre, Maltravers Road, Littlehampton, BN17 5LF

Internal: 37818 | External: +44 (0) 1903 737818 | Fax: +44 (0) 1903 716018 | E-mail: laura.gibbons@arun.gov.uk

Arun is Working in Partnership with Chichester District Council

Visit Arun's web site at <http://www.arun.gov.uk/> and www.chichester.gov.uk



Save the environment - think before you print.

From: planning.responses@arun.gov.uk <planning.responses@arun.gov.uk>

Sent: 22 August 2019 16:51

To: Land Drainage <Land.Drainage@arun.gov.uk>

Subject: Planning Consultation on: BN/65/19/OUT

To: **Engineers (Drainage)**

NOTIFICATION FROM ARUN DISTRICT COUNCIL

Town & Country Planning Act 1990 (as amended)

Town & country Planning (Development Management Procedure) (England) Order 2015 - Article 5

Outline Consent

APPLICATION NO: BN/65/19/OUT

Registered: 22nd August
2019

Site Address: Bexstone House Barnham Road Eastergate PO20 3RT

Grid Reference: 495020 105176

Description of Works: Outline application with some matters reserved for the demolition of existing dwelling & erection of 10 No. new dwellings, widening & reprofiling of site access, provision of a right turn lane with improved visibility splays, retention of significant landscaped highway buffer, parking for 30 No. cars including garages & visitor parking & potential future highway access to adjacent housing land (resubmission following EG/49/18/OUT).

The Council have received the above application. I shall be pleased to receive any observations you may wish to make.

[Click here to view the application details](#)

Should you have any comments to make, these should be sent by replying to this email by 26-SEP-19.

You can also monitor the progress of this application through the Council web site:

www.arun.gov.uk/planning

Please be aware that any comments you may make will be available on our website so please do not insert personal details or signatures on your reply.

In the absence of a reply within the period stated, I shall assume that you have no observations to make.

The application will be determined having regard to the development plan policies (if any are relevant) and other material considerations. The development plan can be accessed via the website as can the leaflet which deals with material planning considerations.

Should the application go to appeal the Planning Inspectorate will publish any comments made to the Council on their website: www.planningportal.gov.uk/planning/appeals/ but they will protect personal details.

The officer dealing with this application is Michael Eastham who can be contacted on telephone number 01903 737772.

Regards
Planning Officer

consultee_email
