


Existing Tree Schedule

Sunnyside,
Yapton Road,
Barnham



Tree No.	Species	Diameter @1.5m	Height (approx.)	Spread (approx.)	Age	Condition/Preliminary Recommendations	Category	Status
T 01	<i>Sambucus nigra</i> (Common Elder); (3.0m Radius of nominal circle; RPA 28m²)	245 mm CSD	4.0 m Clear Stem Height 0.5 m	N: 2.0 m E: 0.5 m S: 1.5 m W: 1.5 m	Early Mature Estimated Remaining Contribution 10 + Years	Scrubby multistem tree pruned away from the gate.	C 1	Retain
TL 02	<i>Cupressus x leylandii</i> (Leyland Cypress); (1.8m Radius of nominal circle; RPA 10m²)	150 mm Average	3.5 m Clear Stem Height 0.5 m	N: 1.0 m E: 1.0 m S: 1.0 m W: 1.0 m	Semi-Mature Estimated Remaining Contribution 10 + Years	Short line of trees with lower growth mostly dead.	C 1	Retain
T 03	<i>Prunus sp.</i> (Cherry sp.); (3.6m Radius of nominal circle; RPA 41m²)	286 mm	5.0 m Clear Stem Height 1.5 m	N: 4.5 m E: 4.0 m S: 2.5 m W: 4.5 m	Early Mature Estimated Remaining Contribution <10 Years	Multistem of scrubby form, signs of historic pruning with a dense vigorous crown.	C 1	Retain
H 04	<i>Ligustrum ovalifolium</i> (Garden Privet); (1.2m Radius of nominal circle; RPA 5m²)	100 mm Average	4.0 m Clear Stem Height 0.0 m	As Shown	Early Mature Estimated Remaining Contribution 10 + Years	A dense screening hedge, which has been heavily pruned.	C 2	Retain

Tree No.	Species	Diameter @1.5m	Height (approx.)	Spread (approx.)	Age	Condition/Preliminary Recommendations	Category	Status
TG 05	<i>Populus tremula</i> (Aspen) (5.4m Radius of nominal circle; RPA 92m²)	450 mm	12.0 m Clear Stem Height 0.0 m	N: 12.0 m E: 8.0 m S: 2.0 m W: 2.0 m	Over-Mature Estimated Remaining Contribution <10 Years	Two trees which have fallen into site from the adjacent property. The smaller has failed whilst the larger has regrown a broad crown. The trees are crushing a small holm oak.	U	Retain
T 06	<i>Picea sp.</i> (Spruce sp.); (3.6m Radius of nominal circle; RPA 41m²)	290 mm	10.0 m Clear Stem Height 3.0 m	N: 3.0 m E: 3.0 m S: 3.0 m W: 3.0 m	Semi-Mature Estimated Remaining Contribution 10 + Years	A tree of fair form but lot vigour with lots of twiggy dieback.	C 1	Retain
T 07	<i>Acer platanoides</i> (Norway Maple); (5.4m Radius of nominal circle; RPA 92m²)	450 mm	12.0 m Clear Stem Height 3.0 m	N: 4.5 m E: 4.5 m S: 4.5 m W: 4.5 m	Early Mature Estimated Remaining Contribution 20 + Years	Off-site tree, c.5.0 m off-site. Good form.	B 2	Retain
T 08	<i>Acer pseudoplatanus</i> (Sycamore); (3.6m Radius of nominal circle; RPA 41m²)	290 mm	11.0 m Clear Stem Height 2.0 m	N: 3.5 m E: 4.0 m S: 4.0 m W: 3.5 m	Semi-Mature Estimated Remaining Contribution 10 + Years	Offsite tree of fair form, growing on a mound of spoil.	C 1	Retain

Tree No.	Species	Diameter @1.5m	Height (approx.)	Spread (approx.)	Age	Condition/Preliminary Recommendations	Category	Status
T 09	<i>Populus tremula</i> (Aspen) (4.2m Radius of nominal circle; RPA 55m²)	344 mm	13.0 m Clear Stem Height 3.0 m	N: 6.0 m E: 6.5 m S: 5.5 m W: 3.0 m	Early Mature Estimated Remaining Contribution 10 + Years	The stem starts off-site and grows east into the site and then upwards. Tree is of indifferent form.	C 1	Retain
T 10	#N/A ; (4.2m Radius of nominal circle; RPA 55m²)	350 mm	11.0 m Clear Stem Height 1.5 m	N: 6.0 m E: 6.0 m S: 6.0 m W: 4.0 m	Semi-Mature Estimated Remaining Contribution 10 + Years	Offsite tree of indifferent form whose crown divides at 1.0m. Heavy ivy noted.	C 2	Retain
T 11	<i>Populus sp.</i> (Poplar sp.); (15m Radius of nominal circle; RPA 707m²)	1500 mm	25.0 m Clear Stem Height 4.0 m	N: 12.0 m E: 12.5 m S: 11.0 m W: 11.0 m	Mature Estimated Remaining Contribution 20 + Years	Behind a chainlink fence. Divides to 7 stems at 4.0 m height. Moderate ivy and mistletoe noted. 1 major failure noted.	B 2	Retain
T 12	<i>Prunus sp.</i> (Cherry sp.); (3.6m Radius of nominal circle; RPA 41m²)	280 mm CSD	4.5 m Clear Stem Height 0.0 m	N: 3.0 m E: 2.5 m S: 2.5 m W: 3.0 m	Semi-Mature Estimated Remaining Contribution 10 + Years	Multistem with a poor main union, but good vigour.	C 1	Retain

Tree No.	Species	Diameter @1.5m	Height (approx.)	Spread (approx.)	Age	Condition/Preliminary Recommendations	Category	Status
T 13	<i>Populus sp.</i> (Poplar sp.) (9m Radius of nominal circle; RPA 255m²)	750 mm	24.0 m Clear Stem Height 3.0 m	N: 10.0 m E: 10.0 m S: 10.0 m W: 10.0 m	Mature Estimated Remaining Contribution 20 + Years	Well off-site, good form, some pruning noted to the north. Heavy ivy noted.	B 2	Retain
SH 14	Hedgerows and Shrubs; (1.2m Radius of nominal circle; RPA 5m²)	100 mm 100 mm	8.0 m Clear Stem Height 0.0 m	As Shown	Semi-Mature Estimated Remaining Contribution 10 + Years	Line of scrub or untended hedge, with dead elms present. Good habitat.	C C 2/3	Retain
T 15	<i>Populus sp.</i> (Poplar sp.); (7.2m Radius of nominal circle; RPA 163m²)	600 mm	25.0 m Clear Stem Height 5.0 m	N: 9.0 m E: 9.0 m S: 9.0 m W: 9.0 m	Mature Estimated Remaining Contribution 40 + Years	Offsite tree of good form and condition.	A 1/2	Retain
T 16	<i>Populus sp.</i> (Poplar sp.); (8.4m Radius of nominal circle; RPA 222m²)	700 mm	25.0 m Clear Stem Height 5.0 m	N: 9.0 m E: 9.0 m S: 9.0 m W: 9.0 m	Mature Estimated Remaining Contribution 40 + Years	Offsite tree of good form and condition. Divides to twin stems at 7.0m.	A 1/2	Retain

Tree No.	Species	Diameter @1.5m	Height (approx.)	Spread (approx.)	Age	Condition/Preliminary Recommendations	Category	Status
SH 17	Hedgerows and Shrubs (3.6m Radius of nominal circle; RPA 41m²)	300 mm Average	8.0 m Clear Stem Height 0.0 m	As Shown	Semi-Mature Estimated Remaining Contribution 10 + Years	Line of scrub or untended hedge, with dead elms present and hazels leaning into the site. Good habitat.	C 2/3	Retain
TG 18	<i>Populus sp.</i> (Poplar sp.); (3.6m Radius of nominal circle; RPA 41m²)	300 mm Average	18.0 m Clear Stem Height 5.0 m	N: 4.0 m E: 4.0 m S: 4.0 m W: 4.0 m	Semi-Mature Estimated Remaining Contribution 10 + Years	Trees approximately 1.0 m offsite, the southernmost leans heavily north.	C 2	Retain
H 19	Hedgerows and Shrubs; (2.4m Radius of nominal circle; RPA 18m²)	200 mm Average	8.0 m Clear Stem Height 0.0 m	As Shown	Early Mature Estimated Remaining Contribution 10 + Years	A gappy line of scrubby willows and shrubs with some trees of better form. Species include sycamore, willow, beech, goat willow, escallonia, hawthorn, hazel, spruce.	C 2	Retain
T 20	<i>Salix sp.</i> (Willow sp.); (5.1m Radius of nominal circle; RPA 81m²)	424 mm CSD	8.0 m Clear Stem Height 2.0 m	N: 5.0 m E: 5.0 m S: 5.0 m W: 5.0 m	Semi-Mature Estimated Remaining Contribution 10 + Years	A multistem hedge tree.	C 2	Retain

Tree No.	Species	Diameter @1.5m	Height (approx.)	Spread (approx.)	Age	Condition/Preliminary Recommendations	Category	Status
TG 21	<i>Quercus robur</i> (Pedunculate Oak) (3.3m Radius of nominal circle; RPA 34m²)	270 mm	11.0 m Clear Stem Height 3.0 m	N: 4.0 m E: 4.0 m S: 3.0 m W: 4.0 m	Semi-Mature Estimated Remaining Contribution 20 + Years	Trees of fair form, growing in the hedge.	B 1	Retain
TG 22	<i>Salix sp.</i> (Willow sp.); (4.8m Radius of nominal circle; RPA 72m²)	400 mm	10.0 m Clear Stem Height 1.0 m	N: 4.0 m E: 5.0 m S: 4.5 m W: 5.0 m	Early Mature Estimated Remaining Contribution 20 + Years	Older hedge trees, of fair form with pruning/flail damage noted to the west.	B 2/3	Retain
H 23	Hedgerows and Shrubs; (3.3m Radius of nominal circle; RPA 34m²)	275 mm Average	10.0 m Clear Stem Height 0.0 m	As Shown	Early Mature Estimated Remaining Contribution 10 + Years	A gappy line of scrubby willows and shrubs with some trees of better form. Species include sycamore, willow, beech, goat willow, escallonia, hawthorn, hazel, spruce.	C 2	Retain
T 24	<i>Tilia sp.</i> (Lime sp.); (6.0m Radius of nominal circle; RPA 113m²)	492 mm	14.0 m Clear Stem Height 4.0 m	N: 5.0 m E: 6.0 m S: 6.0 m W: 6.0 m	Early Mature Estimated Remaining Contribution 20 + Years	Growing on the hedgeline, divides to 3 stems from the base. Very narrow unions and included fence wire.	B 2	Retain

Tree No.	Species	Diameter @1.5m	Height (approx.)	Spread (approx.)	Age	Condition/Preliminary Recommendations	Category	Status
TG 25	Hedgerows and Shrubs (2.4m Radius of nominal circle; RPA 18m²)	200 mm	9.0 m Clear Stem Height 0.0 m	As Shown	Semi-Mature Estimated Remaining Contribution 10 + Years	A sparse, relict line of hedge specimens and self-seeded trees growing on the fence.	C 2	Retain
TL26	<i>Cupressus</i> sp. (Cypress sp.); (3.6m Radius of nominal circle; RPA 41m²)	285 mm	8.0 m Clear Stem Height 0.0 m	As Shown	Semi-Mature Estimated Remaining Contribution 10 + Years	Line of garden screening trees, previously topped. Vigorous but sprawling.	C 1	Retain
H 27	Hedgerows and Shrubs; (2.4m Radius of nominal circle; RPA 18m²)	200 mm Average	6.0 m Clear Stem Height 0.0 m	As Shown	Semi-Mature Estimated Remaining Contribution 10 + Years	Old hedge remnants with interspersed ornamental shrubs.	C 2	Retain
T 28	<i>Salix</i> sp. (Willow sp.); (5.7m Radius of nominal circle; RPA 102m²)	458 mm CSD	16.0 m Clear Stem Height 4.0 m	N: 9.0 m E: 9.0 m S: 10.0 m W: 8.0 m	Mature Estimated Remaining Contribution 10 + Years	Multistem at 1.0 m, inspection limited but the union appears congested. Moderate ivy and an arching crown are noted.	C 3	Retain

Tree No.	Species	Diameter @1.5m	Height (approx.)	Spread (approx.)	Age	Condition/Preliminary Recommendations	Category	Status
T 29	<i>Betula pendula</i> (Silver Birch) (3.6m Radius of nominal circle; RPA 41m²)	300 mm	16.0 m Clear Stem Height 6.0 m	N: 4.0 m E: 5.0 m S: 4.0 m W: 3.0 m	Semi-Mature Estimated Remaining Contribution 20 + Years	In adjacent garden. Leans north, moderate ivy cover, fair form.	B 1	Retain
H 30	Mixed Species Native Hedgerow; (1.8m Radius of nominal circle; RPA 10m²)	150 mm Average	2.0 m Clear Stem Height 0.0 m	As Shown	Early Mature Estimated Remaining Contribution 20 + Years	A dense, continuous hedge, mostly hazel. Tightly pruned.	B 2	Retain
H 31	Ornamental Shrubs; (1.2m Radius of nominal circle; RPA 5m²)	100 mm	4.0 m Clear Stem Height 0.0 m	As Shown	Semi-Mature Estimated Remaining Contribution 0	Screening hedge of limited other value.	C 2	Retain
T 32	<i>Acer pseudoplatanus</i> (Sycamore); (10.8m Radius of nominal circle; RPA 366m²)	897 mm CSD	19.0 m Clear Stem Height 4.0 m	N: 7.5 m E: 7.5 m S: 7.5 m W: 8.0 m	Mature Estimated Remaining Contribution 20 + Years	Divides to 6no. Stems between 1-2m. All unions appear narrow with multiple areas of bark inclusion noted. The stems are vertical holding an even crown with minor deadwood.	B 2	Retain

Tree No.	Species	Diameter @1.5m	Height (approx.)	Spread (approx.)	Age	Condition/Preliminary Recommendations	Category	Status
H 33	<i>Chamaecyparis lawsoniana</i> (Lawson's Cypress) (1.8m Radius of nominal circle; RPA 10m²)	150 mm Average	4.0 m Clear Stem Height 0.0 m	As Shown	Semi-Mature Estimated Remaining Contribution 10 + Years	Screening hedges of limited value.	C 2	Retain
TL 34	<i>Cupressus x leylandii</i> (Leyland Cypress); (4.5m Radius of nominal circle; RPA 64m²)	366 mm Average	11.0 m Clear Stem Height 2.0 m	As Shown	Semi-Mature Estimated Remaining Contribution 10 + Years	Remnant of a screening hedge, of limited value.	C 2	Retain
T 35	<i>Sambucus nigra</i> (Common Elder); (3.6m Radius of nominal circle; RPA 41m²)	280 mm CSD	5.5 m Clear Stem Height 2.0 m	N: 3.0 m E: 3.0 m S: 3.0 m W: 3.0 m	Early Mature Estimated Remaining Contribution 20 + Years	Tree originally part of hedge. Multistemmed and of even dense form.	B 1	Retain
TL 36	<i>Acer pseudoplatanus</i> (Sycamore); (3.6m Radius of nominal circle; RPA 41m²)	300 mm Average	15.0 m Clear Stem Height 2.0 m	N: 4.0 m E: 4.0 m S: 4.0 m W: 3.0 m	Semi-Mature Estimated Remaining Contribution 10 + Years	Boundary trees, generally even and slender but of limited value. Appear to be off-site.	C 2	Retain

Tree No.	Species	Diameter @1.5m	Height (approx.)	Spread (approx.)	Age	Condition/Preliminary Recommendations	Category	Status
T 37	<i>Aesculus hippocastanum</i> (Horse Chestnut) (6.0m Radius of nominal circle; RPA 113m²)	500 mm	13.0 m Clear Stem Height 3.0 m	N: 5.0 m E: 3.0 m S: 5.0 m W: 6.0 m	Semi-Mature Estimated Remaining Contribution 20 + Years	Growing on the boundary, inspection limited but appears of fair form.	B 2	Retain
T 38	<i>Quercus ilex</i> (Holm Oak); (5.1m Radius of nominal circle; RPA 81m²)	423 mm	12.0 m Clear Stem Height 0.0 m	N: 6.0 m E: 6.0 m S: 7.0 m W: 6.0 m	Early Mature Estimated Remaining Contribution 20 + Years	Fair form, divides low on the stem. In hedge.	B 2	Retain
T 39	<i>Quercus ilex</i> (Holm Oak); (3.0m Radius of nominal circle; RPA 28m²)	245 mm	10.0 m Clear Stem Height 0.0 m	N: 3.0 m E: 4.0 m S: 3.0 m W: 4.0 m	Semi-Mature Estimated Remaining Contribution 20 + Years	Leans heavily into site, adds little.	C 2	Retain