

© Crown Rep. All rights reserved. RPS Group license number 010033993



ADOPTABLE SEWERS NOTES/KEY

- Foul Manhole/Access Chamber and sewer/lateral
- Storm Manhole/Access Chamber and sewer/lateral
- Highway Road Gully
- Type 3 Inspection Chamber
- Type 4 Inspection Chamber

PRIVATE SEWERS NOTES/KEY

- FOUL
- STORM
- Sewer/pipe
- Type 3 Inspection Chamber
- Type 4 Inspection Chamber
- Storm Manhole/Access Chamber
- △ Rodding Eye
- ▽ Yard Gully
- Aco Linear Drainage Channel

ANCILLARY NOTES/KEY

- Outfall Location and Level
- Cellular Storage Cassettes (CSC) - Aquacell or similar
- Control Chamber - Garastor or similar
- CS1 Channel blocks

- NOTES
1. Do not scale.
 2. The contractor is to check and verify all buildings and site dimensions and levels, including sewer invert levels, before works start on site. The contractor is to comply in all aspects with the current building legislation, British Standards, building regulations etc.
 3. Positions of existing services/statutory undertakers apparatus adjacent to or crossing proposed excavations are to be checked by the contractor prior to starting work.
 4. This drawing is to be read in conjunction with and checked against all other drawings, Engineering details, Specification and any structural, Geotechnical or other specialist document provided.
 5. Any anomaly or contradiction between any of the above is to be reported to the Engineer.
 6. This drawing is schematic for clarity only, positions of pipe runs and manholes may vary on site due to site conditions.
 7. All concrete within ground to be AC-1 with design sulphate class of DS-1.
 8. Expect Site CBR values of 2%.

- CONSTRUCTION NOTES.
1. All sewers within roads or public areas are to comply with the requirements of the Water Authorities publication "Sewers for Adoption, 7th Edition" together with any addendums and amendments.
 2. Positions of all existing sewers to be established before construction commences and details reported to ENGINEERS.
 3. Invert levels of existing manholes and sewers are to be checked on site before construction commences and results reported to ENGINEERS.
 4. All manhole covers to comply with BS EN 124 or BS497 Equivalent, and be kitemarked. Covers to suit loading as below;
 - Carriageways and Roads - D400
 - Driveways and Verges - C250
 - Footways and Pedestrian Areas - B125
 5. All bedding shall be Class S unless noted otherwise.
 6. All trenches under existing and proposed public highways are to be backfilled with thoroughly compacted DOT Type 1 sub-base material.
 7. Concrete bed and surround (Type Z) is required to pipes laid in areas where depth of cover is less than:
 - 0.35m Domestic gardens and pathways without any possibility of vehicular access
 - 0.5m Domestic driveways, parking areas with height restriction to prevent vehicle entry in excess of 7.5t
 - 0.8m Domestic driveways, parking areas with limited access for vehicle entry in excess of 7.5t
 - 0.9m Agricultural land and public open space
 - 1.2m Highways and parking areas with unrestricted access to vehicles in excess of 7.5t
 8. The use of precast concrete products made with sulphate resisting cement is mandatory. Unless a laboratory report proves such precautions are not required.
 9. Refer also to Public Sewer Construction Details and Manhole Schedules.

ROAD AND SEWER ADOPTION NOTES.

1. All works for adoption under a Section 38 agreement shall be carried out to West Sussex County Council Specification and to the approval of the Area Highway Inspector.
2. All works for adoption under a Section 104 agreement shall be carried out to the National Water Council guide "Sewers for Adoption" 7th edition and Southern Waters requirements.

P	S71, S3, S6, F9, F10, F11 changed to private	21/01/2013	BA	SL
N	Drainage xref updated (discharge flow rate)	10/12/2013	BA	BA
M	Drainage xref updated (discharge flow rate)	24/10/2013	SL	BA
L	Site layout updated	14/10/2013	BA	SM
K	Site layout updated (amendments to facilities)	10/09/2013	BA	SM
J	F7, F8, F9, F10, F11, F24, S25, S31 & S38 amended. S31A added.	13/09/2013	BA	LA
H	Site layout & Engineering updated following comments from WSCC and Southern Water	11/07/2013	BA	SL
G	Site layout & Engineering updated following substructure revisions	20/05/2013	BA	SL
F	S97, S104, S110, S250, F44 levels amended	21/05/2013	BA	SL
E	Plots 125 & 126-133 relocated. Engineering updated to suit.	20/04/2013	LPA	LPA
D	Permeable paving removed, replaced with cellular storage	24/03/2013	BA	SL
C	Drainage updated	20/02/2013	BA	LPA
B	Private drainage amended	09/02/2013	BA	LPA
A	Plan & Key amended to match Site 1	01/09/2012	BA	LPA
Rev	Description	Date	Initial	Checked

20 Milton Park
Abingdon, Oxfordshire, OX14 4SH.
T: +44(0)1235 432 190 E: transport@rpsgroup.com F: +44(0)1235 834 898

N

Client

Bellway

Project

Former Bognor Community College,
Bognor Regis

Title

Site 2
Drainage Plan (Sheet 2 of 2)

Status	Drawn By	Checked by
APPROVED	BA	AD
Project Number	Scale @ A1	Date Created
JNY7768	1:250	21.11.12

Drawing Number	Rev
JNY7768-S2-501	P

© 2012 RPS Group

rpsgroup.com