

Capacity	58.87		kW
Air On Temp. db / wb	32.0 / ~		°C
Ambient R.H.	~		%
Refrigerant	R407F – Dew Point		
Inlet Temperature	43.0		°C
Inlet Connection Size	2 set(s) 42mm		
Outlet Connection Size	2 set(s) 35mm		
Air Volume	7.58		m³/s
Tube Material	Cu (R)		
Fin Material	Alup		
Case Material	Galv		
Coil Volume	70.4		litres
Fin Spacing	4 rows @ 2.1mm		
Total Surface Area	814		m²
Fan Type	EC Variable		
No. Fan(s)	4 (2 x 2)		
Fan Diameter	800		mm
Fan Speed	388 Day (800 Max) 225 Night (800 Max)		rpm
Electrical Supply	1 x 240V - 50Hz		
Noise Level to ISO1680	25 dBa at 10m Day 13 dBa at 10m Night		
Unit Orientation	Horizontal		
Overall Length	2740		mm
Overall Width	2400		mm
Overall Height	1426		mm
Dry Weight	539		kg
Features	EC Fans Isolators per motor 800mm legs EC Common junction box using pack controller		
Not included	Off loading		
Options	Out of hours delivery	£300.00	