


 CONCRETE Blocks 100mm

 100mm cavity

 ThermaLite Blocks 100mm

 450mm wide footing. proposed depth 600mm

 Floor makeup MOT/Blinding sand/DPM/

 200mm X 50mm Floor joists/allowing 150mm beneath/

Notes

Floor DPM to lap up to damp course.

DPM will be sat on blinding sand which will be on 50mm of MOT. Allowing 150mm void from bottom of floor Joists, which will be of 200mm X 50mm.

floor Joists will be protected where needed by a DPC. spaced out at 400mm centers and nogged out where needed.

Air bricks will be used to vent beneath floor.

