



LONGAR® Type 3

Low Pressure Baffle Filter



*Stainless steel 240 grit finish - standard handles



*Stainless steel bright annealed finish - optional fixed high temp handles

LONGAR® TYPE 3 FEATURES:

- Low pressure loss
- Polished finish or 240 grit dull grain finish
- Fully welded construction – all stainless steel construction
- Robust construction, our strongest filter yet
- Folding handles and drain holes standard (optional rigid handle available)
- Meets HVCA DW172 requirements
- Stock Sizes 2-3 days delivery, custom sizes available
- Cutsafe safety edges

APPLICATIONS

- Commercial Kitchens
- Water mist separation
- Spark arrestors
- Sand filtration

LONGAR® TYPE 3 BAFFLE FILTER

For use in commercial kitchens and ventilation to extract grease laden air and offer a barrier to flame. The Type 3 has been developed for customers that require a lower pressure baffle filter, it still holds many of the features of the premium Type 2 yet offer a lower resistance to air. The Type 3 is available in standard depths of 20mm and 45mm. Custom sizes available on request. Meets DW172 and ISO9001.

CONSTRUCTION / MATERIAL SPECIFICATION

As standard all baffles are manufactured with Stainless Steel 430 polished finish and 240 Grit Dull Grain Finish. Maximum Operating temperature 400C or 750F.

FITTING INSTRUCTIONS

- Fit products, handles in direction of air in.
- Product vertical in air stream.

HANDLING

- Handle with care when unpacking.
- Store in dry and frost protected place.

MAINTENANCE

- All maintenance should be carried out in accordance with the planned maintenance set by installation contractor.
- When handling any components suitable PPE should be used - gloves & eye protection and access equipment.
- Filters should be cleaned by a trained operative either daily for heavy use or weekly for light use.
- For more exact guide to cleaning you should contact a cleaning specialist.

PACKAGING

All units are packaged in double wall boxes with separators for standard sizes, glued closed for protection whilst in transit against contamination.

FILTER CLASSIFICATION:

- Filter Class G2.
- UL Class 2.

MANUFACTURED TO:

- DW172.
- ISO9001.

For technical specifications, part numbers and ordering information, please see overleaf.

LONGAR® Type 3

Low Pressure Baffle Filter

TECHNICAL SPECIFICATIONS

Longar specifies the baffle filter as height x width x thickness. The handles are fixed to the height and drain holes punched on the width. The length of the baffle blade is the height; please ensure correct orientation is given when ordering.

SIZE ORDERING GUIDE (TOLERANCES +/- 2mm)			
Part Number	Actual Size HxWxD	Nominal Size HxWxD	Weight
TYPE3ST10X20	243 x 496 x 45mm	254 x 508 x 50mm	1.47kgs
	9.57 x 19.53 x 1.77"	10 x 20 x 2"	3.23lbs
TYPE3ST12X20	295 x 496 x 45mm	304 x 508 x 50mm	1.79kgs
	11.61 x 19.53 x 1.77"	12 x 20 x 2"	3.94lbs
TYPE3ST16X16	395 x 395 x 45mm	406 x 406 x 50mm	1.90kgs
	15.55 x 15.55 x 1.77"	16 x 16 x 2"	4.18lbs
TYPE3ST16X20	395 x 496 x 45mm	406 x 508 x 50mm	2.39kgs
	15.55 x 19.53 x 1.77"	16 x 20 x 2"	5.26lbs
TYPE3ST18X18	444 x 444 x 45mm	457 x 457 x 50mm	2.42kgs
	17.48 x 17.48 x 1.77"	18 x 18 x 2"	5.32kgs
TYPE3ST20X16	496 x 395 x 45mm	508 x 406 x 50mm	2.39kgs
	19.53 x 15.55 x 1.77"	20 x 16 x 2"	5.26lbs
TYPE3ST20X20	496 x 496 x 45mm	508 x 508 x 50mm	2.87kgs
	19.53 x 19.53 x 1.77"	20 x 20 x 2"	6.31lbs
TYPE3ST24X24	597 x 597 x 45mm	609 x 609 x 50mm	4.35kgs
	23.50 x 23.50 x 1.77"	24 x 24 x 2"	9.57lbs
FINAL RECOMMENDED PRESSURE DROP: 400 PASCALS			




LONGAR INDUSTRIES


FILTERS AND FABRICATIONS FOR A CLEANER ENVIRONMENT

Longar Industries Limited, Unit 25, Glenmore Business Park, Colebrook Way, Weyhill Lane, Andover, Hampshire SP10 3GZ United Kingdom

LONGAR® Type 3 - Low PD - Baffle Filter - 243x495x45mm




LONGAR® Type 3 - Low PD - Baffle Filter - 395x395x45mm




LONGAR INDUSTRIES

FILTERS AND FABRICATIONS FOR A CLEANER ENVIRONMENT

LONGAR® Type 3 - Low PD - Baffle Filter - 395x496x45mm




LONGAR® Type 3 - Low PD - Baffle Filters - 444x444x45mm




LONGAR INDUSTRIES

FILTERS AND FABRICATIONS FOR A CLEANER ENVIRONMENT

LONGAR® Type 3 - Low PD - Baffle Filters - 496x496x45mm



LONGAR® Type 3 - Low PD - Baffle Filters - 597x597x45mm



LONGAR INDUSTRIES

FILTERS AND FABRICATIONS FOR A CLEANER ENVIRONMENT

Longar Industries Limited, Unit 25, Glenmore Business Park, Colebrook Way, Weyhill Road, Andover, Hampshire SP10 3GZ United Kingdom