

DOE BR/252/17/L

SZ 9398 NW 7/68 Grade II

Norfolk Hotel Aldwick Road

Probably 1840s, extended subsequently. An imposing elongated facade, set back diagonally to the corner with West Street. 3 storeys. Stuccoed. 17 windows (extended from 7 after 1898). Drafted ground floor and drafted pilasters between windows, which have sashes without glazing bars. 1st floor windows have pediments on brackets (the middle 3 segmental). A stringcourse connects the cills of 2nd floor windows. Free-standing royal arms with supportors in centre, over low parapet. The cornice supported on elongated brackets, rhythmically spaced. Balcony to 7 centre bays, on iron columns and with delicate iron railings. projecting porch, glazed, with columns. Irregular rear.