



Flush Sash Pegstay Casement specification

Description

The Flush Sash Pegstay Casement can be manufactured in unlimited styles and designs. Locking is provided by means of casement stays & fasteners.

DGU's

The Energy Efficient DGU's are made with the following products:

4mm Saint Gobain Diamant (external)
4mm Saint Gobain Planitherm Total + (internal)
16mm Saint Gobain Swiss Spacer V warm edge spacer bar
MATCHING Saint Gobain Swiss Spacer V integral duplex (positioned behind the astragal bars to give the impression of separate DGU's)
Argon filled DGU's

Draught Proofing

Fully draught proofed using Schlegel Aquamac 21

Hardware

Hardware is solid brass which is also offered chrome plated

Paint

The paint system we use is a 3 coat – spray applied microporous semi-gloss finish
