


KEY



Rev. -A-	4.10.2019	Planning changes	BRC
Project:	3 Southdown Road		
Drawing Title:	Landscape Proposals & Planting Plan		
Purpose:	Planning		
Dwg. No.	1022-5300	Tudor Homes (Sussex) Ltd.	
Scale:	1:100 @ A1	Date:	20-May-2017

Specification: Landscape Implementation Guidelines.

The planting and landscaping for the whole site shall be carried out prior to occupation of the building or during the first planting season following the full completion of building works, whichever is sooner.

All planting and landscape operations should comply with the requirements specified in BS 3936 (1992) Nursery Stock Part One, BS 4428 (1989) Code of Practice for General Landscape Operations (excluding hard surfaces) and BS8545 Trees from nursery to independence in the landscape.

Any plant species shown on the approved landscape scheme which within a period of 5 years from the completion of the development (as is removed or in the opinion of the LPA becomes seriously damaged or diseased shall be replaced in the same place in the next planting season with identical species unless the LPA gives written consent to any variation).

Proposed Tree Planting:

Garden tree to be supported using softwood stakes @ 5cm diameter @ 180cm length and should be driven into the ground to knee-height with ties and horizontal cross support.

Tree pit size to conform to BS8545 'Trees from Nursery to Independence in the Landscape' dug to adequately accommodate root ball.

Proposed Shrub Planting:

Shrubsheding to be planted in 450mm depth planting beds, smaller shrubs 400mm depth or to easily accommodate pot depth, comprising minimum of 150mm topsoil, 250mm clean subsoil, plus 20-75mm organic compost mulch, adjust as necessary. Ensure circular area around trees and specimen shrubs in lawns to be mulched.

NB Cultivation of plant beds beneath tree canopy to be carefully dug by hand with soil amelioration carried out that does not raise soil levels over existing

Proposed Seeding / Turfing

Seeds and turfing to be laid out in the first available seeding / turfing season following the occupation of the building or the completion of the development (whichever is sooner) in a minimum 150mm depth of clean topsoil.

Additional Notes:

Allow for removal and maintenance including watering of plant stock to be used as part of new scheme.

Planting Proposals - Vision

The planting scheme aims to provide additional planted enhancements to what is already an attractive setting for the proposed dwellings. At the front there is an existing Tulip tree which is located to the north of Plot 2, some shrub planting to the site and front of the dwellings have been selected to flower in shelter conditions. Small shrub beds at the side of the driveway and in the rear gardens contain fragrant, drought resistant planting with long flowering seasons and interesting mostly evergreen foliage and attractive seed heads.

Trees to be Relocated and Protected

All fruit trees to be retained (see above). The Tulip tree (T1) is to be retained and protected during the construction phase of the project in accordance with BS5837:2012. As the RPA of this tree is in a large proportion of the parking area to the front of the houses, it is proposed that a gravel filled grid system of surfacing is used as a permanent permeable drainage system for the parking area. All other trees on site are to be retained with works carried out prior to occupation of site in accordance with BS3936:2010 with some crown lifting and thinning of the canopy of the Tulip tree to be carried out by a qualified arboriculturalist.

Existing Trees to be Relocated and Protected

There are 2 angle trees and one pear tree planted against the wall in plot 1 which may once have been espaliered, these trees could revert to this with careful work carried out by an experienced gardener / arborist. A new shrub bed to be formed alongside the wall and trellis wires introduced for support. A young apple tree in Plot 2 can be relocated to the boundary between the ornamental cherry and the house in Plot 2. Other shrubs associated with the ornamental Acer to be relocated elsewhere around the gardens.

The only tree to be felled in the ornamental Acer that is unfortunately in conflict with Plot 2

Tree Protection Method

See drawing No. 1022 - 5400 Tree Protection Plan

PLANT SCHEDULE

Species

Specification and Pot Size.

No.

Tree Planting:

Amelanchier lamarckii
Robin Hill

14-16cm girth semi-mature, 3-3.5m height, RB or CG

Fruit Tree:

Apple - 'Braeburn'

Shrub planting:

Abelia xgrandiflora

Cistus xpurpureus

Cytisus praecox 'Albigot'

Cytisus praecox 'Lena' or 'Goldfinch' (orange/red)

Euonymus fortunei

Emerald 'Gold'

Hypericum xindorum

Lonicera nitida

Baggesens 'Gold'

Pittosporum 'Tom Thumb'

Potentilla 'Red Robin'

Ribes sanguineum

Skimmia japonica

Rubus

Herbaceous:

Achillea mollis

Bergenia cordifolia

Geranium macrorrhizum

Heuchera 'Palace Purple'

Liriope muscari

Climbers:

Vitis vinifera 'Purpurea'

As shown

1

MATERIALS SPECIFICATION

Driveway to be surfaced with DekoGrip resin bound materials in col. Haybale from Parking court to be surfaced with Golph gravel retention system (640x330x38mm) with gravel infill. 6-10mm angular (to depth of 38mm) laid over 25mm depth sharp sand, and Cellweb 75-200mm (depth to be confirmed) Cellweb base, using clean angular stone Type 4 / 20 www.geosyn.co.uk

Cellweb In Root Protection Area of Tulip Tree - in accordance with BS5837:2012



Standard BS 400mmx400mm flag paving in col. beige.

Turnbiled block such as Marshalls 'Treglar' 100x200 to be laid to edges of driveway in double row

Protective Edge to stem of tulip tree to prevent conflict with reversing vehicles: semi-circular form comprising upended railway sleepers (200x100mm bannised softwood sleepers) cut to 400mm lengths and fixed into ground using 2 no. ss pins, inserted into Cellweb to a min. depth of 200mm-sleepers to be placed 350-400mm apart in semi-circular formation.

Close boarded fencing to 1500mm ht. with 300mm trellis tops with permeable gravel boards to allow free movement of small mammals and birds.

Trellis wires 'Gripole Support System' from Harrod International www.harrodhorticulture.com to support espaliered fruit trees and climbers along wall to boundary of Plot 1



Acc Raindrain domestic channel connected to soakway beneath parking area

Existing fence panels to be replaced with new close boarded fencing 1.8m ht. Permeable gravel boards

Marshalls Standard Concrete block paving col. Buff 200x100x50mm

Boundary wall to remain

Marshalls Standard Concrete block paving col. Buff 3x rows of 200x100x50mm to edges

Permeable block paved disabled access (over cellweb)

Shrub planting: 3 of each of following species planted randomly in groups of 3 - 4 ensure shrubs are planted at equal distances across the bed

Skimmia japonica 'Rubella'

Euonymus fortunei 'Emerald and Gold'

Cytisus 'Lena' or 'Goldfinch'

Potentilla 'Red Robin'

Layer of mulch beneath tree, largely retained by upended 200x100x400mm ht. railway sleepers placed 250mm apart upended and fixed with 2 no. pins carefully driven between roots

Shrub planting: 7 of each of following species planted randomly in groups of 3 - 4 ensure shrubs are planted at equal distances across the bed and retained by railway sleeper

Skimmia japonica 'Rubella'

Ribes sanguineum 'Brookelbanki'

Euonymus fortunei 'Emerald and Gold'

Cytisus 'Lena' or 'Goldfinch' (red/yellow)

Potentilla 'Red Robin'

Surfacing of parking court to be 'Golpa' gravel retention system over Cellweb base see Dwg. 1022-5300

5 No. plants: 2 No. Lonicera nitida 'Baggesens Gold' (Ln) 2 No. Pittosporum 'Tom Thumb' (PTT) 3 No. Bergenia cordifolia

Plant 1 of each shrub to either side of window and plant 3 Bergenia beneath

Access path to both plots - with 1200mm ht.gate timber palisade gate

Relocate shrubs to garden boundaries

Pavlos 3 x 2.4m using Standard BS paving 400x400mm Single patls edged with row of block pavers

Existing close boarded fence - retained

Plant border with plants saved and stored from original garden and top up with shrubs from planting palette as required

Existing ornamental cherry to be retained within new shrub border. Carry out essential tree work in accordance with BS3936:2010

Maintain existing shrubs along rear fence

Sheds with 300mm gravel surround and retaining timber board at GL150mm depth pegged at 1m centres

Close boarded fence between gardens 1500mm with 300mm trellis panel over ensure permeable gravel boards beneath

Replant all Begonias from old pond in lee of the fence (north facing and shady)

Existing ornamental conifer to be retained

Replant all shrubs saved from original garden along these borders, with lower plants around espaliers. Maintain existing conifer. Fill in gaps with shrubs from palette as required

Excavate planting bed by hand around existing apple tree which can be espaliered against boundary wall. Rear plant bed 11m2

Relocate Apple tree T4 and replace in specially prepared tree pit to completely accommodate depth and spread of rooting area. Stake

Apple tree against wall - old espalier maintain and retain against well as with Pear tree

Pear too old to be moved, maintain against wall and espalier

Permeable block paved alighting areas to edges of parking bays (over cellweb)