

Acme single camber Heather Sandfaced

Fine sanded finish

Similar colours (see back for full range of colours)



Technical data

Minimum pitch	30°
Size of tile (overall)	265 x 165mm
Covering capacity (net)	60 tiles/m ² (100mm gauge)
Weight of tiling (approx.)	64 kg/m ² (0.63 kN/m ²) (100mm gauge)



Single camber



BS EN 1304

Clay plain tile colours

Key (F) Fine sandbed finish (S) Smooth finish




Acme single camber

Natural clay, machine made, single cambered plain tiles, offering crisp, contemporary lines and the warmth and character of clay at an affordable price.




Acme double camber

Natural clay, machine made clay plain tiles with longitudinal and latitudinal camber able to create highly textured roofscapes with accentuated light and shade.




Hawkins

Single cambered (longitudinal), machine made clay tile, manufactured for over 150 years. This heritage, combined with modern firing techniques, gives a unique colour range.



Ashdowne

Handcrafted clay plain tiles offer a warm, mellow appearance, with a granular texture and slight random irregularities that make each tile unique.



* Marley Eternit clay plain tiles can achieve an A+ rating as found in the BRE Green Guide to Specification based on generic rating for UK produced clay plain tiles (element ref: 312 410003).

Note on Acme colour: The body colour of Acme smooth clay plain tiles is red/brown with minor tonal variations which result from the natural clay material. Acme sandfaced clay plain tiles are surfaced with selected sand before firing. The exact photographic reproduction of product colours is limited. For a more accurate colour reference, customers are advised to request an actual product sample before ordering.

Customer Services

Tel 01283 722588 Fax 01283 722219 E-mail roofinginfo@marleyeternit.co.uk
www.marleyeternit.co.uk/clay

Marley Eternit Limited, Litchfield Road, Burslem, Burton-on-Trent DE14 3HD

→ Advice, literature and samples

Visit www.marleyeternit.co.uk/clay

www.marleyeternit.co.uk/downloads

Tel 01283 722588

E-mail roofinginfo@marleyeternit.co.uk



an Etecx group company