

Drawing number 002, rev A

* 6 Parking area + Amenity area to be used for temporary contractors vehicles parking, stacks of materials + loading + unloading of materials. No temporary buildings are to be erected.

* 6 Loading, unloading and parked vehicles will utilise the parking area. So that the footpath and road will be kept clear for free flow of traffic at all times. Deliveries during peak times to be avoided.

Parking and amenity area to be used for delivery of materials. Materials will not be delivered to the footpath, but be stacked within the fenced parking area.

* 8 Soft Parking:
Make use of Holly Tree
already present, tidy
away weeds,
plant a flowering
Cherry Tree.

* 4 Already built dropped kerb.
1st fencing panel to be removed
to allow access for construction
vehicles.

* 5 There is currently no fence in
place to be removed. Temporary site
fencing to be erected with the 4:30 angle
requirements met.


* 9 Amended boundary of fence to be
angled in at 4:50 Angle from the pavement
to the parking area adjoining the rear garden.

* 11 Car parking spaces to
be constructed using
the bricks already
existing spaces 3+4,
bricks to be relayed neatly
for all 4 spaces.

* 12 + 13
Handstandboard wooden
shed provides bike storage
+ bin areas.

* 10
Not being constructed,
as advised by WSC
transport.

* 7 MATERIALS & FINISHES:
BRICKS: FORTERRA USC SANDP
ROOF TILES: PARLEY CONCRETE,
ANTIQUE BROWN



Amendments	by	Date
Job Title		
185 COR/TP		
Drawing		
Site Plan (Proposed)		
Scale: 1:200 @ 1/3		
Drg.No.	ADS-04-P	
Drawn by:	NJH	
Issued to:	LA	
Status:	Planning	
Date	26.04.1	