



From: Sarah Burrow <Sarah.Burrow@arun.gov.uk>
Sent: 11 January 2021 11:13
To: Planning.Responses <Planning.Responses@arun.gov.uk>
Cc: Amy Myer <Amy.Myer@arun.gov.uk>
Subject: RE: Planning Consultation on: BR/292/20/PL

Engineers Comments Regarding Surface Water Drainage

I would like to highlight West Sussex LLFA Policy for the Management of Surface Water (paragraph 5.4.4) below. As part of the submission we would expect to see evidence of a 50% betterment of existing surface water run off rates (if infiltration is not possible). The applicant should contact this department to discuss the details of this, particularly given the temporary nature of the proposed building.

“Redevelopment on brownfield land has the potential to rectify or reduce flood risk. In all cases, including on brownfield sites, runoff should where possible be restricted to the greenfield 1 in 1 year runoff rate during all events up to and including the 1 in 100 year rainfall event with climate change. An alternative approach would be for discharge rates to be limited to a range of greenfield rates, based on the 1 in 1, 1 in 30 and 1 in 100 year storm events. However, the use of this method to restrict discharge rates requires the inclusion of on-line long-term storage, sized to take account of the increased post development volumes, discharging at no greater than 2l/s/ha. While discharging at no greater than 2 l/s/ha is acceptable, it is still the LLFA’s preference that the former approach is used wherever possible. If it is deemed that this is not achievable, evidence must be provided and developers should still seek to achieve no increase in runoff from greenfield sites and a 50% betterment of existing run off rates on brownfield sites (provided this does not result in a runoff rate less than greenfield). For further guidance see

If you are minded to approve the application please apply the following conditions to ensure that the development is adequately drained and does not increase flood risk elsewhere.

PCENG D2

"Development shall not commence, other than works of site survey and investigation, until full details of the proposed surface water drainage scheme have been submitted to and approved in writing by the Local Planning Authority. The design should follow the hierarchy of preference for different types of surface water drainage disposal systems as set out in Approved Document H of the Building Regulations, and the recommendations of the SuDS Manual produced by CIRIA. Winter groundwater monitoring to establish highest annual ground water levels and winter Percolation testing to BRE 365, or similar approved, will be required to support the design of any Infiltration drainage. No building / No part of the extended building shall be occupied until the complete surface water drainage system serving the property has been implemented in accordance with the agreed details and the details so agreed shall be maintained in good working order in perpetuity."

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W SP1, W DM1, W DM2 and W DM3 of the Arun Local Plan. This is required to be a pre-commencement condition because it is necessary to implement the surface water drainage system prior to commencing any building works.

And the accompanying informative:

INFORM D

"Infiltration rates for soakage structures are to be based on percolation tests undertaken in the winter period and at the location and depth of the proposed structures. The percolation tests must be carried out in accordance with BRE365, CIRIA R156 or a similar approved method and cater for the 1 in 10 year storm between the invert of the entry pipe to the soakaway, and the base of the structure. It must also have provision to ensure that there is capacity in the system to contain below ground level the 1 in 100 year event plus 40% on stored volumes, as an allowance for climate change. Adequate freeboard must be provided between the base of the soakaway structure and the highest recorded annual groundwater level identified in that location. Any SuDS or soakaway design must include adequate groundwater monitoring data to determine the highest winter groundwater table in support of the design. The applicant is advised to discuss the extent of groundwater monitoring with the Council's Engineers.

Supplementary guidance notes regarding surface water drainage are located here

<https://www.arun.gov.uk/surfacewater> on Arun District Councils website. A surface water drainage checklist is available on Arun District Councils website, this should be submitted with a Discharge of Conditions Application."

PCENG D4

"Development shall not commence until full details of the maintenance and management of the surface water drainage system is set out in a site-specific maintenance manual and submitted to, and approved in writing, by the Local Planning Authority. The manual is to include details of financial management and arrangements for the replacement of major components at the end of the manufacturer's recommended design life. Upon completed construction of the surface water drainage system, the owner or management company shall strictly adhere to and implement the recommendations contained within the manual."

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W DM1, W DM2 and W DM3 of the Arun Local Plan. It is considered necessary for this to be a pre-commencement condition to ensure that the future maintenance and funding arrangements for the surface water disposal scheme are agreed before construction commences.

Kind Regards

Sarah Burrow

Engineering Assistant, Engineering Services

T: 01903 737815



E: sarah.burrow@arun.gov.uk

Whilst national restrictions are in place I will be working flexibly between the hours of 8am and 8pm. I appreciate your patience if I am slower than usual to respond. Equally I understand that you may be facing similar challenges and varying work patterns and will not be expecting immediate responses to my e-mails.

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF
www.arun.gov.uk

Sign up to our newsletter [here](#)



From: Planning.Responses <Planning.Responses@arun.gov.uk>
Sent: 08 December 2020 11:49
To: Land Drainage [REDACTED]
Subject: Planning Consultation on: BR/292/20/PL

To: **Engineers (Drainage)**

NOTIFICATION FROM ARUN DISTRICT COUNCIL

Town & Country Planning Act 1990 (as amended)
Town and Country Planning (Development Management Procedure) (England) Order 2015

Planning Permission

Application No: BR/292/20/PL
Registered: 7th December 2020
Site Address: Butlins Upper Bognor Road Bognor Regis PO21 1JJ
Grid Reference: 494416 99407
Description of Works: Erection of temporary buildings to accommodate performance stage and seating for a period of up to 3 years. This site is in CIL Zone 4 (Zero Rated) as other development.

The Council have received the above application.

[Click here to view the application details](#)

Should you have any comments to make, these should be sent by replying to this email by 10th January 2021. You can also monitor the progress of this application through the Council web site:

www.arun.gov.uk/planning

The application will be determined having regard to the development plan policies (if any are relevant) and other material considerations. The development plan can be accessed via the website <https://www.arun.gov.uk/development-plan> as can the leaflet how to respond to planning applications <https://www.arun.gov.uk/planning-application-comments> which deals with material planning considerations.

Please be aware that any comments you may make will be available on our website so please do not insert personal details or signatures on your reply.

Should the application go to appeal the Planning Inspectorate will publish any comments made to the Council on their website: <https://www.planningportal.co.uk/info/200207/appeals> but they will protect personal details.

In the absence of a reply within the period stated, I shall assume that you have no observations to make

Yours sincerely

Amy Myer

Planning Officer- Arun District Council

Telephone: 01903 737776

Email: amy.myer@arun.gov.uk

PLCONSULT (ODS) 2020