



Over 30 years of success and still planning

WALSINGHAM PLANNING

SPECIALIST PLANNING & DEVELOPMENT CONSULTANTS

Planning Statement, including FRA and D&AS


Butlins Resort
Upper Bognor Road
Bognor Regis
PO21 1JJ

New Reception Kiosk & revisions to parking layout

DECEMBER 2020

Walsingham Planning

Bourne House
Cores End Road
Bourne End
Buckinghamshire
SL8 5AR



www.walsinghamplanning.co.uk

CONTENTS

1	INTRODUCTION.....	1
2	SITE AND SURROUNDINGS.....	2
3	RELEVANT PLANNING HISTORY	3
4	PROPOSED DEVELOPMENT.....	4
5	PLANNING POLICY.....	6
6	ASSESSMENT.....	9
7	DESIGN & ACCESS	12
8	FLOOD RISKASSESSMENT & DRAINAGE	14
9	CONCLUSION	17

I INTRODUCTION

- I.1 Walsingham Planning has been instructed by Bourne Leisure to submit a planning application at the Butlins Resort, Bognor Regis seeking planning permission for the following development:

“New reception kiosk and revisions to car park layout.”

- I.2 This Statement has been prepared following an examination of the site and surroundings and relevant planning policy documents.

- I.3 This Statement provides the background information on the site and an assessment of the proposals in relation to planning policy and other material considerations, and is set out under the following sections:


- Chapter 2 provides a description of the site and surroundings;
- Chapter 3 sets out the relevant planning history of the site;
- Chapter 4 sets out the proposals and background for the development;
- Chapter 5 sets out the relevant planning policy and guidance;
- Chapter 6 discusses the planning considerations against these policies;
- Chapter 7 provides a brief Design and Access Statement;
- Chapter 8 provides a brief FRA; and
- Chapter 9 sets out the conclusions.

- I.4 This Statement should be read in conjunction with the following documents submitted in support of the application, in view of the very limited scale :

- Application Form, certificate and CIL form
- Existing and Proposed Drawings
- Butlin’s Splash Level 2 Flood Risk Assessment Sep 2016 (for information/background)

2 SITE AND SURROUNDINGS

- 2.1 Whilst the application site comprises the Butlins resort at Bognor Regis, for the purposes of this planning application the development site comprises part of the car park to the north of the new Splash pool and the car park to the east of the Splash.



- 2.2 The boundaries of the north car park are landscaped and enclosed in accordance with the details approved under the planning permission for the Splash, Upper Bognor Road lies to the north, there are residential properties lying to the west. The Splash permission approved a decked car park to the east of the pool building together with a phasing plan which shows this area in use for 152 car parking spaces, beyond the boundary a landscaped area and Sea Road there are residential properties facing toward the site.
- 2.3 No buildings on the application site are listed, and the site does not lie in a conservation area.
- 2.4 The site lies just inside the boundary marking the Pagham Harbour Buffer Zone B (5km buffer). The site is within 2km of the Bognor SSSI.

3 RELEVANT PLANNING HISTORY

- 3.1 There is an extensive planning history for the wider Butlins resort site. Of most relevance, in January 2017, planning permission ref: BR/240/16/PL was granted for the demolition of the existing swimming pool building and erection of a new swimming pool complex (known as The Splash) along with associated works towards the east of the Butlins resort site. This new swimming pool complex has been built and replaced outdated staff and guest accommodation.
- 3.2 The car parks now affected by this new proposal were provided as part of the Splash project.
- 3.3 Part of the Splash scheme included a new kiosk which moved the newly arriving guest registration facility further into the site seeking to reduce the potential of queuing cars to impact on the highway network outside of the site, in particular the roundabout on Upper Bognor Road. An amendment to the approved kiosk arrangement was approved under reference BR/212/20/PL.

4 PROPOSED DEVELOPMENT

- 4.1 At the time of writing the resort has reopened following the lifting of Covid restrictions for a brief period leading up to Christmas 2020 but will then close as usual in January 2021. The resort is taking very extensive measures to ensure the safety of its staff and guests including a significantly reduced number of guests present in the resort. There is a current planning application for a temporary stage on the site of the old swimming pool which will enable an increase in the number of guests that can be safely accommodated whilst maintaining social distancing at the entertainment venues.
- 4.2 As a result of Covid the resort has been either closed altogether or operating at reduced capacity since March 2020 but it is important that the resort returns to full capacity or at least closer to full capacity as soon as possible maintaining the socio-economic benefits of the resort to the town, keeping staff employed and providing holidays for guests many of whom may have been disappointed as a result of closures in 2020.
- 4.3 The revised method for welcoming and registering guests approved under the Splash permission and its amendment making use of hand held devices from a small kiosk on the entrance drive has not functioned as well as had been anticipated, not least as hard copy welcome packs and keys need to be issued to arriving guests either on checking in or at hotel reception areas. Furthermore, as a response to current Covid restrictions and the possibility of on-going operational requirements the hotel reception areas are, effectively, closed and all keys must be issued to arriving guests in a manner that provides social distancing and avoids guest family groups queuing in reception areas.
- 4.4 Therefore, it is proposed to return the welcome and registration process to an office based exercise in a new kiosk. This means that the check in function previously carried out in hotel receptions can also be completed as guests arrive and whilst they are still in their family groups in their separate vehicles (ie fully socially distanced). Keys can be made as guests arrive, including any need to change rooms as may be required.
- 4.5 In order to further ensure that there is no vehicle queuing backing up to the site boundary the kiosk is moved even further into the site and onto the new car park area to the north of the Splash pool. The kiosk will have 4 service windows so that 4 cars can be processed at a time with room for cars to manoeuvre so that guests who have completed the process can move off and queuing guests can take their place. Location of the kiosk as proposed within the new car park means that some 53 cars can queue within the site as shown on plan

WOC/MPN/DR/A/0010A and guests who have completed registration have a free route into all of the parking areas in this part of the resort.

- 4.6 There is loss of 30 parking spaces as a result of locating the kiosk in an existing parking area together with the necessary manoeuvring areas, these are more than compensated for in the formalisation of the parking area at the rear (east) of the Splash. Previously approved phasing plan 5128/105C showed 152 spaces in the area east of the Splash in order to maintain the level of parking provision in this part of the resort. Location of the kiosk and other consequent changes results in loss of 49 spaces but the formalisation of the layout provides 234 spaces, i.e. an overall increase of 33 spaces compared to the approved level of provision as part of the Splash planning approval, please see plans WOC/MPN/BOG/DR/A/0011A & 12A which show the numbers of existing and proposed spaces in each of the car parks (including the unaffected parts of the resort).
- 4.7 The formalisation also completes the circular route around the Splash for guest use thereby enabling guests that have registered at the kiosk to gain access to the full range of parking without conflict with the queuing arrangement.
- 4.8 The planning approval for the Splash showed a decked car park to the east of the building with 225 ground level spaces (and 208 spaces at upper level), future provision of the decked level is not prejudiced by the currently proposed formalisation of the layout in this area.

5 PLANNING POLICY

- 5.1 Section 38(6) of the 2004 Planning & Compulsory Purchase Act requires that determination of any planning application must be in accordance with the development plan, unless material considerations indicate otherwise.
- 5.2 In this case, the development plan comprises policies from the Arun Local Plan (2018) and the Bognor Regis Neighbourhood Plan (2015).
- 5.3 The National Planning Policy Framework (NPPF) is also of relevance.

Arun Local Plan

- 5.4 Policy SD SPI states that the Council will take a positive approach to proposals, reflecting the NPPF and its support of sustainable development.
- 5.5 Policy SD SPIa seeks to promote and enable development which supports Bognor Regis' role as a main service, employment, retail and social centres. It specifically supports development that will benefit Bognor Regis as a holiday centre.
- 5.6 Policy SD SP2 sets out that development should be focused within the Built Up Area Boundaries and will be permitted, subject to consideration against other policies of the Local Plan.
- 5.7 Policy EMP SPI promotes the sustainable growth of the District's economy to meet the varying needs of different economic sectors, support job creation and (inter alia) leisure development, especially in Bognor Regis. The policy supports and promotes a high quality visitor economy.
- 5.8 Policy TOU SPI supports sustainable tourism development which protects the Council's main tourism assets. It sets out that proposals for visitor related development will be determined by Arun's capacity to absorb growth. This means tourism growth which:
- a. Encourages long-term visitor interest / activity;
 - b. Ensures a viable visitor economy;
 - c. Provides benefit to local people;
 - d. Extends the visitor season; and
 - e. Protects and enhances the natural and built environment of Arun.

- 5.9 Policy TOU DMI states that proposals for development, including expansion, which are likely to attract visitors (such as leisure facilities) will be supported provided that they:
- a. are in accessible locations;
 - b. are accompanied by workable and realistic travel plans;
 - c. address visitor management issues; and
 - d. achieve good design.
- 5.10 Policies D SPI and D DMI requires all development to make efficient use of land but reflect the characteristics of the site and local area in their layout, landscaping, density, mix, scale, massing, character, materials, finish and architectural details.
- 5.11 Policy T SPI requires development to be have acceptable transport impacts.
- 5.12 Policy ENV SPI requires the preservation, restoration and enhancement of biodiversity and the natural environment, particularly designated sites, including Pagham Harbour.
- 5.13 Policy ENV DM2 requires development which is within Zone B (0-5km) of Pagham Harbour and likely to have an impact on it to make a contribution towards its management and to create easily accessible new green spaces for recreation within or adjacent to the development site in order to accommodate the predicted increases in demand for local walking, including dog walking.
- 5.14 Policy W SPI and W DM2 require a site specific Flood Risk Assessment to demonstrates that development will be safe, including access and egress, without increasing flood risk elsewhere and reduce flood risk overall.
- 5.15 Policy QE DMI states that new noise generating development must be supported by a noise report. It must demonstrate that the development meets appropriate national and local standards for noise, and that mitigation measures ensure noise can be managed at an acceptable level.

Bognor Regis Neighbourhood Plan

- 5.16 Policy 8d which concerns the Butlin's Resort, states that the "enhancement and development of this major tourist destination on this site will be encouraged subject to compliance with other policies in this plan..."

- 5.17 Policy 7 states that *“where proposals comply with other policies in this plan, development of new and existing tourist facilities will be supported, as a crucial part of improving Bognor Regis as a visitor destination.”*

The NPPF

- 5.18 At the heart of the NPPF is a presumption in favour of sustainable development; development proposals that accord with the development plan should be approved without delay.
- 5.19 The NPPF states how planning should drive and support sustainable economic development (para.17 3rd bullet), and goes on to state (para.19) that the planning system should do everything it can to support sustainable economic growth and that economic growth should be given “significant weight”.
- 5.20 LPAs “should approach decision making in a positive way to foster the delivery of sustainable development” and they “should look for solutions rather than problems”. LPAs “should seek to approve applications for sustainable development where possible” and they “should work proactively with applicants” (paras. 186 & 187).

6 ASSESSMENT

Principle of Development

- 6.1 The proposed development is associated with and located on an existing leisure site within the built-up area of Bognor Regis. It will provide an improved facility which will help the resort to support Bognor Regis' visitor economy and role as a holiday centre in accordance with policies SD SP2, SD SPIa, EMP SPI, and 7, and in response to the Covid pandemic.
- 6.2 The proposals will not increase the capacity of the resort. They allow Butlins to improve visitor experience at check in, enhance the initial reception of guests, enable social distancing of guests as they check in and get their keys whilst increasing the potential vehicle queuing capacity within the site in accordance policies TOU SPI and TOU DMI.
- 6.3 The principle of the development is therefore wholly in accordance with the development plan.

Design & Appearance

- 6.4 Comments on the design of the proposed building are set out in chapter 7 below. The design is functionally efficient and suitable to its location which is well-contained and screened by existing buildings in accordance with policies D SPI and D DMI.

Amenity

- 6.5 The proposal will not generate any new noise or other activity, it simply relocates and reorganises the existing check in process in a more efficient and Covid compliant manner.

Transport & Highways

- 6.6 No Transport Assessment/Statement is submitted as the proposals do not increase guest numbers. The kiosk is only to improve the check in arrangements and should reduce any potential for queuing traffic to obstruct the highway. The proposals will therefore have no adverse impact on transport or the highways in accordance with policy T SPI.
- 6.7 Formalisation of the car park (in the area already approved for car parking) will increase spaces available on site beyond the level agreed to be necessary for the current level of accommodation within the resort.

Flood Risk & Drainage

- 6.8 For obvious reasons, the proposed development needs to be on the existing Butlins site. A Sequential Test exercise is therefore futile. There is only a small part of the resort outside of flood zone 3 and this is occupied by other buildings so there is equally little merit in considering alternative locations from a flood protection point of view. Furthermore, the kiosk must be optimally located in relation to the access and to facilitate free vehicular movement within the site. As the proposal is for “less vulnerable” development used only by staff, albeit in flood zone 3, there is no requirement for an Exception Test.
- 6.9 A very brief Flood Risk Assessment is included in chapter 8 of this Statement, this demonstrates that development will be safe without increasing flood risk in accordance with policies W SPI and W DM2 and NPPF guidance.

Ecology

- 6.10 The site lies just inside the boundary marking the Pagham Harbour Buffer Zone B (5km buffer). However, the proposed development will not increase the capacity of the resort or result in any additional disturbance on the Harbour. It would not therefore have any adverse impact on the protected area and would not incur a Pagham Harbour contribution in accordance with policies ENV SPI and ENV DM2.
- 6.11 The site is within 2km of the Bognor SSSI. However, for the same reasons as above, it would not cause any increased adverse impact on the SSSI and wildlife in general.
- 6.12 No ecology assessment is required, as no demolition is proposed as part of this application.

Heritage

- 6.13 No buildings on the application site are listed, and the site does not lie in a conservation area. The Bognor Regis Hotham Park Conservation Area is located to the north west of the Butlins site, but the application site is not visible from the Conservation Area owing to the presence of existing buildings.

Economy

- 6.14 The economic benefits of the resort are huge and the proposal will assist the resort to operate better – to the benefit of guests, staff and the local community, it will also play a significant part in enabling the resort to operate safely in a Covid and post-Covid environment. The


Butlins resort makes a significant contribution to the local economy through the employment of local people and linked spending outside of the resort within Bognor Regis and the District.

7 DESIGN & ACCESS

- 7.1 This Design and Access Statement is submitted on behalf of Butlins Skyline Ltd in support of the proposal for a Kiosk at Butlins - Bognor Regis. The site is located in Butlins holiday resort on the south coast of England, in West Sussex.
- 7.2 The purpose of this statement is to communicate to the Local Planning Authority and other interested parties the process that has led to the development proposals and the design response.
- 7.3 The project objective is for a new Kiosk in Butlins Resort to enable cars to be processed faster and take them off the surrounding roads.


Location

- 7.4 The proposed Kiosk is to be located in the existing car park on the north side of the Splash pool.



Kiosk Design

- 7.5 The kiosk is of timber construction and is to be 4m wide by 12.5m long and 3.1m high. It includes two desk points along each side, positioned next to sliding windows to facilitate the delivery of information to arriving guests. The kiosk is to be clad in a mix of treated redwood shiplap timber and anthracite grey Trespa flat panels.



Access

- 7.6 Staff will access the kiosk by foot via the existing footpath surrounding the splash building. Given the use of the building, access will be restricted to Butlins staff only. At peak times this will be up to five people. However for the majority of the time, out of peak hours, this will host two or three people who will operate the two proposed check in windows on the northern side of the kiosk. The building includes two entrances, one at each end. These entrances are for staff only and proposed to be stepped access with a mobile ramp kept inside the Kiosk to accommodate disabled access.
- 7.7 No guests will be allowed to access the kiosk by foot.
- 7.8 Guests will arrive at the kiosk by car to be given their welcome packs and then to proceed on to their allocated parking location.
- 7.9 As there are no additional accommodation units proposed as part of this application, there will not be any increase of traffic to the resort.

8 FLOOD RISKASSESSMENT & DRAINAGE

- 8.1 The proposed development will result in the construction of single storey kiosk within land currently occupied by a recently built car park. The car park was constructed as part of the January 2017 planning application for the erection of the Splash Pool complex with the associated parking and access infrastructure.
- 8.2 The existing car park was constructed under the approved planning application and is drained by a series of linear channel drains that capture runoff from the car park surface before directing the flow to the underground drainage pipework leading to a large cellular storage attenuation tank. The tank then drains via a vortex flow control device to the nearby drain that flows into the Aldingbourne Rife at reduced rates approved within the Flood Risk Assessment (FRA2017) written for the approved January 2017 planning application.
- 8.3 The FRA2017 (copy included in this submission for information only) stated:

Flood Risk – To the Development

- There is considered to be no risk of flooding to the proposed development from artificial sources.
- Flood risks to the proposed development from tidal and fluvial flooding have been assessed as low.
- Overall flood risk to the proposed development from pluvial and sewer sources are considered to be low.
- There is considered to be a high risk of flooding from groundwater.

Flood Risk – From the Development

- The increased fluvial and surface water flood risk from the proposed development is considered to be negligible.

Flood Risk Mitigation

The site is protected against tidal flooding by the sea defence wall. In the event of a breach or wave overtopping the defences, the maximum predicted tide level for a 1 in 200 year return period event is 4.5m AOD, which is higher than the level of the ground floor and plant rooms that are situated within the basement. The main structure of the swimming pool will be designed to resist loads imposed by floodwater in order to ensure that it does not collapse in the event of a tidal breach. Plant rooms will be constructed within concrete walls with flood gates to protect plant against flooding during any breach or overtopping. It is also recommended to locate electric power points above 4.5m AOD flood level, where possible, and to use an appropriate circuit breaker system to trip off the power system during flood events.

It is recommended that a Flood Emergency Plan be developed, which will detail the route of egress in the event of a flood to enable occupants of the swimming pool will be evacuated to areas within the swimming pool building, or other areas of the Holiday Centre that are elevated above the maximum predicted flood level (4.5m AOD). It is also recommended that the swimming pool signs up to receive Flood Alerts issued by the Environment Agency, to ensure that the evacuation plan can be implemented with as much forewarning as possible.

The site is located within a high risk area for groundwater flooding and the ground floor slab will be installed above the highest anticipated groundwater level. To mitigate the risk of groundwater seepage, the slab and basement plant room will be constructed using concrete mixes with an appropriate water resistant specification. Measures will also be taken in the foundation design to stop deeper

groundwater from migrating upwards to the perched groundwater level. Pile design and construction methods will mitigate against the formation of a conduit between the two levels of groundwater.

Surface Water Drainage Strategy

A surface water drainage system has been proposed, which will incorporate Sustainable Drainage Systems in the form of porous paving within car parks, shallow cellular storage on the deck of car park and geo-cellular storage below landscaped areas surrounding the swimming pool. These features will enable water quality to be improved and they will provide sufficient attenuation storage to enable the peak discharge during rainfall events with a return period of up to 1 in 100 years plus 40% climate change to be restricted to the mean annual runoff, Q_{bar} .

The proposed surface water drainage network will reduce flood risk to and from the proposed development, as the proposed Sustainable Drainage Systems will enable runoff rates to the Aldingbourne Rife to be reduced, whilst permitting excess surface water generated during extreme events to be stored within Sustainable Drainage Systems constructed as an integrated part of the development.

- 8.4 The proposed kiosk will be constructed on the area already occupied by the recently constructed car park. Therefore, the kiosk will not generate any additional surface water drainage nor will it amend the drainage regime within the Splash site.
- 8.5 The recently constructed linear drainage channel located under the proposed kiosk will be cut short and re-provided with a new outlet gully located north of the kiosk in a manner to allow future maintenance, together with a new connection to the nearby recently constructed drains that currently already receive the runoff from the same area of car park.
- 8.6 A new gully will be installed on the opposite side (south side) of the kiosk to capture any residual runoff and direct it to the nearby drains, again mimicking the regime of drainage currently in operation on site. The runoff from the small roof of the kiosk will drain directly to the surrounding car park surface where it will find its way into either the gully or the channel drain described in above.
- 8.7 The discharge rate of surface water from the Splash site will remain unchanged by the works to the kiosk as the proposed drainage alterations will only be made to the local drains within the immediate vicinity of the kiosk, all upstream of the flow control device and the main attenuation tank beneath the proposed kiosk.
- 8.8 The proposed kiosk foundations solution will be detailed to ensure that it does not adversely affect the attenuation tank located under the kiosk. With a cover depth of over 1.4m for a tank originally designed to accept HGV loading in the car park area, the solution will not result in an overly complicated construction process.

- 8.9 Therefore, the proposed development of the site to include a kiosk within the existing car park will not alter the regime of drainage and will not result in increased risk of flooding to the site of the surrounding properties.

9 CONCLUSION

- 9.1 It is proposed to erect a new kiosk to improve current check in and registration at the resort, it is also needed to ensure that the resort can follow best practice and help guests to maintain social distancing.
- 9.2 The proposal will not increase the capacity of the resort. It would simply allow the resort to operate more efficiently and provide a better and safer experience for guests. The proposal will have no impact on the nearby areas of special ecological and habitat interest as guest capacity is not increased.
- 9.3 The principle of the development is supported by NPPF and the development plan.
- 9.4 The kiosk design is appropriate for its function and location and is located in the optimum position to enhance queuing capacity, minimise loss of parking and maximise post check in flexibility for guests finding a parking space, it meets the policies of the Development Plan. Formalisation of the car park (in the area already approved for car parking) will increase spaces available on site beyond the level agreed to be necessary for the current level of accommodation within the resort.
- 9.5 As set out in the FRA chapter of this Statement the proposal will not add to flood risk on site or in the surrounding area.
- 9.6 In summary, the proposed development complies with the Development Plan and the provisions of the NPPF such that a favourable decision should be reached as expeditiously as possible.