



IMPACT
GEOTECHNICAL

Trial Pit Log

Trial Pit No.
TP1
Sheet 1 of 1

Project Name: 283-285a Chichester Road

Project No
P19.142

Co-ords
n/a

Hole Type
TP


Location: Bognor Regis

Pit Dimensions

Level
n/a

Scale
NTS

Client: Alex Eggett



Date(s)
16/10/2019

Logged By
GC

Well	Sample and Insitu Testing			Results	Depth (m)	Level (m AOD)	Legend	Stratum Description	
	Water Strikes	Depth(s)	Type						
					0.40			MADE GROUND: Dark brown gravelly clayey Sand. Sand is fine to coarse. Gravel is subangular to subrounded, fine to coarse sized flint and brick.	
					0.70			Soft to firm consistency brown mottled slightly sandy silty CLAY. Sand is fine to medium. (RIVER TERRACE DEPOSIT)	
					1.50			Loose to medium dense fine to medium grained SAND. (RIVER TERRACE DEPOSIT)	1
								End of Trial Pit at 1.50mbgl	2
									3

Remarks

No Groundwater encountered. Hole backfilled with arisings. Soil infiltration conducted in general accordance with BRE 365.