GENERAL CONSTRUCTION NOTES:

ALL DIMENSIONS TO BE CHECKED & VERIFIED ON SITE.

DOORS MARKED f.r. TO BE ½ HOUR FIRE DOORS TO BS 476 PT. 22 30/30 GRADE WITH INTUMESCENT STRIPS & COLD SMOKE SEALS FITTED WITH OVERHEAD CLOSERS.

HEATING:- NO. 32; EXISTING ELECTRIC HEATING RETAINED.
NO. 30; INSTAL NEW SMALL BORE RADIATOR SYSTEM WITH GAS FIRED COMBINATION BOILER & BALLANCED FLUE IN STAFF W.C. WHERE SHOWN ON PLAN.

FOUL DRAINAGE:- INSTAL SANITARY FITTINGS IN POSITIONS SHOWN ON PLAN, 32mm. DIA. WASTE TO BASINS, 40mm TO SINK & SHOWER, WASTE PIPES TO BE IN P.V.C. & INCORPORATING 75mm. DEEP SEAL TRAPS, ANTI-VAC TRAPS TO WASTE RUNS OVER 1.5m. LENGTH. ~ WASTES TAKEN IN 100mm. LOW LEVEL SOIL PIPE WHERE SHOWN TO NEW 100mm DIA. P.V.C. SOIL & VENT PIPE ENCASED, TERMINATING INTERNALLY WITH RELIEF VALVE, PROVIDE VENT TO RELIEF VALVE CASING.

NEW FOUL DRAIN RUNS TO BE 100mm DIA. 'MARLEY' OR SIMILAR P.V.C. LAID ON & SURROUNDED IN PEA SHINGLE AT 1:40 FALL TO EXISTING FOUL MANHOLE AS SHOWN.

ARUN DISTRICT COUNCIL BR/64/12/