

Tree Planting Specification for 67 to 71a Upper Bognor Road, Bognor Regis

Four small sized trees of upright habit to suit a small garden situation

Tree / Shrub Location On Plan	Tree Species	Tree Size	Girth	Overall Height	Bare Root Or Container Grown
A	Rowan (variety of) <i>Sorbus aucuparia 'Cardinal Royal'</i>	Select Standard Tree	10-12cm	2.5m to 3.0m	Either depending on time of year planted and availability
B	Tulip Tree (variety of) <i>Liriodendron tulipifera 'Fastigiatum'</i>	Select Standard Tree	10-12cm	2.5m to 3.0m	Either depending on time of year planted and availability
C	Cherry (variety of) <i>Prunus 'Hillieri Spire'</i>	Select Standard Tree	10-12cm	2.5m to 3.0m	Either depending on time of year planted and availability
D	Cherry (variety of) <i>Prunus 'Hillieri Spire'</i>	Select Standard Tree	10-12cm	2.5m to 3.0m	Either depending on time of year planted and availability

- All trees/shrubs to be planted in pits excavated to the exact depth of the root-ball and a width equivalent to a 50% larger radius hole.
- Holes to be backfilled with a mix of 80% clean topsoil and 20% approved green compost to PAS100 and 100gms granular fertilizer.
- Incorporate a proprietary brand of watering/feeding tube system around the rootball.
- Water-in heavily after planting and surface mulch to 75mm depth.
- All trees to be short staked at 45 degrees to the stem and attached to same with a rubber securing block and tie.
- Any necessary tree pruning and tidying works are to be carried out with a 'Silky' hand saw or secateurs to BS3998 standards.