






Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF
www.arun.gov.uk



Arun District Council, Civic Centre, Maltravers Rd
Littlehampton, West Sussex, BN17 5LF
www.arun.gov.uk



From: Chris Moore [REDACTED]
Sent: 07 July 2022 08:35
To: Daniel Vick <Daniel.Vick@arun.gov.uk>

Subject: RE: Planning Consultation on: BR/77/22/PL

CAUTION: This email originated from outside of the organisation. You should take extra care when clicking links or opening attachments - if you are unsure the content is safe contact the IT Helpdesk before clicking or opening.

Dear Dan,

Thank you for looking into this for us.

We therefore confirm that we wish to withdraw the current application and we will re-assess where we go from here as this is clearly a site that is well capable of being developed in planning terms subject to the surface water drainage issue being agreed.

Kind regards,

Chris Moore

BSc (Hons), C.Build E MCABE
Sussex Building Consultancy Limited
3 Northcote Road
BOGNOR REGIS
PO21 5LZ

From: Daniel Vick <Daniel.Vick@arun.gov.uk>
Sent: 06 July 2022 14:44
To: Chris Moore [REDACTED]

Subject: RE: Planning Consultation on: BR/77/22/PL

Chris,

I have had the discussion with engineers – they remain of the opinion expressed in their consultation response. They did suggest an alternative of one dwelling may provide the necessary space to provide the necessary drainage. I would suggest withdrawal of the current application and undertake the monitoring suggested before any other application is made.

Daniel Vick
Team Leader, Development Control

T: 01903 737771
E: daniel.vick@arun.gov.uk

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF
www.arun.gov.uk



Sign up to our newsletter [here](#)



From: Daniel Vick
Sent: 27 June 2022 15:44
To: Chris Moore [REDACTED]

Subject: RE: Planning Consultation on: BR/77/22/PL

Chris,

Thanks for the email. Sorry for the delayed reply.

I will have a discussion with our drainage engineers and get back to you.

Daniel Vick
Team Leader, Development Control

T: 01903 737771
E: daniel.vick@arun.gov.uk

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF
www.arun.gov.uk



Sign up to our newsletter [here](#)



From: Chris Moore [REDACTED]
Sent: 18 June 2022 20:25
To: Daniel Vick <Daniel.Vick@arun.gov.uk>
[REDACTED]

Subject: FW: Planning Consultation on: BR/77/22/PL

CAUTION: This email originated from outside of the organisation. You should take extra care when clicking links or opening attachments - if you are unsure the content is safe contact the IT Helpdesk before clicking or opening.

Dear Dan,

I hope that you are well and not too busy.

I am away in hot sunny France at the moment, sweltering in a caravan in 41 degrees of heat and yet it is 9.00 pm here!

However, less of my current struggles - I have this email from Maria (below) regarding the above application but I am loathed to withdraw it at this stage. The council's drainage engineers have asked us to prove that soakaways will not work (including winter ground water monitoring) before alternative drainage solutions can be applied and yet clearly there is not enough space to fit them in on the site due to surrounding buildings and lack of space on the rear garden.

From a planning point of view, it would appear that the development is in line with other previous developments in terms of density and positioning so it was hoped that going through the motions of the SUDS hierarchy would not be applied where soakaways are not going to work under any circumstances, and that connection to the public surface water sewer would therefore be reasonable under the circumstances as to insist on anything else would effectively blight the site for development.

Can I ask that this email be considered and that the application could otherwise be moved towards a positive decision?

Thank you for your time Dan, I look forward to hearing from you.

Kind regards,

Chris Moore

BSc (Hons), C.Build E MCABE
Sussex Building Consultancy Limited
3 Northcote Road

From: Maria Tomalova <Maria.Tomalova@arun.gov.uk>

Sent: 17 June 2022 11:12

To: Chris Moore [REDACTED]

Cc: Daniel Vick <Daniel.Vick@arun.gov.uk>

Subject: FW: Planning Consultation on: BR/77/22/PL

Hi Chris,

I have left you a voicemail and asked you if you would not consider to withdraw your application due to the objection of Drainage Engineers.

Please see below.

From 20th until 30th of June I am out of office. Please contact Dan and let him know how did you decide.

Kind regards

Maria

Maria Tomalova
Senior Planning Officer
Directorate of Place

T: 01903 737510

E: maria.tomalova@arun.gov.uk

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF
www.arun.gov.uk



From: Sarah Burrow <Sarah.Burrow@arun.gov.uk>

Sent: 14 June 2022 14:52

To: Planning.Responses <Planning.Responses@arun.gov.uk>

Cc: Maria Tomalova <Maria.Tomalova@arun.gov.uk>

Subject: RE: Planning Consultation on: BR/77/22/PL

Engineers Comments Regarding Surface Water Drainage

The hierarchy for sustainable drainage must be followed with infiltration fully investigated. Due to the likely ground conditions it is anticipated that if infiltration is viable it will require a large plan area as blanket solutions may be required and 5m easement from buildings to soakaways must be provided. We also stipulate a 2.5m easement from property boundaries to reduce the risk of conflict with neighbouring soakaways.

The proposed layout shows there is very limited space for surface water drainage, it appears that the proposals will not comply with West Sussex Lead Local Flood Authority Policy for the Management of Surface Water Policy 1. The supplied Drainage Statement even acknowledges that "There is no room to discharge the rainwater into soakaways

on the site". This is an acknowledgement that the proposed layout and density of development precludes the use of infiltration, rather than the ground conditions on the site.

Surface water drainage must be considered at the earliest opportunity and form part of the layout development process. Without winter groundwater monitoring and winter infiltration testing there is no way of determining the area take up required for an infiltrating surface water drainage solution. Leaving drainage design until after a decision has been made will likely unduly prejudice drainage design and not allow for the hierarchy for sustainable drainage to be followed.

Furthermore, inadequately considering drainage at this stage could potentially result in a lack of sufficient capacity being provided for surface water drainage and therefore the development could lead to an increased risk of flooding elsewhere.

Therefore, I object to the application.

To overcome my objection the applicant should complete winter groundwater monitoring and winter infiltration testing and complete calculations to assess the size of structures required. A rough plan should be formed showing where these structures can be provided within the proposed layout. Evidence that no pumping or ground raising would be also be required. Detailed design of the system can be left until discharge of conditions where the applicant should provide the level of information stated within our checklist [Drainage Planning Consultations | Arun District Council](#)

However, if you are minded to approve the application please ensure the following conditions are applied:

PCENG D2

"Development shall not commence, other than works of site survey and investigation, until full details of the proposed surface water drainage scheme have been submitted to and approved in writing by the Local Planning Authority. The design should follow the hierarchy of preference for different types of surface water drainage disposal systems as set out in Approved Document H of the Building Regulations, and the recommendations of the SuDS Manual produced by CIRIA. Winter groundwater monitoring to establish highest annual ground water levels and winter percolation testing to BRE 365, or similar approved, will be required to support the design of any infiltration drainage. No building / No part of the extended building shall be occupied until the complete surface water drainage system serving the property has been implemented in accordance with the agreed details and the details so agreed shall be maintained in good working order in perpetuity."

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W SP1, W DM1, W DM2 and W DM3 of the Arun Local Plan. This is required to be a pre-commencement condition because it is necessary to implement the surface water drainage system prior to commencing any building works.

And the accompanying informative:

INFORM D

"Infiltration rates for soakage structures are to be based on percolation tests undertaken in the winter period and at the location and depth of the proposed structures. The infiltration tests must be carried out in accordance with BRE365, CIRIA R156 or a similar approved method. All design storms must include a climate change allowance, as per <https://www.gov.uk/guidance/flood-risk-assessments-climate-change-allowances>, on stored volumes or rainfall intensity. Infiltration structures must cater for the critical 1 in 10 year storm event, (plus 40%) between the invert of the entry pipe to the soakaway and the base of the structure. All surface water drainage designs must also have provision to ensure there is capacity in the system to contain the critical 1 in 100 year storm event (plus 45%).

Adequate freeboard must be provided between the base of the soakaway structure and the highest recorded annual groundwater level identified in that location. Any SuDS or soakaway design must include adequate groundwater monitoring data to determine the highest groundwater table in support of the design. The applicant is advised to discuss the extend of ground water monitoring with the council's engineers.

Supplementary guidance notes regarding surface water drainage are located at <https://www.arun.gov.uk/drainage-planning-consultations> on Arun District Council's website. A surface water drainage checklist is available on Arun District Council's website, this should be submitted with a Discharge of Conditions Application."

Kind regards

Sarah Burrow
Engineering Assistant, Engineering Services

T: 01903 737815

E: sarah.burrow@arun.gov.uk

Current working pattern: Monday-Friday: 8am - 2:30pm

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF
www.arun.gov.uk

Sign up to our newsletter [here](#)



From: Planning.Responses <Planning.Responses@arun.gov.uk>

Sent: 26 April 2022 10:34

To: Land Drainage [REDACTED]

Subject: Planning Consultation on: BR/77/22/PL

To: **Engineers (Drainage)**

NOTIFICATION FROM ARUN DISTRICT COUNCIL

Town & Country Planning Act 1990 (as amended)

Town and Country Planning (Development Management Procedure) (England) Order 2015

Planning Permission

Application No: BR/77/22/PL

Registered: 25th April 2022

Site Address: Rear of 42 Sudley Road Bognor Regis PO21 1ES

Grid Reference: 493596 99284

Description of Works: 2 No. semi-detached 3-storey houses with parking and new vehicular access.
This application is in CIL Zone 4 and is CIL liable as new dwellings.

The Council have received the above application.

[Click here to view the application details](#)

This application has been identified as CIL Liable. Therefore please be aware that, in accordance with Appendix 2 of the Arun CIL Charging Schedule, your consultation response should only include requests for Section 106 for onsite mitigation, Pagham Harbour Management Contributions (if applicable) or Affordable Housing. "Off" Site mitigation measures directly related to this development should be dealt with by condition if possible to ensure the scaling back of Section 106 if possible. CIL contributions will be used for "off" site infrastructure mitigation schemes. Therefore if this proposal triggers the need for "off" site

mitigation, please ensure that you engage in the CIL Infrastructure List Consultation process upon receipt of a consultation letter.

Should you have any comments to make, these should be sent by replying to this email by 26th May 2022 . You can also monitor the progress of this application through the Council web site:

<https://www.arun.gov.uk/planning-application-search>

The application will be determined having regard to the development plan policies (if any are relevant) and other material considerations. The development plan can be accessed via the website

<https://www.arun.gov.uk/development-plan> as can information on what comments we can consider

<https://www.arun.gov.uk/planning-application-comments>

Please be aware that any comments you may make will be available on our website so please do not insert personal details or signatures on your reply.

Should the application go to appeal the Planning Inspectorate will publish any comments made to the Council on their website: <https://app.planninginspectorate.gov.uk/> but they will protect personal details.

In the absence of a reply within the period stated, I shall assume that you have no observations to make

Yours sincerely

Maria Tomalova

Planning Officer- Arun District Council

Telephone: 01903 737510

Email: maria.tomalova@arun.gov.uk

PLCONSULT (ODD) 2020

<http://www.arun.gov.uk>

DX 57406 Littlehampton

You can view Arun District Council's Privacy Policy from <https://www.arun.gov.uk/privacy-policy>

Important Notice This e-mail is intended exclusively for the addressee and may contain information that is confidential and/or privileged. If you are not the intended recipient (or authorised to receive it for the addressee), please notify the sender and delete the e-mail immediately; using, copying, or disclosing it to anyone else, is strictly prohibited and may be unlawful. Any views, opinions or options presented are solely those of the author and do not necessarily represent those of Arun District Council. The information in this e-mail may be subject to public disclosure under the Freedom of Information Act 2000, therefore we cannot guarantee that we will not provide the whole or part of this e-mail to a third party. The Council reserves the right to monitor e-mails in accordance with relevant legislation. Whilst outgoing e-mails are checked for viruses, we cannot guarantee this e-mail is virus-free or has not been intercepted or changed and we do not accept liability for any damage caused. Any reference to "e-mail" in this disclaimer includes any attachments.

<http://www.arun.gov.uk>

DX 57406 Littlehampton

You can view Arun District Council's Privacy Policy from <https://www.arun.gov.uk/privacy-policy>

Important Notice This e-mail is intended exclusively for the addressee and may contain information that is confidential and/or privileged. If you are not the intended recipient (or authorised to receive it for the addressee), please notify the sender and delete the e-mail immediately; using, copying, or disclosing it to anyone else, is strictly prohibited and may be unlawful. Any views, opinions or options presented are solely those of the author and do not necessarily represent those of Arun District Council. The information in this e-mail may be subject to public disclosure under the Freedom of Information Act 2000, therefore we cannot guarantee that we will not provide the whole or part of this e-mail to a third party. The Council reserves the right to monitor e-mails in accordance with relevant legislation. Whilst outgoing e-mails are checked for viruses, we cannot guarantee this e-mail is virus-free or has not been intercepted or changed and we do not accept liability for any damage caused. Any reference to "e-mail" in this disclaimer

includes any attachments.
