



Planning and Development Services
Arun District Council
Arun Civic Centre
Maltravers Road
Littlehampton
West Sussex
BN17 5LF

Developer Services
Southern Water
Sparrowgrove House
Sparrowgrove
Otterbourne
Hampshire
SO21 2SW

Tel: 0330 303 0119
Email: southernwaterplanning@atkinsglobal.com

Your Ref
CM/13/18/OUT
Our Ref
PLAN-022901
Date
07/06/2018

Dear Sirs,

Proposal: Outline application with some matters reserved for the erection of up to 300 dwellings and ancillary development comprising open space, a building within use class D1 of up to 875 square metres net, a building for A1 use having a floor area of up to 530 sq. metres net, together with open space and ancillary works, including access points, car parking and drainage arrangements, with appearance, landscaping, layout; and scale wholly reserved for subsequent approval. The access detail, showing the points of access to the development, and indicated on Bellamy Roberts drawings numbered 4724/013 and 4724/005 Rev A are access proposals to be determined at this stage of the application. For the avoidance of doubt all other access detail within the site is to be determined as reserved matter at a later stage. Resubmission following CM/1/17/OUT. Departure from the Development Plan. Site: Land to West of Church Lane South of Horsemere Green Lane, Clymping, BN17 5QX. CM/13/18/OUT

Thank you for your letter of 04/05/2018.

Please find attached a plan of the sewer records showing the approximate position of a public foul rising main and treated effluent rising main sewer crossing the site. The exact position of the public sewers must be determined on site by the applicant before the layout of the proposed development is finalised.

Please note:

No development or new tree planting should be located within 4 metres either side of the centreline of the 700 mm treated effluent rising main and all existing infrastructure should be protected during the course of construction works.

No development or new tree planting should be located within 3.5 metres either side of the centreline of the 500 mm public foul rising main and all existing infrastructure should be protected during the course of construction works.

No development or new tree planting should be located within 3 metres either side of the centreline of the 100 mm public foul rising main and all existing infrastructure should be protected during the course of construction works.

No new soakaways should be located within 5 metres of a public sewer.

Please note there is deed of easement for sewer within the site.

Due to changes in legislation that came in to force on 1st October 2011 regarding the future ownership of sewers it is possible that a sewer now deemed to be public could be crossing the above property. Therefore, should any sewer be found during construction works, an investigation of the sewer will be required to ascertain its condition, the number of properties served, and potential means of access before any further works commence on site.

The applicant is advised to discuss the matter further with Southern Water, Sparrowgrove House, Sparrowgrove, Otterbourne, Hampshire SO21 2SW (Tel: 0330 303 0119) or www.southernwater.co.uk.

In order to protect drainage apparatus, Southern Water requests that if consent is granted, a condition is attached to the planning permission. For example "The developer must advise the local authority (in consultation with Southern Water) of the measures which will be undertaken to protect the public sewers, prior to the commencement of the development."

Southern Water requires a formal application for a connection to the public sewer to be made by the applicant or developer.

We request that should this application receive planning approval, the following informative is attached to the consent:

"A formal application for connection to the public sewerage system is required in order to service this development. To initiate a sewer capacity check to identify the appropriate connection points for the development, please contact *Southern Water, Southern House Sparrowgrove, Otterbourne, Hampshire SO21 2SW (Tel: 0330 303 0119)* or www.southernwater.co.uk. Please read through our New Connections Services Charging Arrangements documents which has now been published and is

available to read through on our website via the following link
<https://beta.southernwater.co.uk/infrastructure-charges>.

The planning application form makes reference to drainage using Sustainable Urban Drainage Systems (SUDS).

Under current legislation and guidance SUDS rely upon facilities which are not adoptable by sewerage undertakers. Therefore, the applicant will need to ensure that arrangements exist for the long term maintenance of the SUDS facilities. It is critical that the effectiveness of these systems is maintained in perpetuity. Good management will avoid flooding from the proposed surface water system, which may result in the inundation of the foul sewerage system. Thus, where a SUDS scheme is to be implemented, the drainage details submitted to the Local Planning Authority should:

- Specify the responsibilities of each party for the implementation of the SUDS scheme
- Specify a timetable for implementation

- Provide a management and maintenance plan for the lifetime of the development. This should include the arrangements for adoption by any public authority or statutory undertaker and any other arrangements to secure the operation of the scheme throughout its lifetime.

This initial assessment does not prejudice any future assessment or commit to any adoption agreements under Section 104 of the Water Industry Act 1991. Please note that non-compliance with Sewers for Adoption standards will preclude future adoption of the foul and surface water sewerage network on site. The design of drainage should ensure that no groundwater or land drainage is to enter public sewers.

We request that should this application receive planning approval, the following condition is attached to the consent: "Construction of the development shall not commence until details of the proposed means of foul and surface water sewerage disposal have been submitted to, and approved in writing by, the Local Planning Authority in consultation with Southern Water."

Any works within highway/ access road will require to protect public apparatus and the protection details need to be submitted to, and approved by Southern Water under NRSWA enquiry.

The developer has proposed an on-site pumping station, with a controlled discharge to the public sewer. This may be acceptable, provided the control mechanism and point of monitoring are agreed, prior to construction taking place.

Due to the vibration, noise and potential odour generated by sewage pumping stations, no habitable rooms should be located closer than 15 metres to the boundary of a proposed pumping station site and the pumping station layout and the drainage details should comply with the Sewers for Adoption Standards.

Yours sincerely,

A solid black rectangular box used to redact a signature.

Developer Services

SOUTHERN WATER



The positions of pipes shown on this plan are believed to be correct, but Southern Water Services Ltd accept no responsibility in the event of inaccuracy. The actual positions should be determined on site.

Based upon Ordnance Survey Digital Data with the permission of the controller of H.M.S.O. Crown Copyright Reserved Licence No. WU 298530

O.S. REF: SU9902SE

Scale: 1:4772

Screen Print

WARNING: BAC pipes are constructed of Bonded Asbestos Cement

WARNING: Unknown (UNK) materials may include Bonded Asbestos Cement

ARUN DISTRICT COUNCIL CM/13/18/OUT



Printed By: chandne

Date: 4-6-2018

Southern Water MapGuide Browser

Requested By: