

Proposed new Pétanque Terrain at Clymping Village Hall & Sports Ground. May 2019

Description of works

Existing situation

The proposed area currently consists of grassland that rises as you go east from the Village hall and ends adjacent to a hedge. At this point, the ground level is approximately 0.7m higher than the neighbouring field suggesting that this area was used for the disposal of soil from earlier site workings.

The Proposal

To build a Pétanque Terrain (Court) consisting of 8 no 'Piste' (playing lanes) of approximately 3m wide x 13m long. Total area 24m x 13m

The development will consist of clearing the site of vegetation, scraping back the soil between the Village Hall outbuildings and the boundary hedge and reducing the ground level over the actual playing area by 150mm. The surplus material will be used to form a grass covered 'bund' alongside the car park so as to 1, protect the car park from the playing area and 2, create a barrier so that cars cannot be driven onto the playing fields.

150mm of type 1 MOT will be laid and compacted over the playing area and 100mm will be laid and compacted over the area between the terrain and the buildings. The terrain will be surrounded by 200mm x 100mm timbers (sleepers). The surface of the terrain will be topped off with a mixture of sharp sand and 6mm chippings (limestone or similar) to a depth of 10mm maximum. The surface between the terrain and the buildings will be topped with 10mm shingle to form a pathway and seating area.

A Picket fence (or similar style) of a maximum of 1m height will be positioned alongside the terrain to separate the playing area from the pathway. The area's to the north, south and east of the terrain will be left as grassland.