

Schedule of Materials and Finishes

<u>Walls</u>	Matching stock hand-made bricks in colour blend equivalent to existing adjoining walls. Pointing to follow suit in lime mortar.
<u>Parapets</u>	Coping stones, weathered one way onto roof with feature outer profile for additional character
<u>Roof Lights</u>	Framed pyramid roof lanterns in powder coated aluminium (Black) as supplied by "Toughened Glass Systems Ltd"
<u>Roof</u>	Roof coverings in molded glassfibre resin by "Polyroof Systems 185" in grey colouring to run up and under the copings and up and onto the roof light upstands
<u>Windows</u>	In timber with hardwood cills and double glazing (thin units - 12mm (4 x 4 x 4) all painted (as shown on Section diagram on plan no 112/168/10) in white to match house
<u>Doors</u>	In timber with hardwood cills and durable glazing (thin units @ 4 x 4 x 4 - 12mm) all painted (as shown in Section drawing no 112/168/10) to match house