Proposed New dwelling
On
Land to rear of 4 Elm Grove South, Barnham

Schedule of external materials

Roof:

Flat roof to be covered with a single ply polymeric membrane in grey.

Walls:

Walls to be constructed in concrete block work, rendered with sand/cement render with a smooth finish and painted.

Where indicated on elevations external walls to be clad with vertical western red cedar boarding – sample provided

Where indicated on elevations section of the external wall are to be clad with stacked slate cladding (By Padipa Ltd) – sample provided

Windows :

Windows to be polyester powder coated aluminium finished in grey.

ARUN DISTRICT COUNCIL EG/76/10/DOC