

G. A. MacDonald Master Thatcher Ltd

Company No. 7415847

55, Sea Lane
East Preston
West Sussex BN16 1ND

VAT Registration 929 1192 14

80, Barnham Road
Barnham
West Sussex
PO22 6QE

31st May 2017

Dear Beth,

Further to my inspection and fitting of the waterproof sheet at the above address I have pleasure in submitting the following estimate to re thatch the roof using combed wheat reed.

To provide a suitable scaffold to allow safe access for thatching work.
To remove old wire and ridge materials.
To remove all existing thatch down to a suitable base for re thatching.
To thatch using combed wheat reed fixed with hazel spars. Thatch to be laid to an even thickness of approximately 12".
To ridge using combed wheat reed and sedge fixed with hazel spars. Ridge to be of wrap over design with ornamental spar pattern to follow existing.
To 'dress and sweep' entire roof area.
To cover entire roof using 20-gauge galvanized wire netting, fixed under ridge and eaves.
To remove all thatching waste materials from site.

To supply and fix for the sum of	£12,600.00
VAT at 20%	£ 2,520.00
Total	£15,120.00

I hope the above is acceptable and I look forward to hearing from you. Please do not hesitate to contact me for any further information or advice.

Yours sincerely,


G A MacDonald

Member of National Society of Master Thatchers