




From: Laura Gibbons

Sent: 21 August 2019 15:46

To: [REDACTED]

Subject: RE: EG/7/19/PL, 26 Downview Road

Hi Maria,

Condition is:

PCENG D2

“Development shall not commence, other than works of site survey and investigation, until full details of the proposed surface water drainage scheme have been submitted to and approved in writing by the Local Planning Authority. The design should follow the hierarchy of preference for different types of surface water drainage disposal systems as set out in Approved Document H of the Building Regulations, and the recommendations of the SuDS Manual produced by CIRIA. Winter groundwater monitoring to establish highest annual ground water levels and winter Percolation testing to BRE 365, or similar approved, will be required to support the design of any Infiltration drainage. No building / No part of the extended building shall be occupied until the complete surface water drainage system serving the property has been implemented in accordance with the agreed details and the details so agreed shall be maintained in good working order in perpetuity.”

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W SP1, W DM1, W DM2 and W DM3 of the Arun Local Plan. This is required to be a pre-commencement condition because it is necessary to implement the surface water drainage system prior to commencing any building works.

And the following informative should also be applied:

INFORM D

“Infiltration rates for soakage structures are to be based on percolation tests undertaken in the winter period and at the location and depth of the proposed structures. The percolation tests must be carried out in accordance with BRE365, CIRIA R156 or a similar approved method and cater for the 1 in 10 year storm between the invert of the entry pipe to the soakaway, and the base of the structure. It must also have provision to ensure that there is capacity in the system to contain below ground level the 1 in 100 year event plus 40% on stored volumes, as an allowance for climate change. Adequate freeboard must be provided between the base of the soakaway structure and the highest recorded annual groundwater level identified in that location. Any SuDS or soakaway design must include adequate

groundwater monitoring data to determine the highest winter groundwater table in support of the design. The applicant is advised to discuss the extent of groundwater monitoring with the Council's Engineers. Supplementary guidance notes regarding surface water drainage are located here <https://www.arun.gov.uk/surfacewater> on Arun District Councils website. A surface water drainage checklist is available here <https://www.arun.gov.uk/drainagechecklist> on Arun District Councils website, this should be submitted with a Discharge of Conditions Application."

Thanks,

Laura Gibbons, MEng, GMICE
Engineer (Drainage & Coastal)

Laura Gibbons | Engineer (Drainage & Coastal), Engineering Services, Arun District Council | Location: First Floor, Arun Civic Centre, Maltravers Road, Littlehampton, BN17 5LF

Internal: 37818 | External: +44 (0) 1903 737818 | Fax: +44 (0) 1903 716018 | E-mail: laura.gibbons@arun.gov.uk

Arun is Working in Partnership with Chichester District Council

Visit Arun's web site at <http://www.arun.gov.uk/> and www.chichester.gov.uk



Save the environment - think before you print.

From: Maria Tomalova
Sent: 20 August 2019 16:18
To: Laura Gibbons <Laura.Gibbons@arun.gov.uk>
Subject: EG/7/19/PL, 26 Downview Road

Hi Laura,

Another historic case (above) with historic condition ENGD28.
Please update that one as well.

Thank you

Kind regards

Maria

Maria Tomalova | Senior Planning Officer, Directorate of Place, Arun District Council | Location: First Floor, Arun Civic Centre, Maltravers Road, Littlehampton, BN17 5LF

Internal: 37510 | External: +44 (0) 1903 737510 | E-mail: maria.tomalova@arun.gov.uk

Visit Arun's web site at www.arun.gov.uk



Save the environment - think before you print.