



PLAIN TILE

Available in a range of fourteen natural shades, granular, through-coloured and acrylic coated, to match any roofing environment.

KEY ADVANTAGES

- Versatile concrete tile with wide scope for a variety of roofing effects
- Quick and easy to lay
- Smooth, coated and varnished finishes to blend with every regional roofing style

TECHNICAL DATA

Size (overall)	266 x 165mm
Minimum Pitch	35°
Maximum Pitch (subject to fixing specification)	90°
Minimum Headlap	Below 90° 65mm / at 90° 35mm
Maximum Headlap	88mm
Minimum Gauge/Batten Spacing	88mm
Maximum Gauge/Batten Spacing	below 90° 100mm / at 90° 115mm
Hanging Length (approx)	246mm
Cover (all figures are net and do not allow for wastage)	
Linear cover of 1 tile	165mm
Covering capacity	below 90° 60 tiles/m ² / at 90° 52 tiles/m ²
Weight (at max gauge approx)*	below 90° 75kg/m ² / at 90° 65kg/m ²
per pallet, including pallet (approx)	1.01 tonnes
per 1000	1.25 tonnes
Battens Required (at max gauge)	below 90° 10.0m/m ²
Batten Size	
Rafter centres up to 600mm	38 x 25mm
Fixing Clips	Top Tile Clips
Nail Size for Tiles*	40 x 2.65mm (A/A)
Pallet Quantities	Tiles per pallet 768 / Tiles per pack 16 / Packs per pallet 48

*All weights nominal. *(A/A) Aluminium Alloy

FITTINGS & ACCESSORIES

Granulated Tile	Clay Tile
Angles	External Angles
Hip	Universal Spurred Hip Third Round Hip Slate Ridge Dry Hip Rapid Hip
Valley	Universal Valley Tile 1:25 GPP Valley Dry Valley
Ridge	Half Round Ridge Half Round Corner Ridge
Ventilation Systems	Red Vent Saver Vent Re-Vent 25 Over Edge Vent Rapid Edge Vent Top Edge Absorbent Ventilation Dry Vent Ridge Dry Vent Matchedge Rapid Vent Ridge Dry Vent Rapid Ridge Hip Red Line Ventilation Tile Rapid Roof Vent 4 St. Through Vent Tile

ORNAMENTAL TILES, RIDGES AND FINIALS

Please refer to page 63.

COLOURS



PLAIN TILE | 02 Brown (Granular)

An established brown tile with a granulated finish popular across the UK.