



**Manufactured From**

Defender Ferritic - 1.4016 grade stainless steel, components – nylon and acetal.

Defender Austenitic - 1.4301 High Grade stainless steel, components – nylon and acetal.

**Recommended Screws**

Stainless steel No.8 or equivalent.

**Performance**

Tested in accordance with DD CEN/TS 13126-6:2004.

**Finishes**

Suffix product code with: /368 (Ferritic), /369 (Austenitic).

| Hinge Size (mm) | Max Sash Weight (Kg) | Max Sash Height (mm) | Min Sash Height (mm) | Restricted Opening Angle | Opening Angle ( + / - 2.5° ) |
|-----------------|----------------------|----------------------|----------------------|--------------------------|------------------------------|
| 615             | 40                   | 1300                 | 850                  | 6°                       | 37.5°                        |