

AEA - Ambiental		Page 1
Science Park Square Brighton East Sussex	4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations	
Date 20/05/2019	Designed by SD	
File 4501_MARMONT_EASTPRESTON_DRAINAGENETWORK.MDX	Checked by SB	
XP Solutions		Network 2018.1

STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Storm

« - Indicates pipe capacity < flow

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.000	6.426	0.043	150.0	0.000	4.00	0.0	0.600	o	150	Pipe/Conduit	
1.001	6.839	0.046	150.0	0.007	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.002	6.839	0.046	150.0	0.007	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.003	6.979	0.047	150.0	0.007	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.004	6.903	0.046	150.0	0.009	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.005	18.746	0.125	150.0	0.011	0.00	0.0	0.600	o	150	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	50.00	4.13	7.430	0.000	0.0	0.0	0.0	0.82	14.5	0.0
1.001	50.00	4.27	7.387	0.007	0.0	0.0	0.0	0.82	14.5	0.9
1.002	50.00	4.41	7.342	0.013	0.0	0.0	0.0	0.82	14.5	1.8
1.003	50.00	4.55	7.296	0.020	0.0	0.0	0.0	0.82	14.5	2.7
1.004	50.00	4.69	7.249	0.028	0.0	0.0	0.0	0.82	14.5	3.9
1.005	50.00	5.07	7.203	0.040	0.0	0.0	0.0	0.82	14.5	5.4

AEA - Ambiental										Page 2	
Science Park Square Brighton East Sussex					4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations						
Date 20/05/2019					Designed by SD						
File 4501_MARMONT_EASTPRESTON_DRAINAGENETWORK.MDX					Checked by SB						
XP Solutions					Network 2018.1						
<u>STORM SEWER DESIGN by the Modified Rational Method</u> <u>Network Design Table for Storm</u>											
PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
2.000	13.912	0.093	150.0	0.004	4.00	0.0	0.600	o	150	Pipe/Conduit	
2.001	5.470	0.036	150.0	0.008	0.00	0.0	0.600	o	150	Pipe/Conduit	
2.002	13.458	0.090	150.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
3.000	22.616	0.151	150.0	0.003	4.00	0.0	0.600	o	150	Pipe/Conduit	
2.003	10.049	0.178	56.4	0.009	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.006	11.516	0.029	400.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
<u>Network Results Table</u>											
PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)	
2.000	50.00	4.28	7.475	0.004	0.0	0.0	0.0	0.82	14.5	0.5	
2.001	50.00	4.39	7.382	0.012	0.0	0.0	0.0	0.82	14.5	1.6	
2.002	50.00	4.67	7.346	0.012	0.0	0.0	0.0	0.82	14.5	1.6	
3.000	50.00	4.46	7.570	0.003	0.0	0.0	0.0	0.82	14.5	0.4	
2.003	50.00	4.79	7.256	0.024	0.0	0.0	0.0	1.34	23.7	3.2	
1.006	50.00	5.46	7.078	0.063	0.0	0.0	0.0	0.50	8.8	8.6	
©1982-2018 Innovyze											

AEA - Ambiental										Page 3	
Science Park Square Brighton East Sussex					4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations						
Date 20/05/2019					Designed by SD						
File 4501_MARMONT_EASTPRESTON_DRAINAGENETWORK.MDX					Checked by SB						
XP Solutions					Network 2018.1						

STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.007	14.476	0.036	400.0	0.053	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.008	4.166	0.028	150.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.007	50.00	5.95	7.049	0.116	0.0	0.0	0.0	0.50	8.8«	15.7
1.008	50.00	6.03	7.013	0.116	0.0	0.0	0.0	0.82	14.5«	15.7

©1982-2018 Innovyze

AEA - Ambiental				Page 4		
Science Park Square		4501_Marmont_EastPreston				
Brighton		Marmont Developments Ltd				
East Sussex		Proposed Calculations				
Date 20/05/2019		Designed by SD				
File 4501_MARMONT_EASTPRESTON_DRAINAGENETWORK.MDX		Checked by SB				
XP Solutions		Network 2018.1				
Area Summary for Storm						
Pipe Number	PIMP Type	PIMP Name	PIMP (%)	Gross Area (ha)	Imp. Area (ha)	Pipe Total (ha)
1.000	-	-	100	0.000	0.000	0.000
1.001	User	-	100	0.007	0.007	0.007
1.002	User	-	100	0.007	0.007	0.007
1.003	User	-	100	0.007	0.007	0.007
1.004	User	-	100	0.009	0.009	0.009
1.005	User	-	100	0.011	0.011	0.011
2.000	User	-	100	0.004	0.004	0.004
2.001	User	-	100	0.003	0.003	0.003
	User	-	100	0.004	0.004	0.007
	User	-	100	0.000	0.000	0.008
	User	-	100	0.001	0.001	0.008
2.002	-	-	100	0.000	0.000	0.000
3.000	User	-	100	0.003	0.003	0.003
2.003	User	-	100	0.009	0.009	0.009
1.006	-	-	100	0.000	0.000	0.000
1.007	User	-	100	0.004	0.004	0.004
	User	-	100	0.004	0.004	0.008
	User	-	100	0.004	0.004	0.013
	User	-	100	0.001	0.001	0.014
	User	-	100	0.001	0.001	0.016
	User	-	100	0.001	0.001	0.017
	User	-	100	0.001	0.001	0.018
	User	-	100	0.001	0.001	0.018
	User	-	100	0.001	0.001	0.019
	User	-	100	0.001	0.001	0.020
	User	-	100	0.001	0.001	0.021
	User	-	100	0.032	0.032	0.053
©1982-2018 Innovyze						

AEA - Ambiental			Page 5																												
Science Park Square Brighton East Sussex	4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations																														
Date 20/05/2019	Designed by SD																														
File 4501_MARMONT_EASTPRESTON_DRAINAGENETWORK.MDX	Checked by SB																														
XP Solutions	Network 2018.1																														
Area Summary for Storm <table><thead><tr><th>Pipe Number</th><th>PIMP Type</th><th>PIMP Name</th><th>PIMP (%)</th><th>Gross Area (ha)</th><th>Imp. Area (ha)</th><th>Pipe Total (ha)</th></tr></thead><tbody><tr><td>1.008</td><td>-</td><td>-</td><td>100</td><td>0.000</td><td>0.000</td><td>0.000</td></tr><tr><td></td><td></td><td></td><td></td><td>Total</td><td>Total</td><td>Total</td></tr><tr><td></td><td></td><td></td><td></td><td>0.116</td><td>0.116</td><td>0.116</td></tr></tbody></table>				Pipe Number	PIMP Type	PIMP Name	PIMP (%)	Gross Area (ha)	Imp. Area (ha)	Pipe Total (ha)	1.008	-	-	100	0.000	0.000	0.000					Total	Total	Total					0.116	0.116	0.116
Pipe Number	PIMP Type	PIMP Name	PIMP (%)	Gross Area (ha)	Imp. Area (ha)	Pipe Total (ha)																									
1.008	-	-	100	0.000	0.000	0.000																									
				Total	Total	Total																									
				0.116	0.116	0.116																									
©1982-2018 Innovyze																															

AEA - Ambiantal		Page 6
Science Park Square Brighton East Sussex	4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations	
Date 20/05/2019	Designed by SD	
File 4501_MARMONT_EASTPRESTON_DRAINAGENETWORK.MDX	Checked by SB	
XP Solutions		Network 2018.1

Online Controls for Storm

Depth/Flow Relationship Manhole: 8, DS/PN: 1.008, Volume (m³): 0.6

Invert Level (m) 7.013

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.200	0.0000	1.200	0.0000	2.200	0.0000	3.200	0.0000	4.200	0.0000	5.200	0.0000
0.400	0.0000	1.400	0.0000	2.400	0.0000	3.400	0.0000	4.400	0.0000	5.400	0.0000
0.600	0.0000	1.600	0.0000	2.600	0.0000	3.600	0.0000	4.600	0.0000	5.600	0.0000
0.800	0.0000	1.800	0.0000	2.800	0.0000	3.800	0.0000	4.800	0.0000	5.800	0.0000
1.000	0.0000	2.000	0.0000	3.000	0.0000	4.000	0.0000	5.000	0.0000	6.000	0.0000

©1982-2018 Innovyze

AEA - Ambiental		Page 7																								
Science Park Square Brighton East Sussex	4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations																									
Date 20/05/2019	Designed by SD																									
File 4501_MARMONT_EASTPRESTON_DRAINAGENETWORK.MDX	Checked by SB																									
XP Solutions	Network 2018.1																									
Storage Structures for Storm Porous Car Park Manhole: PERMEABLE PAVING, DS/PN: 1.007 <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.01515</td><td>Porosity</td><td>0.30</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Invert Level (m)</td><td>6.592</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Max Percolation (l/s)</td><td>152.8</td><td>Width (m)</td><td>25.0</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Safety Factor</td><td>2.0</td><td>Length (m)</td><td>22.0</td><td>Membrane Depth (mm)</td><td>0</td></tr></table>			Infiltration Coefficient Base (m/hr)	0.01515	Porosity	0.30	Slope (1:X)	0.0	Membrane Percolation (mm/hr)	1000	Invert Level (m)	6.592	Depression Storage (mm)	5	Max Percolation (l/s)	152.8	Width (m)	25.0	Evaporation (mm/day)	3	Safety Factor	2.0	Length (m)	22.0	Membrane Depth (mm)	0
Infiltration Coefficient Base (m/hr)	0.01515	Porosity	0.30	Slope (1:X)	0.0																					
Membrane Percolation (mm/hr)	1000	Invert Level (m)	6.592	Depression Storage (mm)	5																					
Max Percolation (l/s)	152.8	Width (m)	25.0	Evaporation (mm/day)	3																					
Safety Factor	2.0	Length (m)	22.0	Membrane Depth (mm)	0																					
©1982-2018 Innovyze																										

AEA - Ambiental										Page 8																																	
Science Park Square Brighton East Sussex					4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations																																						
Date 20/05/2019					Designed by SD																																						
File 4501_MARMONT_EASTPRESTON_DRAINAGENETWORK.MDX					Checked by SB																																						
XP Solutions					Network 2018.1																																						
<u>2 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm</u>																																											
<u>Simulation Criteria</u>																																											
Areal Reduction Factor 1.000 Manhole Headloss Coeff (Global) 0.500 MADD Factor * 10m³/ha Storage 2.000																																											
Hot Start (mins) 0 Foul Sewage per hectare (l/s) 0.000 Inlet Coeffiecient 0.800																																											
Hot Start Level (mm) 0 Additional Flow - % of Total Flow 0.000 Flow per Person per Day (l/per/day) 0.000																																											
Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0																																											
Number of Online Controls 1 Number of Storage Structures 1 Number of Real Time Controls 0																																											
<u>Synthetic Rainfall Details</u>																																											
Rainfall Model FEH Site Location GB 506868 102558 Cv (Summer) 0.750																																											
FEH Rainfall Version 2013 Data Type Point Cv (Winter) 0.840																																											
Margin for Flood Risk Warning (mm) 0.0 DVD Status ON																																											
Analysis Timestep 2.5 Second Increment (Extended) Inertia Status ON																																											
DTS Status ON																																											
<u>Profile(s)</u>																																											
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080																																											
Return Period(s) (years) 2, 30, 100																																											
Climate Change (%) 40, 40, 40																																											
<table><tr><th colspan="2">US/MH</th><th rowspan="2">Event</th><th rowspan="2">Duration Storm (mins)</th><th rowspan="2">US/CL Rank</th><th rowspan="2">US/CL (m)</th><th colspan="2">Water Surcharged</th><th rowspan="2">Flow / Cap.</th><th rowspan="2">Maximum Vol (m³)</th><th rowspan="2">Discharge Vol (m³)</th><th colspan="2">Pipe Flow</th></tr><tr><th>PN</th><th>Name</th><th>Level (m)</th><th>Depth (m)</th><th>(l/s)</th><th>Status</th></tr><tr><td>1.000</td><td>1</td><td>360 minute 2 year Winter I+40%</td><td>360</td><td>1</td><td>8.180</td><td>7.430</td><td>-0.150</td><td>0.00</td><td>0.000</td><td>0.000</td><td>0.0</td><td>OK</td></tr></table>												US/MH		Event	Duration Storm (mins)	US/CL Rank	US/CL (m)	Water Surcharged		Flow / Cap.	Maximum Vol (m³)	Discharge Vol (m³)	Pipe Flow		PN	Name	Level (m)	Depth (m)	(l/s)	Status	1.000	1	360 minute 2 year Winter I+40%	360	1	8.180	7.430	-0.150	0.00	0.000	0.000	0.0	OK
US/MH		Event	Duration Storm (mins)	US/CL Rank	US/CL (m)	Water Surcharged		Flow / Cap.	Maximum Vol (m³)	Discharge Vol (m³)	Pipe Flow																																
PN	Name					Level (m)	Depth (m)				(l/s)	Status																															
1.000	1	360 minute 2 year Winter I+40%	360	1	8.180	7.430	-0.150	0.00	0.000	0.000	0.0	OK																															
©1982-2018 Innovyze																																											

AEA - Ambiental												Page 9	
Science Park Square Brighton East Sussex						4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations							
Date 20/05/2019						Designed by SD							
File 4501_MARMONT_EASTPRESTON_DRAINAGENETWORK.MDX						Checked by SB							
XP Solutions						Network 2018.1							
2 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm													
PN	US/MH Name	Event	Duration (mins)	Storm Rank	US/CL (m)	Water Level (m)	Surcharged Depth (m)	Flow / Cap.	Maximum Vol (m³)	Discharge Vol (m³)	Pipe Flow (l/s)	Status	
1.001		2 15 minute 2 year Winter I+40%	15	1	8.180	7.420	-0.117	0.11	0.023	0.750	1.4	OK	
1.002		3 15 minute 2 year Winter I+40%	15	1	8.180	7.390	-0.102	0.22	0.037	1.499	2.7	OK	
1.003		4 15 minute 2 year Winter I+40%	15	1	8.180	7.356	-0.090	0.33	0.047	2.253	4.1	OK	
1.004		5 15 minute 2 year Winter I+40%	15	1	8.500	7.330	-0.069	0.47	0.065	3.234	5.8	OK	
1.005		6 15 minute 2 year Winter I+40%	15	1	8.550	7.314	-0.039	0.58	0.091	4.498	7.9	OK	
2.000		13 15 minute 2 year Winter I+40%	15	1	8.225	7.501	-0.124	0.07	0.006	0.400	0.9	OK	
2.001		12 15 minute 2 year Winter I+40%	15	1	8.200	7.430	-0.102	0.22	0.046	1.362	2.7	OK	
2.002		11 15 minute 2 year Winter I+40%	15	1	8.180	7.391	-0.104	0.20	0.031	1.362	2.7	OK	
3.000		9 15 minute 2 year Winter I+40%	15	1	8.320	7.593	-0.127	0.05	0.005	0.328	0.8	OK	
2.003		10 15 minute 2 year Winter I+40%	15	1	8.200	7.307	-0.100	0.24	0.048	2.680	5.2	OK	
1.006		7 15 minute 2 year Winter I+40%	15	1	8.250	7.270	0.042	1.69	0.413	7.170	13.0	SURCHARGED	
1.007	PERMEABLE PAVING	360 minute 2 year Winter I+40%	360	1	8.200	6.728	-0.471	0.00	22.517	0.000	0.0	OK	
1.008		8 360 minute 2 year Winter I+40%	360	1	8.200	7.013	-0.150	0.00	0.000	0.000	0.0	OK	
©1982-2018 Innovyze													

AEA - Ambiental		Page 10
Science Park Square Brighton East Sussex	4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations	
Date 20/05/2019	Designed by SD	
File 4501_MARMONT_EASTPRESTON_DRAINAGENETWORK.MDX	Checked by SB	
XP Solutions		Network 2018.1

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Manhole Headloss Coeff (Global) 0.500 MADD Factor * 10m³/ha Storage 2.000
 Hot Start (mins) 0 Foul Sewage per hectare (l/s) 0.000 Inlet Coefficient 0.800
 Hot Start Level (mm) 0 Additional Flow - % of Total Flow 0.000 Flow per Person per Day (l/per/day) 0.000

Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0
 Number of Online Controls 1 Number of Storage Structures 1 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH Site Location GB 506868 102558 Cv (Summer) 0.750
 FEH Rainfall Version 2013 Data Type Point Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 0.0 DVD Status ON
 Analysis Timestep 2.5 Second Increment (Extended) Inertia Status ON
 DTS Status ON

Profile(s)

Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880,
 4320, 5760, 7200, 8640, 10080

Return Period(s) (years) 2, 30, 100
 Climate Change (%) 40, 40, 40

PN	US/MH Name	Event	Duration (mins)	Storm Rank	US/CL (m)	Water Surcharged			Pipe			Status
						Level (m)	Depth (m)	Flow / Cap.	Maximum Vol (m³)	Discharge Vol (m³)	Flow (l/s)	
1.000	1	15 minute 30 year Winter I+40%	15	1	8.180	7.854	0.274	0.05	0.119	0.001	0.6	SURCHARGED

©1982-2018 Innovyze

AEA - Ambiental														Page 11	
Science Park Square Brighton East Sussex								4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations							
Date 20/05/2019								Designed by SD							
File 4501_MARMONT_EASTPRESTON_DRAINAGENETWORK.MDX								Checked by SB							
XP Solutions								Network 2018.1							
30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm															
PN	US/MH Name	Event				Duration (mins)	Storm Rank	US/CL (m)	Water Level (m)	Surcharged Depth (m)	Flow / Cap.	Maximum Vol (m³)	Discharge Vol (m³)	Pipe Flow (l/s)	Status
1.001		2	15 minute	30 year	Winter I+40%	15	1	8.180	7.855	0.318	0.25	0.234	1.663	3.1	SURCHARGED
1.002		3	15 minute	30 year	Winter I+40%	15	1	8.180	7.848	0.356	0.49	0.252	3.326	6.0	SURCHARGED
1.003		4	15 minute	30 year	Winter I+40%	15	1	8.180	7.833	0.387	0.72	0.261	4.997	8.9	SURCHARGED
1.004		5	15 minute	30 year	Winter I+40%	15	1	8.500	7.809	0.409	1.02	0.269	7.175	12.6	SURCHARGED
1.005		6	15 minute	30 year	Winter I+40%	15	1	8.550	7.758	0.405	1.30	0.267	9.982	17.7	SURCHARGED
2.000		13	15 minute	30 year	Winter I+40%	15	1	8.225	7.612	-0.013	0.14	0.037	0.887	1.9	OK
2.001		12	15 minute	30 year	Winter I+40%	15	1	8.200	7.606	0.073	0.45	0.288	3.022	5.4	SURCHARGED
2.002		11	15 minute	30 year	Winter I+40%	15	1	8.180	7.594	0.098	0.41	0.155	3.022	5.5	SURCHARGED
3.000		9	15 minute	30 year	Winter I+40%	15	1	8.320	7.605	-0.115	0.12	0.008	0.727	1.7	OK
2.003		10	15 minute	30 year	Winter I+40%	15	1	8.200	7.573	0.166	0.47	0.499	5.943	9.9	SURCHARGED
1.006		7	15 minute	30 year	Winter I+40%	15	1	8.250	7.535	0.307	3.54	0.616	15.928	27.2	SURCHARGED
1.007	PERMEABLE PAVING	240	minute	30 year	Winter I+40%	240	1	8.200	6.908	-0.291	0.00	52.194	0.000	0.0	OK
1.008		8	360 minute	30 year	Winter I+40%	360	1	8.200	7.013	-0.150	0.00	0.000	0.000	0.0	OK
©1982-2018 Innovyze															

AEA - Ambiental										Page 12																															
Science Park Square Brighton East Sussex					4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations																																				
Date 20/05/2019					Designed by SD																																				
File 4501_MARMONT_EASTPRESTON_DRAINAGENETWORK.MDX					Checked by SB																																				
XP Solutions					Network 2018.1																																				
100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm																																									
Simulation Criteria Areal Reduction Factor 1.000 Manhole Headloss Coeff (Global) 0.500 MADD Factor * 10m³/ha Storage 2.000 Hot Start (mins) 0 Foul Sewage per hectare (l/s) 0.000 Inlet Coeffiecient 0.800 Hot Start Level (mm) 0 Additional Flow - % of Total Flow 0.000 Flow per Person per Day (l/per/day) 0.000 Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0 Number of Online Controls 1 Number of Storage Structures 1 Number of Real Time Controls 0																																									
Synthetic Rainfall Details Rainfall Model FEH Site Location GB 506868 102558 Cv (Summer) 0.750 FEH Rainfall Version 2013 Data Type Point Cv (Winter) 0.840 Margin for Flood Risk Warning (mm) 0.0 DVD Status ON Analysis Timestep 2.5 Second Increment (Extended) Inertia Status ON DTS Status ON Profile(s) Summer and Winter Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080 Return Period(s) (years) 2, 30, 100 Climate Change (%) 40, 40, 40																																									
<table><tr><th colspan="2">US/MH</th><th rowspan="2">Event</th><th rowspan="2">Duration (mins)</th><th rowspan="2">Storm Rank</th><th rowspan="2">US/CL (m)</th><th colspan="2">Water Surcharged</th><th rowspan="2">Flow / Cap.</th><th rowspan="2">Maximum Vol (m³)</th><th rowspan="2">Discharge Vol (m³)</th><th rowspan="2">Pipe Flow (l/s)</th><th rowspan="2">Status</th></tr><tr><th>PN</th><th>Name</th><th>Level (m)</th><th>Depth (m)</th></tr><tr><td>1.000</td><td>1 15 minute 100 year Winter I+40%</td><td></td><td>15</td><td>1</td><td>8.180</td><td>8.165</td><td>0.585</td><td>0.07</td><td>0.206</td><td>0.001</td><td>0.8</td><td>SURCHARGED</td></tr></table>												US/MH		Event	Duration (mins)	Storm Rank	US/CL (m)	Water Surcharged		Flow / Cap.	Maximum Vol (m³)	Discharge Vol (m³)	Pipe Flow (l/s)	Status	PN	Name	Level (m)	Depth (m)	1.000	1 15 minute 100 year Winter I+40%		15	1	8.180	8.165	0.585	0.07	0.206	0.001	0.8	SURCHARGED
US/MH		Event	Duration (mins)	Storm Rank	US/CL (m)	Water Surcharged		Flow / Cap.	Maximum Vol (m³)	Discharge Vol (m³)	Pipe Flow (l/s)	Status																													
PN	Name					Level (m)	Depth (m)																																		
1.000	1 15 minute 100 year Winter I+40%		15	1	8.180	8.165	0.585	0.07	0.206	0.001	0.8	SURCHARGED																													
©1982-2018 Innovyze																																									

AEA - Ambiental													Page 13	
Science Park Square Brighton East Sussex						4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations								
Date 20/05/2019						Designed by SD								
File 4501_MARMONT_EASTPRESTON_DRAINAGENETWORK.MDX						Checked by SB								
XP Solutions						Network 2018.1								
100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm														
PN	US/MH Name	Event	Duration (mins)	Storm Rank	US/CL (m)	Water Level (m)	Surcharged Depth (m)	Flow / Cap.	Maximum Vol (m³)	Discharge Vol (m³)	Pipe Flow (l/s)	Status		
1.001		2 15 minute 100 year Winter I+40%	15	1	8.180	8.166	0.629	0.32	0.322	2.110	4.0	SURCHARGED		
1.002		3 15 minute 100 year Winter I+40%	15	1	8.180	8.158	0.666	0.59	0.340	4.219	7.3	SURCHARGED		
1.003		4 15 minute 100 year Winter I+40%	15	1	8.180	8.139	0.693	0.87	0.347	6.339	10.7	SURCHARGED		
1.004		5 15 minute 100 year Winter I+40%	15	1	8.500	8.105	0.706	1.23	0.353	9.101	15.2	SURCHARGED		
1.005		6 15 minute 100 year Winter I+40%	15	1	8.550	8.034	0.681	1.57	0.345	12.663	21.3	SURCHARGED		
2.000		13 15 minute 100 year Winter I+40%	15	1	8.225	7.827	0.202	0.15	0.098	1.125	2.0	SURCHARGED		
2.001		12 15 minute 100 year Winter I+40%	15	1	8.200	7.820	0.288	0.57	0.358	3.832	6.8	SURCHARGED		
2.002		11 15 minute 100 year Winter I+40%	15	1	8.180	7.806	0.311	0.48	0.215	3.832	6.3	SURCHARGED		
3.000		9 15 minute 100 year Winter I+40%	15	1	8.320	7.789	0.069	0.14	0.060	0.922	2.0	SURCHARGED		
2.003		10 15 minute 100 year Winter I+40%	15	1	8.200	7.782	0.375	0.58	0.763	7.537	12.2	SURCHARGED		
1.006		7 15 minute 100 year Winter I+40%	15	1	8.250	7.716	0.488	4.36	0.667	20.202	33.5	SURCHARGED		
1.007	PERMEABLE PAVING	360 minute 100 year Winter I+40%	360	1	8.200	7.006	-0.193	0.00	68.393	0.000	0.0	OK		
1.008		8 360 minute 100 year Winter I+40%	360	1	8.200	7.013	-0.150	0.00	0.000	0.000	0.0	OK		
©1982-2018 Innovyze														