

AEA - Ambiental		Page 1												
Science Park Square Brighton East Sussex	4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations - REV B													
Date 12/07/2019	Designed by SD													
File 4501_Marmont_EastPreston_DrainageNetwork_...	Checked by													
XP Solutions		Network 2018.1												
<u>Time Area Diagram for Storm</u> <table border="1"> <thead> <tr> <th>Time (mins)</th> <th>Area (ha)</th> <th>Time (mins)</th> <th>Area (ha)</th> <th>Time (mins)</th> <th>Area (ha)</th> </tr> </thead> <tbody> <tr> <td>0-4</td> <td>0.057</td> <td>4-8</td> <td>0.059</td> <td>8-12</td> <td>0.000</td> </tr> </tbody> </table> Total Area Contributing (ha) = 0.116 Total Pipe Volume (m³) = 2.716			Time (mins)	Area (ha)	Time (mins)	Area (ha)	Time (mins)	Area (ha)	0-4	0.057	4-8	0.059	8-12	0.000
Time (mins)	Area (ha)	Time (mins)	Area (ha)	Time (mins)	Area (ha)									
0-4	0.057	4-8	0.059	8-12	0.000									
©1982-2018 Innovyze														

AEA - Ambiental										Page 2	
Science Park Square Brighton East Sussex					4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations - REV B						
Date 12/07/2019					Designed by SD						
File 4501_Marmont_EastPreston_DrainageNetwork_...					Checked by						
XP Solutions					Network 2018.1						

STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Storm

« - Indicates pipe capacity < flow

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.000	7.320	0.049	150.0	0.002	4.00	0.0	0.600	o	150	Pipe/Conduit	
1.001	11.626	0.078	150.0	0.002	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.002	7.026	0.047	150.0	0.002	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.003	17.869	0.119	150.0	0.014	0.00	0.0	0.600	o	150	Pipe/Conduit	
2.000	12.288	0.154	80.0	0.005	4.00	0.0	0.600	o	150	Pipe/Conduit	
2.001	13.672	0.137	100.0	0.006	0.00	0.0	0.600	o	150	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	50.00	4.15	7.430	0.002	0.0	0.0	0.0	0.82	14.5	0.2
1.001	50.00	4.39	7.381	0.004	0.0	0.0	0.0	0.82	14.5	0.5
1.002	50.00	4.53	7.303	0.006	0.0	0.0	0.0	0.82	14.5	0.8
1.003	50.00	4.89	7.253	0.020	0.0	0.0	0.0	0.82	14.5	2.7
2.000	50.00	4.18	7.500	0.005	0.0	0.0	0.0	1.12	19.9	0.6
2.001	50.00	4.41	7.346	0.011	0.0	0.0	0.0	1.00	17.8	1.5

©1982-2018 Innovyze

AEA - Ambiental										Page 3	
Science Park Square Brighton East Sussex					4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations - REV B						
Date 12/07/2019					Designed by SD						
File 4501_Marmont_EastPreston_DrainageNetwork_...					Checked by						
XP Solutions					Network 2018.1						
STORM SEWER DESIGN by the Modified Rational Method											
Network Design Table for Storm											
PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.004	11.946	0.000	0.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
3.000	10.882	0.109	100.0	0.004	4.00	0.0	0.600	o	150	Pipe/Conduit	
3.001	8.274	0.083	100.0	0.004	0.00	0.0	0.600	o	150	Pipe/Conduit	
3.002	6.502	0.000	0.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
4.000	11.015	0.110	100.0	0.004	4.00	0.0	0.600	o	150	Pipe/Conduit	
4.001	7.893	0.079	100.0	0.004	0.00	0.0	0.600	o	150	Pipe/Conduit	
Network Results Table											
PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)	
1.004	50.00	7.04	7.420	0.031	0.0	0.0	0.0	0.09	1.6«	4.2	
3.000	50.00	4.18	7.500	0.004	0.0	0.0	0.0	1.00	17.8	0.6	
3.001	50.00	4.32	7.391	0.008	0.0	0.0	0.0	1.00	17.8	1.1	
3.002	50.00	5.49	7.420	0.008	0.0	0.0	0.0	0.09	1.6	1.1	
4.000	50.00	4.18	7.500	0.004	0.0	0.0	0.0	1.00	17.8	0.5	
4.001	50.00	4.31	7.390	0.008	0.0	0.0	0.0	1.00	17.8	1.1	
©1982-2018 Innovyze											

AEA - Ambiental										Page 4																																																																																													
Science Park Square Brighton East Sussex					4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations - REV B																																																																																																		
Date 12/07/2019					Designed by SD																																																																																																		
File 4501_Marmont_EastPreston_DrainageNetwork_...					Checked by																																																																																																		
XP Solutions					Network 2018.1																																																																																																		
<u>STORM SEWER DESIGN by the Modified Rational Method</u> <u>Network Design Table for Storm</u> <table><tr><th>PN</th><th>Length (m)</th><th>Fall (m)</th><th>Slope (1:X)</th><th>I.Area (ha)</th><th>T.E. (mins)</th><th>Base Flow (l/s)</th><th>k (mm)</th><th>HYD SECT</th><th>DIA (mm)</th><th>Section Type</th><th>Auto Design</th></tr><tr><td>3.003</td><td>8.049</td><td>0.000</td><td>0.0</td><td>0.000</td><td>0.00</td><td>0.0</td><td>0.600</td><td>o</td><td>150</td><td>Pipe/Conduit</td><td></td></tr><tr><td>5.000</td><td>13.909</td><td>0.000</td><td>0.0</td><td>0.002</td><td>4.00</td><td>0.0</td><td>0.600</td><td>o</td><td>150</td><td>Pipe/Conduit</td><td></td></tr><tr><td>1.005</td><td>5.436</td><td>0.000</td><td>0.0</td><td>0.067</td><td>0.00</td><td>0.0</td><td>0.600</td><td>o</td><td>150</td><td>Pipe/Conduit</td><td></td></tr></table> <u>Network Results Table</u> <table><tr><th>PN</th><th>Rain (mm/hr)</th><th>T.C. (mins)</th><th>US/IL (m)</th><th>Σ I.Area (ha)</th><th>Σ Base Flow (l/s)</th><th>Foul (l/s)</th><th>Add Flow (l/s)</th><th>Vel (m/s)</th><th>Cap (l/s)</th><th>Flow (l/s)</th></tr><tr><td>3.003</td><td>50.00</td><td>6.93</td><td>7.420</td><td>0.016</td><td>0.0</td><td>0.0</td><td>0.0</td><td>0.09</td><td>1.6«</td><td>2.2</td></tr><tr><td>5.000</td><td>50.00</td><td>6.50</td><td>7.420</td><td>0.002</td><td>0.0</td><td>0.0</td><td>0.0</td><td>0.09</td><td>1.6</td><td>0.2</td></tr><tr><td>1.005</td><td>50.00</td><td>8.02</td><td>7.350</td><td>0.116</td><td>0.0</td><td>0.0</td><td>0.0</td><td>0.09</td><td>1.6«</td><td>15.7</td></tr></table>												PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design	3.003	8.049	0.000	0.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit		5.000	13.909	0.000	0.0	0.002	4.00	0.0	0.600	o	150	Pipe/Conduit		1.005	5.436	0.000	0.0	0.067	0.00	0.0	0.600	o	150	Pipe/Conduit		PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)	3.003	50.00	6.93	7.420	0.016	0.0	0.0	0.0	0.09	1.6«	2.2	5.000	50.00	6.50	7.420	0.002	0.0	0.0	0.0	0.09	1.6	0.2	1.005	50.00	8.02	7.350	0.116	0.0	0.0	0.0	0.09	1.6«	15.7
PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design																																																																																												
3.003	8.049	0.000	0.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit																																																																																													
5.000	13.909	0.000	0.0	0.002	4.00	0.0	0.600	o	150	Pipe/Conduit																																																																																													
1.005	5.436	0.000	0.0	0.067	0.00	0.0	0.600	o	150	Pipe/Conduit																																																																																													
PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)																																																																																													
3.003	50.00	6.93	7.420	0.016	0.0	0.0	0.0	0.09	1.6«	2.2																																																																																													
5.000	50.00	6.50	7.420	0.002	0.0	0.0	0.0	0.09	1.6	0.2																																																																																													
1.005	50.00	8.02	7.350	0.116	0.0	0.0	0.0	0.09	1.6«	15.7																																																																																													
©1982-2018 Innovyze																																																																																																							

AEA - Ambiantal				Page 5																																																																																																																																						
Science Park Square		4501_Marmont_EastPreston																																																																																																																																								
Brighton		Marmont Developments Ltd																																																																																																																																								
East Sussex		Proposed Calculations - REV B																																																																																																																																								
Date 12/07/2019		Designed by SD																																																																																																																																								
File 4501_Marmont_EastPreston_DrainageNetwork_...		Checked by																																																																																																																																								
XP Solutions		Network 2018.1																																																																																																																																								
Area Summary for Storm <table><thead><tr><th>Pipe Number</th><th>PIMP Type</th><th>PIMP Name</th><th>PIMP (%)</th><th>Gross Area (ha)</th><th>Imp. Area (ha)</th><th>Pipe Total (ha)</th></tr></thead><tbody><tr><td>1.000</td><td>User</td><td>-</td><td>100</td><td>0.002</td><td>0.002</td><td>0.002</td></tr><tr><td>1.001</td><td>User</td><td>-</td><td>100</td><td>0.002</td><td>0.002</td><td>0.002</td></tr><tr><td>1.002</td><td>User</td><td>-</td><td>100</td><td>0.002</td><td>0.002</td><td>0.002</td></tr><tr><td>1.003</td><td>User</td><td>-</td><td>100</td><td>0.003</td><td>0.003</td><td>0.003</td></tr><tr><td></td><td>User</td><td>-</td><td>100</td><td>0.011</td><td>0.011</td><td>0.014</td></tr><tr><td>2.000</td><td>User</td><td>-</td><td>100</td><td>0.005</td><td>0.005</td><td>0.005</td></tr><tr><td>2.001</td><td>User</td><td>-</td><td>100</td><td>0.006</td><td>0.006</td><td>0.006</td></tr><tr><td>1.004</td><td>-</td><td>-</td><td>100</td><td>0.000</td><td>0.000</td><td>0.000</td></tr><tr><td>3.000</td><td>User</td><td>-</td><td>100</td><td>0.004</td><td>0.004</td><td>0.004</td></tr><tr><td>3.001</td><td>User</td><td>-</td><td>100</td><td>0.004</td><td>0.004</td><td>0.004</td></tr><tr><td>3.002</td><td>-</td><td>-</td><td>100</td><td>0.000</td><td>0.000</td><td>0.000</td></tr><tr><td>4.000</td><td>User</td><td>-</td><td>100</td><td>0.004</td><td>0.004</td><td>0.004</td></tr><tr><td>4.001</td><td>User</td><td>-</td><td>100</td><td>0.004</td><td>0.004</td><td>0.004</td></tr><tr><td>3.003</td><td>-</td><td>-</td><td>100</td><td>0.000</td><td>0.000</td><td>0.000</td></tr><tr><td>5.000</td><td>User</td><td>-</td><td>100</td><td>0.002</td><td>0.002</td><td>0.002</td></tr><tr><td>1.005</td><td>User</td><td>-</td><td>100</td><td>0.067</td><td>0.067</td><td>0.067</td></tr><tr><td></td><td></td><td></td><td></td><td>Total</td><td>Total</td><td>Total</td></tr><tr><td></td><td></td><td></td><td></td><td>0.116</td><td>0.116</td><td>0.116</td></tr></tbody></table>						Pipe Number	PIMP Type	PIMP Name	PIMP (%)	Gross Area (ha)	Imp. Area (ha)	Pipe Total (ha)	1.000	User	-	100	0.002	0.002	0.002	1.001	User	-	100	0.002	0.002	0.002	1.002	User	-	100	0.002	0.002	0.002	1.003	User	-	100	0.003	0.003	0.003		User	-	100	0.011	0.011	0.014	2.000	User	-	100	0.005	0.005	0.005	2.001	User	-	100	0.006	0.006	0.006	1.004	-	-	100	0.000	0.000	0.000	3.000	User	-	100	0.004	0.004	0.004	3.001	User	-	100	0.004	0.004	0.004	3.002	-	-	100	0.000	0.000	0.000	4.000	User	-	100	0.004	0.004	0.004	4.001	User	-	100	0.004	0.004	0.004	3.003	-	-	100	0.000	0.000	0.000	5.000	User	-	100	0.002	0.002	0.002	1.005	User	-	100	0.067	0.067	0.067					Total	Total	Total					0.116	0.116	0.116
Pipe Number	PIMP Type	PIMP Name	PIMP (%)	Gross Area (ha)	Imp. Area (ha)	Pipe Total (ha)																																																																																																																																				
1.000	User	-	100	0.002	0.002	0.002																																																																																																																																				
1.001	User	-	100	0.002	0.002	0.002																																																																																																																																				
1.002	User	-	100	0.002	0.002	0.002																																																																																																																																				
1.003	User	-	100	0.003	0.003	0.003																																																																																																																																				
	User	-	100	0.011	0.011	0.014																																																																																																																																				
2.000	User	-	100	0.005	0.005	0.005																																																																																																																																				
2.001	User	-	100	0.006	0.006	0.006																																																																																																																																				
1.004	-	-	100	0.000	0.000	0.000																																																																																																																																				
3.000	User	-	100	0.004	0.004	0.004																																																																																																																																				
3.001	User	-	100	0.004	0.004	0.004																																																																																																																																				
3.002	-	-	100	0.000	0.000	0.000																																																																																																																																				
4.000	User	-	100	0.004	0.004	0.004																																																																																																																																				
4.001	User	-	100	0.004	0.004	0.004																																																																																																																																				
3.003	-	-	100	0.000	0.000	0.000																																																																																																																																				
5.000	User	-	100	0.002	0.002	0.002																																																																																																																																				
1.005	User	-	100	0.067	0.067	0.067																																																																																																																																				
				Total	Total	Total																																																																																																																																				
				0.116	0.116	0.116																																																																																																																																				
©1982-2018 Innovyze																																																																																																																																										

AEA - Ambiental		Page 6
Science Park Square Brighton East Sussex	4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations - REV B	
Date 12/07/2019	Designed by SD	
File 4501_Marmont_EastPreston_DrainageNetwork_...	Checked by	
XP Solutions		Network 2018.1

Storage Structures for Storm

Complex Manhole: COMPLEX, DS/PN: 1.005

Cellular Storage

Invert Level (m) 6.550 Infiltration Coefficient Side (m/hr) 0.00385 Porosity 0.95
Infiltration Coefficient Base (m/hr) 0.00000 Safety Factor 3.0

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	24.5	24.5	1.200	24.5	49.7	1.201	0.0	49.7

Porous Car Park

Infiltration Coefficient Base (m/hr)	0.01516	Porosity	0.30	Slope (1:X)	0.0
Membrane Percolation (mm/hr)	1000	Invert Level (m)	7.570	Depression Storage (mm)	5
Max Percolation (l/s)	152.8	Width (m)	22.0	Evaporation (mm/day)	3
Safety Factor	3.0	Length (m)	25.0	Cap Volume Depth (m)	0.418

©1982-2018 Innovyze

AEA - Ambiantal		Page 7
Science Park Square Brighton East Sussex	4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations - REV B	
Date 12/07/2019	Designed by SD	
File 4501_Marmont_EastPreston_DrainageNetwork_...	Checked by	
XP Solutions		Network 2018.1

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Manhole Headloss Coeff (Global) 0.500 MADD Factor * 10m³/ha Storage 2.000
 Hot Start (mins) 0 Foul Sewage per hectare (l/s) 0.000 Inlet Coefficient 0.800
 Hot Start Level (mm) 0 Additional Flow - % of Total Flow 0.000 Flow per Person per Day (l/per/day) 0.000

Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0
 Number of Online Controls 1 Number of Storage Structures 1 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH Site Location GB 506868 102558 Cv (Summer) 0.750
 FEH Rainfall Version 2013 Data Type Point Cv (Winter) 1.000

Margin for Flood Risk Warning (mm) 0.0 DVD Status ON
 Analysis Timestep 2.5 Second Increment (Extended) Inertia Status ON
 DTS Status ON

Profile(s) Winter
 Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880,
 4320, 5760, 7200, 8640, 10080
 Return Period(s) (years) 2, 30, 100
 Climate Change (%) 40, 40, 40

US/MH		Duration (mins)	Storm Rank	US/CL (m)	Water Surcharged		Flow / Cap.	Maximum Vol (m³)	Discharge Vol (m³)	Pipe	Status
PN	Name				Event	Level (m)				Depth (m)	
1.000	1-0 1440 minute 2 year Winter I+40%	1440	1	8.180	7.644	0.064	0.00	0.033	1.032	0.0	SURCHARGED

©1982-2018 Innovyze

AEA - Ambiental		Page 8
Science Park Square Brighton East Sussex	4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations - REV B	
Date 12/07/2019	Designed by SD	
File 4501_Marmont_EastPreston_DrainageNetwork_...	Checked by	
XP Solutions	Network 2018.1	

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Event	Duration (mins)	Storm Rank	US/CL (m)	Water Surcharged		Flow / Cap.	Maximum Vol (m³)	Discharge Vol (m³)	Pipe	
						Level (m)	Depth (m)				Flow (l/s)	Status
1.001	1-1	1440 minute 2 year Winter I+40%	1440	1	8.180	7.644	0.113	0.01	0.162	1.903	0.1	SURCHARGED
1.002	1-2	1440 minute 2 year Winter I+40%	1440	1	8.500	7.644	0.191	0.01	0.291	2.922	0.2	SURCHARGED
1.003	1-3	1440 minute 2 year Winter I+40%	1440	1	8.550	7.644	0.241	0.03	0.223	10.922	0.4	SURCHARGED
2.000	4-0	1440 minute 2 year Winter I+40%	1440	1	8.250	7.644	-0.006	0.00	0.039	2.584	0.1	OK
2.001	4-1	1440 minute 2 year Winter I+40%	1440	1	8.120	7.644	0.148	0.01	0.286	5.946	0.2	SURCHARGED
1.004	1-4	1440 minute 2 year Winter I+40%	1440	1	8.250	7.644	0.074	0.10	0.679	16.181	0.5	SURCHARGED
3.000	2-0	1440 minute 2 year Winter I+40%	1440	1	8.250	7.644	-0.006	0.00	0.022	2.356	0.1	OK
3.001	2-1	1440 minute 2 year Winter I+40%	1440	1	8.320	7.644	0.103	0.01	0.216	4.667	0.1	SURCHARGED
3.002	2-2	1440 minute 2 year Winter I+40%	1440	1	8.150	7.644	0.074	0.02	0.230	4.472	0.2	SURCHARGED
4.000	3-0	1440 minute 2 year Winter I+40%	1440	1	8.250	7.643	-0.007	0.00	0.039	2.032	0.1	OK
4.001	3-1	1440 minute 2 year Winter I+40%	1440	1	8.320	7.644	0.104	0.01	0.217	4.313	0.1	SURCHARGED
3.003	2-3	1440 minute 2 year Winter I+40%	1440	1	8.150	7.644	0.074	0.04	0.327	8.509	0.3	SURCHARGED
5.000	5-0	1440 minute 2 year Winter I+40%	1440	1	8.150	7.643	0.073	0.01	0.062	1.008	0.0	SURCHARGED
1.005	COMPLEX	1440 minute 2 year Winter I+40%	1440	1	8.050	7.643	0.143	0.00	38.226	0.000	0.0	SURCHARGED

AEA - Ambiental		Page 9
Science Park Square Brighton East Sussex	4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations - REV B	
Date 12/07/2019	Designed by SD	
File 4501_Marmont_EastPreston_DrainageNetwork_...	Checked by	
XP Solutions		Network 2018.1

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Manhole Headloss Coeff (Global) 0.500 MADD Factor * 10m³/ha Storage 2.000
 Hot Start (mins) 0 Foul Sewage per hectare (l/s) 0.000 Inlet Coefficient 0.800
 Hot Start Level (mm) 0 Additional Flow - % of Total Flow 0.000 Flow per Person per Day (l/per/day) 0.000

Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0
 Number of Online Controls 1 Number of Storage Structures 1 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH Site Location GB 506868 102558 Cv (Summer) 0.750
 FEH Rainfall Version 2013 Data Type Point Cv (Winter) 1.000

Margin for Flood Risk Warning (mm) 0.0 DVD Status ON
 Analysis Timestep 2.5 Second Increment (Extended) Inertia Status ON
 DTS Status ON

Profile(s)

Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080
 Return Period(s) (years) 2, 30, 100
 Climate Change (%) 40, 40, 40

PN	US/MH Name	Event	Duration (mins)	Storm Rank	US/CL (m)	Water Surcharged			Pipe			Status
						Level (m)	Depth (m)	Flow / Cap.	Maximum Vol (m³)	Discharge Vol (m³)	Flow (l/s)	
1.000	1-0 15 minute	30 year Winter I+40%	15	1	8.180	7.898	0.318	0.10	0.074	0.520	1.2	SURCHARGED

©1982-2018 Innovyze

AEA - Ambiental		Page 10
Science Park Square Brighton East Sussex	4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations - REV B	
Date 12/07/2019	Designed by SD	
File 4501_Marmont_EastPreston_DrainageNetwork_...	Checked by	
XP Solutions		Network 2018.1

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name		Event	Duration (mins)	Storm Rank	US/CL (m)	Water Surcharged		Flow / Cap.	Maximum Vol (m³)	Discharge Vol (m³)	Pipe	
							Level (m)	Depth (m)				Flow (l/s)	Status
1.001	1-1	15 minute	30 year Winter I+40%	15	1	8.180	7.894	0.363	0.18	0.202	0.887	2.4	SURCHARGED
1.002	1-2	15 minute	30 year Winter I+40%	15	1	8.500	7.886	0.433	0.32	0.359	1.281	3.9	SURCHARGED
1.003	1-3	15 minute	30 year Winter I+40%	15	1	8.550	7.875	0.472	0.95	0.288	5.306	12.9	SURCHARGED
2.000	4-0	720 minute	30 year Winter I+40%	720	1	8.250	7.838	0.188	0.01	0.094	3.811	0.2	SURCHARGED
2.001	4-1	720 minute	30 year Winter I+40%	720	1	8.120	7.837	0.341	0.03	0.344	8.859	0.5	SURCHARGED
1.004	1-4	720 minute	30 year Winter I+40%	720	1	8.250	7.838	0.268	0.29	0.734	24.643	1.5	SURCHARGED
3.000	2-0	720 minute	30 year Winter I+40%	720	1	8.250	7.837	0.187	0.01	0.053	3.482	0.2	SURCHARGED
3.001	2-1	720 minute	30 year Winter I+40%	720	1	8.320	7.837	0.296	0.03	0.255	6.924	0.4	SURCHARGED
3.002	2-2	720 minute	30 year Winter I+40%	720	1	8.150	7.837	0.267	0.05	0.285	6.690	0.4	SURCHARGED
4.000	3-0	720 minute	30 year Winter I+40%	720	1	8.250	7.837	0.187	0.01	0.094	2.992	0.2	SURCHARGED
4.001	3-1	720 minute	30 year Winter I+40%	720	1	8.320	7.837	0.297	0.02	0.256	6.365	0.4	SURCHARGED
3.003	2-3	720 minute	30 year Winter I+40%	720	1	8.150	7.837	0.267	0.12	0.382	12.713	0.8	SURCHARGED
5.000	5-0	720 minute	30 year Winter I+40%	720	1	8.150	7.836	0.266	0.02	0.116	1.493	0.1	SURCHARGED
1.005	COMPLEX	720 minute	30 year Winter I+40%	720	1	8.050	7.836	0.336	0.00	72.803	0.000	0.0	SURCHARGED

AEA - Ambiantal		Page 11
Science Park Square Brighton East Sussex	4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations - REV B	
Date 12/07/2019	Designed by SD	
File 4501_Marmont_EastPreston_DrainageNetwork_...	Checked by	
XP Solutions		Network 2018.1

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Manhole Headloss Coeff (Global) 0.500 MADD Factor * 10m³/ha Storage 2.000
 Hot Start (mins) 0 Foul Sewage per hectare (l/s) 0.000 Inlet Coefficient 0.800
 Hot Start Level (mm) 0 Additional Flow - % of Total Flow 0.000 Flow per Person per Day (l/per/day) 0.000

Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0
 Number of Online Controls 1 Number of Storage Structures 1 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH Site Location GB 506868 102558 Cv (Summer) 0.750
 FEH Rainfall Version 2013 Data Type Point Cv (Winter) 1.000

Margin for Flood Risk Warning (mm) 0.0 DVD Status ON
 Analysis Timestep 2.5 Second Increment (Extended) Inertia Status ON
 DTS Status ON

Profile(s)

Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080
 Return Period(s) (years) 2, 30, 100
 Climate Change (%) 40, 40, 40

PN	US/MH Name	Event	Duration (mins)	Storm Rank	US/CL (m)	Water Surcharged			Flow / Cap.	Maximum Vol (m³)	Discharge Vol (m³)	Pipe Flow (l/s)	Status
						Level (m)	Depth (m)						
1.000	1-0 15 minute	100 year Winter I+40%	15	1	8.180	8.072	0.492	0.12	0.101	0.660	1.5	SURCHARGED	

©1982-2018 Innovyze

AEA - Ambiental												Page 12	
Science Park Square Brighton East Sussex						4501_Marmont_EastPreston Marmont Developments Ltd Proposed Calculations - REV B							
Date 12/07/2019						Designed by SD							
File 4501_Marmont_EastPreston_DrainageNetwork_...						Checked by							
XP Solutions						Network 2018.1							
100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm													
PN	US/MH Name	Event	Duration (mins)	Storm Rank	US/CL (m)	Water Surcharged		Flow / Cap.	Maximum Vol (m³)	Discharge Vol (m³)	Pipe Flow (l/s)	Status	
						Level (m)	Depth (m)						
1.001	1-1	15 minute 100 year Winter I+40%	15	1	8.180	8.068	0.537	0.23	0.230	1.158	3.0	SURCHARGED	
1.002	1-2	15 minute 100 year Winter I+40%	15	1	8.500	8.058	0.605	0.40	0.408	1.720	4.9	SURCHARGED	
1.003	1-3	15 minute 100 year Winter I+40%	15	1	8.550	8.045	0.642	1.19	0.336	6.884	16.1	SURCHARGED	
2.000	4-0	960 minute 100 year Winter I+40%	960	1	8.250	7.967	0.317	0.01	0.131	4.959	0.2	SURCHARGED	
2.001	4-1	960 minute 100 year Winter I+40%	960	1	8.120	7.967	0.471	0.03	0.381	11.627	0.5	SURCHARGED	
1.004	1-4	960 minute 100 year Winter I+40%	960	1	8.250	7.968	0.398	0.28	0.770	32.595	1.5	SURCHARGED	
3.000	2-0	960 minute 100 year Winter I+40%	960	1	8.250	7.967	0.317	0.01	0.073	4.532	0.2	SURCHARGED	
3.001	2-1	960 minute 100 year Winter I+40%	960	1	8.320	7.967	0.426	0.03	0.275	9.059	0.4	SURCHARGED	
3.002	2-2	960 minute 100 year Winter I+40%	960	1	8.150	7.967	0.397	0.05	0.322	8.818	0.4	SURCHARGED	
4.000	3-0	960 minute 100 year Winter I+40%	960	1	8.250	7.967	0.317	0.01	0.131	3.894	0.2	SURCHARGED	
4.001	3-1	960 minute 100 year Winter I+40%	960	1	8.320	7.967	0.427	0.02	0.276	8.343	0.4	SURCHARGED	
3.003	2-3	960 minute 100 year Winter I+40%	960	1	8.150	7.967	0.397	0.11	0.418	16.828	0.7	SURCHARGED	
5.000	5-0	960 minute 100 year Winter I+40%	960	1	8.150	7.966	0.396	0.02	0.153	1.947	0.1	SURCHARGED	
1.005	COMPLEX	960 minute 100 year Winter I+40%	960	1	8.050	7.966	0.466	0.00	94.218	0.000	0.0	SURCHARGED	
©1982-2018 Innovyze													