







ALTERATIONS AND REPAIRS
ELEVATION 01




SECTION 01






ALTERATIONS AND REPAIRS
ELEVATION 02



ALTERATIONS AND REPAIRS
ELEVATION 03



ALTERATIONS AND REPAIRS
ELEVATION 04



ALTERATIONS AND REPAIRS
GROUND FLOOR

EXISTING ELEMENTS

- 0.1 Existing dark grey facing brick walls to be retained
- 0.2 White strip fascia to be retained
- 0.3 White strip cladding to be retained
- 0.4 Existing, non-original, car port doors.
- 0.5 Existing original door to garage
- 0.6 Existing, non-original, opening into car port to be retained.
- 0.7 Existing, non-original, laundry room to be retained.
- 0.8 Existing 9" brickwall to be retained
- 0.9 Existing black painted fascias above car port and garage doors to remain
- 0.10 Existing timber joists to be retained.
- 0.11 Existing ground slab and screed to be retained.

SCOPE OF WORKS

- Alterations and Repairs
- 1.1 Remove existing, non original, car port doors
- 1.2 Omitted
- 1.3 Form new rooflight openings aligned with existing roof joists
- 1.4 Remove existing ceiling
- 1.5 Existing roof timber joists to be removed, subject to inspection.
- 1.6 Existing roof timber joists to be locally modified to allow for rooflight openings.
- 1.7 Step no. 1 removed to allow for raised floor finish level
- 1.8 Remove existing door to garage
- 1.9 Remove existing walls and doors as indicated.
- Roof
- 2.1 Provide new sarking board and roofing felt
- 2.2 New insulation between existing timber joists
- 2.3 Allow for ventilation between existing timber joists by installing grills in external walls. Subject to Heritage approval.
- External Windows and Doors
- 3.1 New aluminium double glazed screens to replace non-original car port doors.
- 3.2 New aluminium double glazed windows
- 3.3 New aluminium double glazed rooflights in new dormer
- 3.4 Blinds to be provided to all new windows and rooflights
- 3.5 New double doors with white strip slats cladding
- 3.6 New glazed screen and glazed door

Services

- 4.1 Provide suitable new space heating, power, lighting, data, and security installations.
- 4.2 Provide Hot&Cold water supply

Linings

- 5.1 New insulation and plasterboard applied internally to external walls.
- 5.2 New plasterboard ceiling to underside of timber joists TBC

Floors

- 6.1 New insulation and floating floor existing floor ground floor

Joinery

- 7.1 New full height storage unit to be provided.
- 7.2 New storage unit with space to park table-tennis table.
- 7.3 New window bench seating unit

Fixed Equipment

- 8.1 Wall mounted TV

Internal Finishes

- 9.1 New engineered timber floor finish to Car Port
- 9.2 Walls and ceilings to be painted on white matt emulsion paint

Loose furniture

- 10.1 Table football
- 10.2 Table tennis
- 10.3 Table and chairs
- 10.4 Sofas and pouf seating



This drawing and design is for use solely in connection with the project described below. The drawing and design is the copyright of Avanti Architects Ltd, and must not be re-issued, loaned or copied without written consent. All dimensions and setting out to be checked on site before construction. This drawing is to be read in conjunction with all other information relevant to the project. Any apparent discrepancy is to be brought to the attention of Avanti Architects Ltd. Do not scale from this drawing.

Notes

DRAWING NOT BASED ON SURVEY INFORMATION

1. Do not scale.
2. Contractor to Check all dimensions and report omissions and errors to Architect.
3. Works subject to planning and listed building consent. No works to commence without prior approval from heritage/planning authorities.

Key Plan



C	16/07/19	20/07/20	Issued for Planning
B	16/07/19	20/07/20	Issued for Comments
A	16/07/19	20/07/20	Issued for Comments
Revision	Date	Issued by	Description
A	16/07/19	IMA	Drawn by IMA
B	16/07/19	IMA	Checked by FL
C	16/07/19	IMA	Checked by FL

Scale	Size	Date First Issue
1:50	A1	02/04/2019
Drawn by	Checked by	
IMA	FL	

Project
VISTA POINT VILLA

Drawing
ALTERATIONS AND REPAIRS TO CAR PORT

Drawing number
AA-18064-GA-50-05

Revision
C

Status
PLANNING

AVANTI
ARCHITECTS

© Avanti Architects Ltd
361-373 City Road
London EC1V 1AS

www.avantiarchitects.co.uk
+ 44 (0) 20 7278 3060
aa@avantiarchitects.co.uk