

CUSTOMER : Steve Reeves - Reeves Transport Planning

CONTACT [REDACTED]

PROJECT : Traffic control system - Ferringham Lane, Worthing

REFERENCE : 802-59MC Reeves Transport Worthing rev2

DATE : 13th November 2018

The following specification & quotation is for the supply and installation of a traffic control scheme. We are main distributors of RIB automation equipment and all our drive units are assembled to ISO 9001 to ensure maximum reliability. All our engineers are highly trained and certified/approved installers of the equipment used.

Equipment detail

- 2 100mm Diameter LED red/green traffic light signal head complete with LED optics, wall or pole mounting brackets and sun visors
- 1 AGD radar detectors to detect vehicles approaching the signal to exit
- 2 A/B logic directional photocells installed at the site entrance (post mounted)
- 2 Photocell mounting posts
- 2 3m x 80mm signal mounting poles coated grey

Entry signal pole to be wall mounted due to the narrow access roadway


- 1 AMS-M3 Traffic signal controller mounted inside a lockable steel enclosure with outputs to each signal and inputs from the vehicle detectors
- 1 FBD software for the controller to carry out the traffic light phases as per the required operation
All phase times are adjustable from the front panel of the controller

The signals will automatically turn off after a period of inactivity and will illuminate only when triggered by any of the vehicle detectors.

The following works are included in this quotation:

Installation of detailed equipment.

Commissioning of detailed equipment



The following works are NOT included in this quotation

- Foundations for the equipment as required
- Power supply at the location of the signal controller
- Control cables as required – between controller and signal heads
- Line markings and signage as required
- Traffic control equipment or staff while the work is in progress

DELIVERY

Our normal installation / delivery time is 4 - 6 weeks from receipt of your official order, however this may be subject to variation due to results from a site survey and production schedules at the time the order is received. We take delivery dates very seriously and our Projects Manager will contact you to confirm your requirements and agree a schedule for the installation of the required equipment. Auto Mate Systems Ltd cannot accept any liabilities due to late delivery of any equipment no matter how excessive the delay may be.


COSTS - All excluding VAT

The cost for supply and installation of the equipment as detailed above will be: **£8220.00**

OPTION

The cost to add a pedestrian phase to the signals, including 2no puffin demand boxes (as below) would be: **£1880.00**

- 2 AGD Puffin style Pedestrian demand units will illuminated RED/GREEN man indicators – operating at 48V (as below)



When pressed, this would hold the vehicle signals RED and give a green signal for a pedestrian.

The vehicle signals will be held RED for a preset time period to allow sufficient time for the pedestrian to clear the roadway.

PAYMENT TERMS

50 % deposit with order and balance due for payment 30 days from invoice for account holders within agreed terms otherwise proforma invoice.

Companies without an account Initial transaction Strictly pro-forma there after an account can be opened only following receipt of satisfactory references. The account facility can be withdrawn without notice should the payment terms be breached.

WARRANTY.

All new equipment supplied and installed by Auto mate Systems Ltd is covered by our comprehensive 12-month guarantee from the date of system commissioning. As part of our commitment to quality, we are able to offer various levels of service contract once the standard warranty has expired. Further details are available on request.

This warranty guarantee will be invalidated if:

- Personnel not authorised by Auto Mate Systems Ltd carry out installation or maintenance.
- Personnel not qualified by Auto Mate Systems Ltd carry out repairs.
- Repairs are performed without prior consent of Auto Mate Systems Ltd.
- The equipment is not maintained in accordance with the recommended Maintenance Schedules / periods.
- The equipment is subject to misuse and malicious or accidental damage.

TERMS.

In accordance with Auto Mate Systems Ltd standard terms and conditions

The proposal is based on the understanding that all work will be carried out during the Company's normal working hours and does not include overtime, weekend or Bank Holiday working. Requests for our staff to work these times will incur additional costs.

Our proposal assumes that the Company's engineers will have free access to all relevant areas and are afforded continuous and uninterrupted working. We try to ascertain that any work being performed by others is ready prior to our attending site, however, should we have to return to site due to incomplete items then we reserve the right to make additional charges at the appropriate rates.

The Company asks that you advise our engineers of the location of any concealed water, gas, electricity, telephone or other services, wiring or pipes, prior to installation commencing. Auto Mate Systems Ltd cannot be held responsible in the absence of such advice for damage caused to unseen services or consequential damages.

The proposal assumes that both installation and commissioning work will be undertaken as a single continuous operation.

Auto mate Systems Ltd have not allowed for any change in the present rate of VAT and all prices shown in this quotation are excluding VAT at the current rate at this time.

Also our proposal price does not include for extra expenses incurred should the site not be ready for us to install on the agreed date. Should the delay be protracted we reserve the right to apply storage and protection costs and to invoice any costs incurred prior to installation.

The Company accept no liability for any loss of earnings due to equipment failure.

Terms are strictly net monthly for approved accounts.

VALIDATION

This quotation is valid for 60 days from the date of issue; our standard terms and conditions apply.

RISK ASSESSMENT

It is advised that the customer must carry out their own risk assessment on the safe operation of Automatic vehicle barriers. Auto Mate systems Ltd will provide any information or advice with the risk assessment upon request.

DISCLAIMER

It is the end users responsibility to ensure that all staff, visitors or any other users of the system are fully aware of the correct control procedures. Written instructions or clear warning / advisory notices at the entrance or exit to the site will help in avoiding any confusion.