

SPECIFICATION - ASDAS PROTOTYPE

Building size: 6.6mx2.6m
Structural Ceiling Height: 2.177m
Roof Pitch: MONO PITCH

Roof Construction:
PROTAN PERMANENT ROOFING MEMBRANE – RAL 7044
ON 15mm T&G OSB OVER TR31 50mm RIGID
INSULATION FIXED TO STEEL C SECTION ROOF
PANEL WITH CEILING JOISTS AT APPROX 400mm
CTRS WITH 50mm ROCKWOOL INSULATION LAID
BETWEEN.

Ceiling Finish:
LINED INTERNALLY WITH WHITE 15mm VINYL FACED
MEGADECO C/W STANDARD WHITE TWO PART PLASTIC
KNOCK IN SECTIONS.

Cornice:

50mm BLACK PVC-U DOWN PIPE. DRAINAGE SOCK
OUTLET C/W LEAF GUARD TO SUIT. ALL JOINTS AND
CONNECTIONS TO BE SOLEVANT WELDED

Floor Construction:
18mm T&G FLOORING GRADE PLYWOOD OVER STEEL
FABRICATED FLOOR FRAME WITH FLOOR JOISTS AT
APPROX. 300mm CTRS 2 LAYERS OF FOL THERM
INSULATION LAID BETWEEN JOISTS.

18-20mm LARCH TIMBER CLADDING FIXED TO
TANALISED 25x50mm TIMBER BATTENS ON 1 LAYER OF
BREATHER MEMBRANE (BS5250) OVER 11mm OSB
BOARD
FIXED TO STEEL C SECTION WALL PANELS WITH STUD
URIGHTS AT APPROX 400mm CTRS WITH 70mm
ROCKWOOL INSULATION PACKED BETWEEN.

Wall Interior Finish:
LINED INTERNALLY WITH CREAM 15mm VINYL FACED PLASTERBOARD C/W CREAM STANDARD KNOCK IN SECTIONS AND J MOULDS OVER 11mm OSB BOARDS C/THERMA SHEET FIXED TO STEEL C SECTION WALL FRAMING UPRIGHTS.

SHALLING;
FITTED BY OTHERS

External Entrance Doors:
ALUMINIUM DOORSET WITH FIXED SIDE SCREENS AND
AUTOMATIC SLIDING DOOR – RAL 7044

Floor Covering:
Torreitt Vylon Plus 2.0mm sheet vinyl – Colour: 534 Charcoal
All joints welded using weldrod – Colour to be suitably matched.

External Trim Colours:

TYPE A = POWDER COATED - RAL 7044
TYPE B = POWDER COATED - RAL 7044
TYPE C = POWDER COATED - RAL 7044
TYPE D = POWDER COATED - RAL 7044
TYPE E = POWDER COATED - RAL 7044
TYPE F = POWDER COATED - RAL 7044
TYPE G = POWDER COATED - RAL 7044

TYPE	DESCRIPTION
TYPE M213	POWDER COATED TO GALVANISED STEEL
TYPE N	POWDER COATED TO GALVANISED STEEL

By	Date	Description
----	------	-------------



**PREMIER
INTERLINK**
WACO UK LTD

HEAD OFFICE
CATFOSS LANE, BRANDESBURTON, DRIFFIELD
EAST YORKSHIRE YO25 8EJ
Telephone: (01964) 545000 Fax: (01964) 545001
email: sales@waco.co.uk internet: www.waco.co.uk

Elevation

Asda

Slimline Kiosk

Elevations

Issuing No.	50	Drawn	JM	Date:	19.12.17	Checked	CHECK	Rev
-------------	----	-------	----	-------	----------	---------	-------	-----

Asda STD_002