



KEY

Proposed Tree Planting
Proposed tree planting to be 12 - 14 cm Girth Size / 3.5 - 4.25m height / 1.75-2.0m Clear Stem / Standard Heavy Stock. Trees to be supplied and planted in accordance with BS 8545: 2014 Trees: from nursery to independence in the landscape: Recommendations.

Proposed Hedgerow Planting
Proposed hedgerow planting areas to have 300mm depth (minimum) subsoil overlain with 300mm (minimum) multi purpose topsoil to BS3882: 2015 'Specification for Topsoil'. Hedgerow planting areas to have 75 mm depth (min) of ornamental bark mulch.

Proposed Ornamental Shrub / herbaceous Planting Areas
Proposed ornamental shrub / herbaceous planting areas to have 300mm depth (minimum) subsoil overlain with 300mm (minimum) multi purpose topsoil to BS3882: 2015 'Specification for Topsoil'. Planting areas to have 75 mm depth of ornamental bark mulch.

Proposed Ornamental/Native Species Shrub Specimens
Proposed shrub specimens to have 300mm depth (minimum) subsoil overlain with 300mm (minimum) multi purpose topsoil to BS3882: 2015 'Specification for Topsoil'. Planting areas to have 75 mm depth of ornamental bark mulch.

Proposed Climbing Shrub Specimens
Proposed ornamental shrub specimens to have 300mm depth (minimum) subsoil overlain with 300mm (minimum) multi purpose topsoil to BS3882: 2015 'Specification for Topsoil'. Planting areas to have 75 mm depth of ornamental bark mulch.

Proposed Flowering Lawn Areas
Proposed grass lawn areas to be seeded with Emongate EL1 (Flowering Lawn Mixture) or equal and approved. Emongate Seeds (Limes Farm, Tilney, All Saints, King's Lynn, Norfolk, PE34 4RT T: (01553) 829028 / https://wildseed.co.uk

Proposed Pebble / Shingle Surfacing
Proposed shingle pebbles surfacing to be 20 - 50mm Ø.

Proposed & Existing Tarmacadam
Proposed and existing access off Ferringham Lane to be tarmacadam surfacing.

Proposed Vehicular Paving
Proposed access road to be permeable block paviors laid in a herringbone pattern. Blocks to be: Brett Alpha Flow / Colour to be Charcoal (or similar and approved) supplied by Brett Landscaping and Building Products, Sileby Road, Barrow-upon-Soar, Leicestershire, LE12 8LX.

Proposed Vehicular Paving
Proposed private parking spaces to be permeable block paviors. Blocks to be: Brett Alpha Silver Haze / Colour to be Silver Haze (or similar and approved) supplied by Brett Landscaping and Building Products, Sileby Road, Barrow-upon-Soar, Leicestershire, LE12 8LX.

Proposed Pedestrian Paving
Proposed pedestrian paving to be porcelain slabs. Slabs to be: Brett Eclipse porcelain paving slabs / Lume (or similar and approved) supplied by: Brett Landscaping and Building Products, Sileby Road, Barrow-upon-Soar, Leicestershire, LE12 8LX.

Proposed Timber Boundary Fencing
Proposed close boarded timber fencing and gates: Internal boundaries to be 3.8m height / External boundaries - new fencing to be 2.0m height close boarded timber fencing.

Proposed Timber Boundary Fencing
Proposed hand cleft, timber, post and rail fencing (1.2m height) defining frontage boundaries between Plots 03 and 04.

Proposed Bin Storage Areas

NOTES

Refer to RCo391 / 02 / Detailed Planting Plan, RCo391 / 03 / Detailed Planting Plan and RCo391 / Detailed Plant Schedule and Specification detailed planting proposals.

REV	DESCRIPTION	DATE	INITIALS
01	Layout updated following comments	13-07-21	AR
02	Layout updated following comments	16-07-21	AR
03	Layout updated following comments	19-07-21	AR
04	Layout updated following comments	20-07-21	AR
05	Layout updated following comments	23-07-21	AR

Ramsay & Co
Landscape Architecture

The Studio, 68 Cuckfield Road, Hurstpierpoint, West Sussex, BN6 9SB
T: 01273 834 198 M: 07973 770047 E: landscape@ramsayandco.com

Project Title:
Pebble Lane, Ferringham Lane, Ferring, W. Sussex

Globe Estates Southern Ltd.

Drawing Title:
Hard & Soft General Arrangement Drawing

Scale: 1:200@A1

Drawn: AR

Date: 01-07-21

Drawing Number: RCo391 / 01

Revision: 05