ARUN DISTRICT COUNCIL FG/180/21/PL

FOR SITE DESIGN DEPENDENCIES REFER TO DRAWING 503

N
W E
S

EXISTING GARDEN AREA

EXISTING 13m HIGH TREES

1620

NOTES:
STATS REPORT REQUIRED

TARMAC FOOTPATH

2323

PROPOSED 20.0m HIGH ORION ERV1 STREETPOLE TO BE INSTALLED ON NEW 12 BOLT ROOT FOUNDATION (COLOUR GOOSE GREY BS00A05) WITH GPS MODULE FIXED TO TOP OF POLE

EXISTING WOODEN PANEL FENCE

GRASS VERGE

4212

PROPOSED 150ø POWER & FIBRE DUCT

PROPOSED 150ø FEEDER DUCTS

EXISTING WOODEN FENCE

100

PROPOSED TEF SFMC TO BE INSTALLED ON NEW ROOT FOUNDATION (COLOUR FIR GREEN RAL6009)

30

PROPOSED TEF SIDEPOD TO BE INSTALLED ON NEW ROOT FOUNDATION (COLOUR FIR GREEN RAL6009) C/W PROPOSED TEF N7, GU09 & 3No. C2 COMBINERS.

1510

PROPOSED 150ø POWER DUCT FROM SFMC TO LANCASTER CABINET

EXISTING TEF LANCASTER EQUIPMENT CABINET ON ROOT FOUNDATION C/W PROPOSED TEF L08, L09, L18/L21, 4G/5G AIRSCALE 6No. C4 COMBINERS & 3No. C2 COMBINERS.

BT

KERBLINE

GREYSTOKE ROAD (MAX SPEED 30mph)

PROPOSED 150ø POWER DUCT FROM SFMC TO SPITFIRE CABINET

EXISTING TEF HUTCHINSON ENGINEERING 13.8m HIGH ELARA POLE C/W EXISTING TEF 3No. ANTENNAS TO BE REMOVED

EXISTING TEF SPITFIRE EQUIPMENT CABINET ON ROOT FOUNDATION TO BE UPGRADED INTERNALLY

GROUND LEVEL +0.00m AGL

EXISTING 100ø INCOMING COMMS DUCT

NOTE:
PROPOSED TEF 24No. FEEDERS & DC/FIBRE CABLES TO BE INSTALLED INSIDE OF STREETPOLE

EQUIPMENT LAYOUT

(1:50)

2500 2000 1500 1000 500 0 1000 2000 3000 4000 5000

ORIGINAL SCALE AT A3 – 1:50

ALL DIMENSIONS IN MILLIMETRES

The drawings comply with TEF & Vodafone Standard ICNIRP guidelines.
Designed in accordance with CORNERSTONE document: SDN0008 & SDN0009

ALL DIMENSIONS ARE IN mm UNLESS NOTED OTHERWISE

N.G.R E: 509405 N: 102776

DUCT KEY

- EXISTING 100ø POWER
- EXISTING 100ø COMMS
- EXISTING 150ø FEEDER
- EXISTING 100ø INCOMING*
- PROPOSED 100ø POWER
- PROPOSED 100ø COMMS
- PROPOSED 150ø FEEDER
- PROPOSED 100ø POKE–OUT*
- PROPOSED 150ø POWER & FIBRE

*INCOMING AND POKE–OUT DUCTS TO BE COLOURED BY DUCT TYPE (POWER/COMMS/FEEDER)

EXISTING U/G SERVICES KEY

HV	POWER LINE HV
LV	POWER LINE LV
E	POWER LINE UNIDENTIFIED
GLP	GAS LOW PRESSURE
GMP	GAS MEDIUM PRESSURE
GHP	GAS HIGH PRESSURE
PW	POTABLE WATER
FW	FOUL SEWER
CSEW	COMBINED SEWER
SW	SURFACE WATER SEWER
TU	TELECOM
CTV	CABLE
EA	ABANDONED PIPE
?	UNIDENTIFIED

REV	MODIFICATION	BY	CH	DATE
A	Issued for Approval	INS	JSO	29.04.21

GBC
Great British Communications
Lapwing House, Block 3 Forward Point,
Tan House Lane, Widnes, Cheshire, WA8 0SL
t. 44 (0)151 420 4128
www.gbcservices.co.uk

O2
TEF SOUTH EAST

Cell Name	Opt.
FERRING STREET FURNITURE	–

Cell ID No

CORNERSTONE	TEF	VF
116488	45386	N/A

Site Address / Contact Details

FERRING STREET FURNITURE
GREYSTOKE ROAD
LITTLEHAMPTON
WEST SUSSEX
BN12 5JL

Drawing Title: EQUIPMENT LAYOUT

Purpose of issue: PLANNING — Dwg Rev: A

Drawing Number: 401

Surveyed By: INS — Original Sheet Size: A3 — Pack Issue: A

Drawn:	Date:	Checked:	Date:
INS	29.04.21	JSO	29.04.21