

[REDACTED]

[REDACTED]

From: stephen jupp [REDACTED]
Sent: 11 May 2018 08:38
To: Anita Gardner
Cc: Ben Reeder
Subject: Re: FG/48/18/DOC Onslow Caravan Park, Ferring

Anita

My clients drainage engineer has responded as below to the points raised by your engineer [his responses are in magenta]

The Drainage Engineer has stated relating to Condition 4 Drainage:

- It is noted that only a 20% allowance for climate change has been included in the design of the surface water drainage system. This needs to be increased to 30% in line with the condition applied. THE 20% ALLOWANCE ACCORDS WITH PLANNING PRACTICE GUIDANCE FOR THE LIFETIME OF THE DEVELOPMENT PROPOSED, AND ALSO WITH THE CENTRAL ALLOWANCE FOR RESIDENTIAL DEVELOPMENT. 30% IS NOT JUSTIFIED.
- Storm durations from and including 15 minutes need to be used. THE CALCULATION INVESTIGATED STORM DURATIONS AT TEN MINUTE INTERVALS FROM 10 MINUTES TO 72 HOUR DURATION. ONLY SELECTED DETAILS ARE REPORTED, THE CRITICAL DURATION IS QUOTED TO THE NEAREST TEN MINUTES.
- The restriction size of 20mm is of concern regarding the possibility of blockage. It is recommended that a mesh or similar is installed within each tank at the face of the outlet. THE INLET STRAINER IS SUPPLIED TO PREVENT LARGE PARTICLES ENTERING THE TANKS. FLOW RATES THROUGH THE OUTLET ARE SO LOW THAT IF GROWTH OCCURS WITHIN THE TANKS, IT WOULD NOT TEND TO BE DRAWN TOWARDS THE OUTLET, WHICH HAS THE ABILITY TO PASS 15 MM PARTICLES. IF A BLOCKAGE WERE TO OCCUR, IT WOULD SPOTTED QUICKLY AND WOULD BE EASY TO REMOVE. WHEREAS THE TEE COULD BE CHANGED AND A 1 1/2" BSP STRAINER ADDED, ALLOWING EASY MAINTENANCE, SUCH A STRAINER IS LIABLE TO BLOCKAGE WITH SMALL PARTICLES. THEREFORE NO STRAINER IS RECOMMENDED. A MESH SCREEN WITHIN THE TANKS AS SUGGESTED WOULD BE VERY DIFFICULT TO MAINTAIN AND THUS ALSO IS NOT RECOMMENDED.

- It is currently proposed that the outlet to the existing ditch will be formed by a paving slab. This is not acceptable, we require a formal headwall to be formed using concrete bags or brickwork. With full construction detail drawings to be supplied and approved by us. THE OUTLET PIPE IS DUCTILE IRON WITH A FLAP ATTACHED. AS SUCH THE OUTLET IS RESILIENT TO DAMAGE AND BARELY ANY DISTURBANCE OF THE BANK WILL OCCUR. A HEADWALL IS ENTIRELY UNNECESSARY, THE PROPOSED PAVING SLAB CAN BE OMITTED.
- Full construction details will be required including the gully/headwall, any manholes, and silt traps. DRAWING 100A ALREADY SHOWS EVERY DETAIL NECESSARY TO BUILD THE UNDERGROUND DRAINAGE. NO OTHER DETAIL COULD BE REQUIRED.

Kind regards

Steve Jupp

 Stephen Jupp MRTPI
 Chartered Town Planner
 Sally Field Lodge
 Rotten Row
 Sidlesham
 West Sussex
 PO20 7QB



NB: Please note my new telephone number and office address

On 9 May 2018, at 16:08, Anita Gardner <Anita.Gardner@arun.gov.uk> wrote:

Dear Mr Jupp,

The following comments have been received from the Environmental Health Officer re discharge of Condition 6 - Construction Management Plan.

- b. the site manager's contact details to be provided on all notification of works to neighbouring residents
- c. to state the careful selection of low noise plant and machinery to minimise noise and use of noise mitigation barriers where necessary.

The Drainage Engineer has stated relating to Condition 4 Drainage:

- It is noted that only a 20% allowance for climate change has been included in the design of the surface water drainage system. This needs to be increased to 30% in line with the condition applied.
- Storm durations from and including 15 minutes need to be used.
- The restriction size of 20mm is of concern regarding the possibility of blockage. It is recommended that a mesh or similar is installed within each tank at the face of the outlet.
- It is currently proposed that the outlet to the existing ditch will be formed by a paving slab. This is not

acceptable, we require a formal headwall to be formed using concrete bags or brickwork. With full construction detail drawings to be supplied and approved by us.

- Full construction details will be required including the gully/headwall, any manholes, and silt traps. I would therefore appreciate receipt.

If you agree to an extension of time on the application until 15-06-2018 by lunchtime tomorrow I will await receipt of revised drainage plans and calculations and an amended version of the Management Plan. Alternatively the application will be refused given the present lack of acceptable detail.

Regards

Anita Gardner

Anita Gardner | Principal Planner, Directorate of Place, Arun District Council | Location: First Floor, Arun Civic Centre, Maltravers Road, Littlehampton, BN17 5LF

Internal: 37529 | External: +44 (0) 1903 737529 | E-mail: anita.gardner@arun.gov.uk

Visit Arun's web site at www.arun.gov.uk  Save the environment - think before you print.

<http://www.arun.gov.uk>
NLPG UPRN 100062237016
DX 57406 Littlehampton

Important Notice This e-mail is intended exclusively for the addressee and may contain information that is confidential and/or privileged. If you are not the intended recipient (or authorised to receive it for the addressee), please notify the sender and delete the e-mail immediately; using, copying, or disclosing it to anyone else, is strictly prohibited and may be unlawful. Any views, opinions or options presented are solely those of the author and do not necessarily represent those of Arun District Council. The information in this e-mail may be subject to public disclosure under the Freedom of Information Act 2000, therefore we cannot guarantee that we will not provide the whole or part of this e-mail to a third party. The Council reserves the right to monitor e-mails in accordance with relevant legislation. Whilst outgoing e-mails are checked for viruses, we cannot guarantee this e-mail is virus-free or has not been intercepted or changed and we do not accept liability for any damage caused. Any reference to "e-mail" in this disclaimer includes any attachments.
