

Established 1970

SCCE SOUTH COAST CATERING EQUIPMENT Ltd

Sales, Service, Design and Installation of Commercial Catering Equipment

Commercial House, Units 4 & 5 Apex Park, Diplocks Way, Hailsham, East Sussex BN27 3JU

Megan Grover
3 Grassmere Parade
Felpham Village
West Sussex
PO22 7NT

1st July 2019

To Supply and Install

One Section Wall Canopy size 1200mm W x 1100mm D x 480mm H 430 Stainless Steel. Unit to include for two removable Stainless Steel baffle filters. The extraction system will be fitted with S400 Commercial Fan with a Speed Controller sited in close proximity. The extract duct from the canopy will be manufactured in galvanized steel and will terminate at the window which will have a blank sheet fitted to accept the fan. The outside duct will be fitted with bird mesh wire grill and will protrude not more than 300mm. The fan will be located inside the building which will keep the noise level to a minimum. The data sheet for the fan is attached to this specification. Due to the light cooking menu a carbon odour control system should not be required.

Kind regards
Mike Barnes
Extract Technical Department.

