

REFER TO FABRIK DRAWING L.202

L.300 Plant Schedule

Tree Planting

Species	Size/Spec	Condition	Qty
Ac. Acer campestre 'Sireetwise'	12-14cm Girth / 2m clear stem	RB	3
Bp. Betula pendula	12-14cm Girth / 2m clear stem	RB	13
Pa. Prunus avium 'Pleni'	14-16cm Girth / 2m clear stem	RB	14
Pr. Prunus serotina	14-16cm Girth / 2m clear stem	RB	5
Pc. Pyrus calleryana 'Chanticleer'	16-18cm Girth / 2m clear stem	RB	11
Tc. Tilia cordata 'Greenspire'	16-18cm Girth / 2m clear stem	RB	5

Shrub Planting

Species	Density	Size	Condition	Qty
Abelia x grandiflora	4m ²	3L	CG	0
Acacia japonica 'Salicoides'	4m ²	3L	CG	158
Berberis thunbergii 'Atropurpurea Nana'	4m ²	3L	CG	0
Chydrea tenuis	4m ²	3L	CG	89
Cissua 'Silver Pink'	4m ²	3L	CG	41
Cornus alba	4m ²	3L	CG	72
Daphne x burkwoodii 'Somerset'	4m ²	3L	CG	101
Deutzia x elegantissima	4m ²	3L	CG	36
Escallonia 'Apple Blossom'	4m ²	3L	CG	145
Hebe 'White Gem'	4m ²	3L	CG	54
Hebe 'White Gem'	4m ²	3L	CG	69
Lonicera nitida	4m ²	3L	CG	38
Lavandula 'Vera'	4m ²	3L	CG	110
Manissea aquilifolium	4m ²	3L	CG	30
Manissea x media 'Winter Sun'	4m ²	3L	CG	34
Osmianthus x burkwoodii	4m ²	3L	CG	40
Philadelphus 'Mantau d'Hermine'	4m ²	3L	CG	72
Phodina x fraseri	4m ²	3L	CG	22
Rosa carolina	4m ²	3L	CG	22
Sarcococca hookeriana	4m ²	3L	CG	100
Spiraea japonica	4m ²	3L	CG	67
Spiraea japonica 'Little Princess'	4m ²	3L	CG	26
Viburnum tinus	4m ²	3L	CG	8
Vinca minor	5m ²	2L	CG	30

Native Mix Planting

Species	Density	Size	Condition	Qty
Acer campestre	4/m ²	125-150cm H	BR	151
Cornus sanguinea	4/m ²	100-125cm H	BR	136
Crataegus monogyna	4/m ²	125-150cm H	BR	151
Ilex aquifolium	4/m ²	3L	CG	15
Prunus spinosa	4/m ²	125-150cm H	BR	112
Rosa canina	4/m ²	60-80cm H	BR	51
Sambucus nigra	4/m ²	60-80cm H	BR	76
Ulex europaeus	4/m ²	3L	CG	76

Climbing Plants

Species	Density	Size	Condition	Qty
Ca. Clematis armandi	As shown	2L	CG	0
Da. Decumaria sinensis	As shown	2L	CG	3
Hi. Hibiscus syriacus	As shown	2L	CG	0
Hi. Hydrangea serrata	As shown	2L	CG	0

Bulb Planting

Species	Density	Size/Spec	Qty
Camassia leichtlinii	50/m ²	Top Size	800
Crocus (mixed)	50/m ²	Top Size	
Galanthus nivalis	50/m ²	Top Size	
Fritillaria meleagris	50/m ²	Top Size	
Hyacinthoides non-scripta	50/m ²	Top Size	
Tulip sylvestris	50/m ²	Top Size	

EGG - Meadow Grass Mixture for Wetlands

Species	Common Name	Percentage
Agrostis capillaris	Meadow Foxtail	15
Alcepsurus pratensis	Slender Creeping Red-fescue	3.75
Anthoxanthum odoratum	Sweet Vernal-grass	2.5
Beta media	Quaking Grass	1.25
Cynodon dactylon	Crested Dogtail	45
Deschampsia cespitosa	Tufted Hair-grass	1.25
Festuca rubra ssp. juncea	Slender-creeping Red-fescue	31.25

E10 - Tussock Grass Mixture

Species	Common Name	Percentage
Alcepsurus pratensis	Meadow Foxtail	6.25
Cynodon dactylon	Crested Dogtail	25
Deschampsia cespitosa	Tufted Hair-grass	18.75
Festuca rubra ssp. rubra	Tufted Hair-grass	6.25
Holcus lanatus	Meadow Fescue	12.5
Yorkshire Fog	Yorkshire Fog	3.75
Yellow Oat-grass	Yellow Oat-grass	2.5

A4 - Amenity Grass (Low Maintenance)

Species	Common Name	Percentage
Aniset	Strong Creeping Red Fescue	40
Rala	Chewing Fescue	30
Menor	Hard Fescue	25
Highland	Brown-top Bent	5

A19 - Amenity Grass

Species	Common Name	Percentage
Aniset	Strong Creeping Red Fescue	30
Rala	Chewing Fescue	25
Menor	Hard Fescue	20
Highland	Brown-top Bent	5

Planting Guidelines

- All planting and landscape operations should comply with the requirements specified in BS 3606 (1992) Nursery Stock Part One and BS 4428 (1988) Code of Practice for General Landscape Operations (excluding hard surfaces).
- All landscaped areas to be maintained for 12 months.
- All planted areas to be forked through regularly to keep soil loose and aerated.
- All litter and debris to be removed from landscaped areas and carried off site.
- Plants reformed and straightened as required.
- Plants proved as instructed by the Landscape Architect to promote healthy growth and to remove dead and diseased wood.
- Watering as required to maintain healthy growth (allow for 12 hr watering minimum).
- Any species that does or fails to establish in the first five years should be replaced by identical species.
- Allow for a minimum of 18 maintenance visits.

Additional Notes

- Existing levels to be preserved around existing trees and vegetation to be retained.
- Existing trees and vegetation to be retained are to be protected during construction to BS 9537:2005. (Refer to tree survey carried out by tree clerk / July 2007).
- Any necessary tree works to be carried out by an approved tree surgeon to BS 3998.
- All planting in ability slays should be below 600mm in height.

Proposed Tree Planting

To be planted as notified stock in the first available planting season after construction. Stock size proposed to be as shown and tree support shall be two softwood stakes @ 7.5cm diameter @ 200cm length and should be driven into the ground to knee-height with file and horizontal cross support. Tree pit: 750x750x600mm depth.

Proposed Shrub Planting

To be planted as notified stock in the first available planting season after construction. Stock size to be 3-5litre, type and densities proposed are as shown. Shrubs are to be planted in a minimum depth of 400mm of approved topsoil overlying clean subsoil previously broken up by the Main Contractor to alleviate any compaction. Area planted to be spread with 75mm deep of approved bark mulch.

Proposed Hedge Planting

Hedgeplanting to be planted 300mm apart in double staggered rows at 450mm centres with plants of the same species in groups of 3 to 5 to be planted in the first available planting season after construction in a minimum 450mm depth of clean topsoil, with a minimum of 50mm approved bark mulch applied.

L.301 Plant Schedule

Tree Planting

Species	Size/Spec	Condition	Qty
Ac. Acer campestre 'Sireetwise'	12-14cm Girth / 2m clear stem	RB	1
Bp. Betula pendula	12-14cm Girth / 2m clear stem	RB	1
Pa. Prunus avium 'Pleni'	14-16cm Girth / 2m clear stem	RB	15
Pr. Prunus serotina	14-16cm Girth / 2m clear stem	RB	7
Pc. Pyrus calleryana 'Chanticleer'	16-18cm Girth / 2m clear stem	RB	11
Tc. Tilia cordata 'Greenspire'	16-18cm Girth / 2m clear stem	RB	6

Shrub Planting

Species	Density	Size	Condition	Qty
Abelia x grandiflora	4m ²	3L	CG	9
Acacia japonica 'Salicoides'	4m ²	3L	CG	129
Berberis thunbergii 'Atropurpurea Nana'	4m ²	3L	CG	0
Chydrea tenuis	4m ²	3L	CG	233
Cissua 'Silver Pink'	4m ²	3L	CG	160
Cornus alba	4m ²	3L	CG	38
Daphne x burkwoodii 'Somerset'	4m ²	3L	CG	300
Deutzia x elegantissima	4m ²	3L	CG	234
Escallonia 'Apple Blossom'	4m ²	3L	CG	371
Hebe 'White Gem'	4m ²	3L	CG	298
Hebe 'White Gem'	4m ²	3L	CG	498
Lonicera nitida	4m ²	3L	CG	125
Lavandula 'Vera'	4m ²	3L	CG	129
Manissea aquilifolium	4m ²	3L	CG	0
Manissea x media 'Winter Sun'	4m ²	3L	CG	0
Osmianthus x burkwoodii	4m ²	3L	CG	150
Philadelphus 'Mantau d'Hermine'	4m ²	3L	CG	247
Phodina x fraseri	4m ²	3L	CG	0
Rosa carolina	4m ²	3L	CG	134
Sarcococca hookeriana	4m ²	3L	CG	328
Spiraea japonica	4m ²	3L	CG	247
Spiraea japonica 'Little Princess'	4m ²	3L	CG	120
Viburnum tinus	4m ²	3L	CG	59
Vinca minor	5m ²	2L	CG	294

Native Mix Planting

Species	Density	Size	Condition	Qty
Acer campestre	4m ²	125-150cm H	BR	608
Cornus sanguinea	4m ²	100-125cm H	BR	458
Crataegus monogyna	4m ²	125-150cm H	BR	608
Ilex aquifolium	4m ²	3L	CG	64
Prunus spinosa	4m ²	125-150cm H	BR	458
Rosa canina	4m ²	60-80cm H	BR	244
Sambucus nigra	4m ²	60-80cm H	BR	304

Climbing Plants

Species	Density	Size	Condition	Qty
Ca. Clematis armandi	As shown	2L	CG	3
Da. Decumaria sinensis	As shown	2L	CG	5
Hi. Hibiscus syriacus	As shown	2L	CG	0
Hi. Hydrangea serrata	As shown	2L	CG	0

Specimen Shrub Planting

Species	Density	Size	Condition	Qty
Ca. Cornus sanguinea	As shown	15L	CG	0
Sy. Syringa vulgaris	As shown	15L	CG	0

Bulb Planting

Species	Density	Size/Spec	Qty
Camassia leichlinii	50/m ²	Top Size	300
Crocus (mixed)	50/m ²	Top Size	
Galanthus nivalis	50/m ²	Top Size	
Fritillaria meleagris	50/m ²	Top Size	
Hyacinthoides non-scripta	50/m ²	Top Size	
Tulip sylvestris	50/m ²	Top Size	

EGG - Meadow Grass Mixture for Wetlands

Species	Common Name	Percentage
Agrostis capillaris	Meadow Foxtail	15
Alcepsurus pratensis	Slender Vernal-grass	3.75
Anthoxanthum odoratum	Sweet Vernal-grass	2.5
Beta media	Quaking Grass	1.25
Cynodon dactylon	Crested Dogtail	45
Deschampsia cespitosa	Tufted Hair-grass	1.25

E10 - Tussock Grass Mixture

Species	Common Name	Percentage
Alcepsurus pratensis	Meadow Foxtail	6.25
Cynodon dactylon	Crested Dogtail	25
Deschampsia cespitosa	Tufted Hair-grass	18.75
Festuca rubra ssp. rubra	Tufted Hair-grass	6.25
Holcus lanatus	Meadow Fescue	12.5
Yorkshire Fog	Yorkshire Fog	3.75
Yellow Oat-grass	Yellow Oat-grass	2.5

A4 - Amenity Grass (Low Maintenance)

Species	Common Name	Percentage
Aniset	Strong Creeping Red Fescue	40
Rala	Chewing Fescue	30
Menor	Hard Fescue	25
Highland	Brown-top Bent	5

A19 - Amenity Grass

Species	Common Name	Percentage
Aniset	Strong Creeping Red Fescue	30
Rala	Chewing Fescue	25
Menor	Hard Fescue	20
Highland	Brown-top Bent	5

External References:

- D15302/Engineer/Record 08 04 21/Fabrik/L.300 Eng Base
- D15302/Architect/Record 08 04 22/1043 SITE LAYOUT REV D
- D15302/Engineer/Record 07 09 11/Drawing Number 3004/04 - Plot Rev A
- D15302/VP/Temporary access drawing 3004/04 G/L-102 Rev C
- D15302/Architect/Record 10 02 22/04/05 LAYOUT REV C - 02/07/07.dwg

Note:

- for full details of tree survey and tree protection refer to treeback drawing no. TF6077/Plot 101-110 Rev F.
- Footpaths in POS areas to be finished on site.

REFER TO FABRIK DRAWING L.302

REFER TO FABRIK DRAWING L.301

fabrik

38a High Street
Alton
Hampshire
GU34 1BD
T : 01420 593250
F : 01420 544243
E : studio@fabrikuk.com
W : www.fabrikuk.com

Soft Landscape	Existing Trees	Proposed Trees	Existing Vegetation	Proposed Hedge Planting

Proposed Native Hedge Planting	Proposed Shrub Planting	Proposed Grass	Proposed Meadow Grass	Proposed Bulb Planting

