

Specification Sheet

Adam James Bespoke
116 Whyke Lane
Chichester
W. Sussex
PO19 8AS

Limmer Lane

All windows to be produced to the same specification as follows;

- Timber used - Sapele
- Painted undercoat finish
- Traditional Box Sash production with steel weights and pulley system. 100mm boxes
- Traditional 25mm Glazing bars
- Slimline double glazed units 12mm/14mm with heritage slim sightline
- Traditional locking furniture to be installed, finish tbc
- Frame depth with be total of 150mm with 45mm thick sash's
- Seals and brushes installed
- Timber 45 degree "putty style" beads to encase the glazing
- Ovlo profile to interior of sash's
- Rebated meeting styles with seals