



From: Sarah Burrow <Sarah.Burrow@arun.gov.uk>
Sent: 03 November 2020 10:36
To: Planning.Responses <Planning.Responses@arun.gov.uk>
Cc: Maria Tomalova <Maria.Tomalova@arun.gov.uk>
Subject: RE: Planning Consultation on: FP/184/20/PL

Engineers Comments Regarding Surface Water Drainage

Within the DAS the applicant states that:

"The proposals are for all surface water to be disposed of on site via soakaways, with no additional surface water discharging into the foul drainage system. Winter groundwater monitoring took place during the winter of 2019/2020 to establish infiltration rates. A detailed surface water management design has subsequently been created and accompanies this application."

No surface water management design or evidence of groundwater monitoring and infiltration testing has been uploaded on the system. If the applicant would like these to be assessed they will need to be supplied. In the absence of such documents, I would request that standard condition PCENG2 is applied (should you be minded to approve the application), so that the design can be assessed as a discharge of conditions application.

I am happy to provide a second consultation to potentially avoid the application of said condition.

PCENG2

"Development shall not commence, other than works of site survey and investigation, until full details of the proposed surface water drainage scheme have been submitted to and approved in writing by the Local Planning

Authority. The design should follow the hierarchy of preference for different types of surface water drainage disposal systems as set out in Approved Document H of the Building Regulations, and the recommendations of the SuDS Manual produced by CIRIA. Winter groundwater monitoring to establish highest annual ground water levels and winter Percolation testing to BRE 365, or similar approved, will be required to support the design of any Infiltration drainage. No building / No part of the extended building shall be occupied until the complete surface water drainage system serving the property has been implemented in accordance with the agreed details and the details so agreed shall be maintained in good working order in perpetuity."

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W SP1, W DM1, W DM2 and W DM3 of the Arun Local Plan. This is required to be a pre-commencement condition because it is necessary to implement the surface water drainage system prior to commencing any building works.

And the accompanying informative:

INFORMD

"Infiltration rates for soakage structures are to be based on percolation tests undertaken in the winter period and at the location and depth of the proposed structures. The percolation tests must be carried out in accordance with BRE365, CIRIA R156 or a similar approved method and cater for the 1 in 10 year storm between the invert of the entry pipe to the soakaway, and the base of the structure. It must also have provision to ensure that there is capacity in the system to contain below ground level the 1 in 100 year event plus 40% on stored volumes, as an allowance for climate change. Adequate freeboard must be provided between the base of the soakaway structure and the highest recorded annual groundwater level identified in that location. Any SuDS or soakaway design must include adequate groundwater monitoring data to determine the highest winter groundwater table in support of the design. The applicant is advised to discuss the extent of groundwater monitoring with the Council's Engineers.

Supplementary guidance notes regarding surface water drainage are located here

<https://www.arun.gov.uk/surfacewater> on Arun District Councils website. A surface water drainage checklist is available on Arun District Councils website, this should be submitted with a Discharge of Conditions Application."

Kind Regards

Sarah Burrow

Engineering Assistant, Engineering Services

T: 01903 737815

E: sarah.burrow@arun.gov.uk



Current working hours: Mon 8:00-2:30, Tues-Thur 8:00-17:30, Fri 8:00-11:30

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF

www.arun.gov.uk

Sign up to our newsletter [here](#)



From: Planning.Responses <Planning.Responses@arun.gov.uk>

Sent: 05 October 2020 09:49

To: Land Drainage [REDACTED]

Subject: Planning Consultation on: FP/184/20/PL

To: Engineers (Drainage)

NOTIFICATION FROM ARUN DISTRICT COUNCIL

Town & Country Planning Act 1990 (as amended)

Town and Country Planning (Development Management Procedure) (England) Order 2015

Planning Permission

Application No: FP/184/20/PL
Registered: 2nd October 2020
Site Address: Rear of 7 Middleton Road Felpham PO22 6BL
Grid Reference: 496183 100310
Description of Works: Demolition of existing garage/outbuilding & construction of a pair of semi-detached houses & associated works. This site is in CIL Zone 4 & is CIL Liable as new dwellings.

The Council have received the above application.

[Click here to view the application details](#)

This application has been identified as CIL Liable. Therefore please be aware that, in accordance with Appendix 2 of the Arun CIL Charging Schedule, your consultation response should only include requests for Section 106 for onsite mitigation, Pagham Harbour Management Contributions (if applicable) or Affordable Housing. Off Site mitigation measures directly related to this development should be dealt with by condition if possible to ensure the scaling back of Section 106 if possible. CIL contributions will be used for off site infrastructure mitigation schemes. Therefore if this proposal triggers the need for off site mitigation, please ensure that you engage in the CIL Infrastructure List Consultation process upon receipt of a consultation letter.

Should you have any comments to make, these should be sent by replying to this email by 5th November 2020. You can also monitor the progress of this application through the Council web site:

www.arun.gov.uk/planning.

The application will be determined having regard to the development plan policies (if any are relevant) and other material considerations. The development plan can be accessed via the website <https://www.arun.gov.uk/development-plan> as can the leaflet how to respond to planning applications <https://www.arun.gov.uk/planning-application-comments> which deals with material planning considerations.

Please be aware that any comments you may make will be available on our website so please do not insert personal details or signatures on your reply.

Should the application go to appeal the Planning Inspectorate will publish any comments made to the Council on their website: <https://www.planningportal.co.uk/info/200207/appeals> but they will protect personal details.

In the absence of a reply within the period stated, I shall assume that you have no observations to make

Yours sincerely

Maria Tomalova

Planning Officer- Arun District Council

Telephone: 01903 737510

Email: maria.tomalova@arun.gov.uk

