





Existing elevation facing South




Existing end elevation facing East




Existing return elevation facing East


(There is no fenestration in the existing North and West elevations of the single storey building. As these walls form the boundaries with adjacent properties there will be no changes to the North and West elevations as part of these proposals)



Proposed elevation facing South



Proposed end elevation facing East
(no works)



Proposed return elevation facing East

- EXISTING MATERIALS & FINISHES**
- Pitched Roofs: Plain tile
 - Walls: Coarse pebble with facing brickwork detailing
 - Windows: White UPVC
 - Doors: Paint finished timber
 - Rainwater goods: Grey UPVC
- PROPOSED MATERIALS & FINISHES**
- Pitched roofs: Plain tile (no changes)
 - Walls: Coarse pebble with facing brickwork detailing (no changes)
 - Windows: White UPVC sash windows.
 - Doors: Paint finished timber
 - Rainwater goods: Black UPVC

1. In proposed single storey two bedroom dwelling retain existing arch head windows.
2. In proposed single storey two bedroom dwelling remove 6no. existing white UPVC fixed light Georgian style windows and replace with white UPVC sliding sash Georgian style windows to existing openings.
3. In proposed single storey two bedroom dwelling remove existing entrance door and install new door to match existing, but to include small vision panel for security purposes.
4. In proposed single storey two bedroom dwelling externally remove existing sealed entrance door and internally false wall concealing door and install new door to match existing, but to be split horizontally as stable door.
5. In proposed single storey two bedroom dwelling remove existing entrance door and install new door to match existing, but secure in to frame. Internally create false wall to conceal door but expose clerestory light over.
6. Replace all existing grey UPVC rainwater goods with black UPVC rainwater goods.

INSCAPE
INTERIOR
CONTRACTS

CLINT
PROJECT
TITLE
DATE
AUGUST 2010
SCALE
1:50
DRAWN
BB
CLIENT APPROVED
Rev:

INSCAPE INTERIOR CONTRACTS LTD
Orchard House | 38 Appletree Walk | Climping West Sussex BN17 5QN
Tel & Fax: +44 (0)1903 723678 | e-mail: inscapeinterior@btconnect.com

CLIENT SCL Ltd.
PROJECT Sub-division of existing dwelling in to two units of accommodation
Nº 15 Limmer Lane, Felpham
TITLE EXISTING and PROPOSED ELEVATIONS
Drawing Nº RTLL - 2010 - 005