



SPECIFICATION
All works generally, to comply with the written Soft Landscape Specification.

NOTE: DO NOT SCALE FROM DRAWING

Legend

- Existing trees to be retained and protected during construction
- Proposed tree planting within soft landscape. See detail on Sheet 1
- Proposed specimen shrub planting to receive short angular staking on half standards with expandable tree ties. Irrigation tubing to root system of *Amelanchier* and *Cotinus* specimens as required
- Proposed *Lonicera* (honeysuckle) hedge planting to be planted in a double staggered row 400mm apart and at 500mm centres in each row. To be maintained at 1m height
- Proposed mixed native hedge planting to be planted in a double staggered row 300mm apart and at 500mm centres in each row. To be maintained at 1m height and 1.8m height adjacent to site boundaries
- Proposed shrub planting to receive 75mm bark mulch after planting operations
- Proposed mix bulb planting
- Proposed grass areas to receive good quality amenity grass turves laid in line with good horticultural practices
- Proposed wildflower areas, to be seeded with butterfly and honey bee mix (WFG16), or similar and approved
- Cut lines
- Approximate position of bird boxes. For details refer to Ecology Report by Aluko Ecology
- Approximate position of bat boxes. For details refer to Ecology Report by Aluko Ecology

Date: 07.11.16
Details: LPA comments
Drawn: DKM

ACD ENVIRONMENTAL
Ecology
Archaeology
Arboriculture
Landscape Architecture

ACD at these offices:
Rodbourne Rail Business Centre, Grange Lane, Malmesbury, SN16 0ES
Tel: 01666 825646

Courtyard House, Mill Lane, Godalming, GU7 1EY
Tel: 01483 425714

Suite 6, Crescent House, Yonge Close, Eastleigh, SO50 9XS
Tel: 02382 026 300
email: mail@acdenv.co.uk
www.acdenvironmental.co.uk

DAVID WILSON HOMES
BARRATT HOMES

scheme: Phase 4&5 re-plan, Felpham
client: Barratt Homes/ David Wilson Homes
drawing: Landscape Proposals
date: March 2016
scale: 1:200@A1
drawing no: BDWS20444 11 Sheet 1
drawn: JD checked: AE

Copyright of ACD Environmental Ltd. All rights described in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally assigned. 2011. Copyright of this plan remains with ACD until all fees have been paid in full.

Planting Schedule Sheet 1

Trees	Species Name	Girth	Height	Density	Specification	No.
	<i>Prunus avium</i> 'Plena'	12-14cm	350-425cm	Counted	Heavy Standard : Clear Stem 175-200 : BR	11No
	<i>Pyrus calleryana</i> 'Chanticleer'	12-14cm	350-425cm	Counted	Heavy Standard : Clear Stem 175-200 : RB	11No
	<i>Carpinus betulus</i> 'Frans Fontaine'	12-14cm	350-425cm	Counted	Heavy Standard : Clear Stem min. 200 : BR	11No

Shrubs	Species Name	Height	Pot Size	Specification	Density	No.
	<i>Aucuba japonica</i> 'Rozannie'	40-60cm	5L	Bushy	4/m ²	29No
	<i>Berberis verruculosa</i>	40-60cm	5L	Branched	4/m ²	5No
	<i>Choisya ternata</i> 'Sundance'	40-60cm	5L	Bushy	4/m ²	13No
	<i>Cistus</i> 'Silver Pink'	40-60cm	5L	Bushy	4/m ²	17No
	<i>Cotinus coggygria</i> 'Royal Purple'	80-100cm	15L	Bushy	Counted	2No
	<i>Cotoneaster</i> 'Coral Beauty'	40-60cm	5L	Bushy	4/m ²	18No
	<i>Daphne odora</i> 'Aureomarginata'	40-60cm	5L	Bushy	4/m ²	25No
	<i>Euonymus fortunei</i> 'Emerald Gaiety'	30-40cm	5L	Bushy	4/m ²	13No
	<i>Hebe</i> 'Red Edge'	30-40cm	5L	Bushy	4/m ²	11No
	<i>Hydrangea macrophylla</i> 'Altona'	40-60cm	5L	Branched	4/m ²	20No
	<i>Hydrangea paniculata</i> 'Grandiflora'	40-60cm	5L	Branched : 4/6 brks	Counted	2No
	<i>Lavandula angustifolia</i> 'Hidcote'	30-40cm	5L	Bushy	4/m ²	6No
	<i>Mahonia aquifolium</i> 'Apollo'	40-60cm	10L	Bushy	4/m ²	32No
	<i>Mahonia aquifolium</i> 'Atropurpurea'	40-60cm	5L	Bushy	4/m ²	7No
	<i>Mahonia media</i> 'Charity'	60-80cm	10L	Bushy	4/m ²	11No
	<i>Photinia fraseri</i> 'Little Red Robin'	40-60cm	5L	Bushy	4/m ²	15No
	<i>Pittosporum tenuifolium</i> 'Irene Patterson'	40-60cm	10L	Branched	4/m ²	11No
	<i>Pittosporum tenuifolium</i> 'Golf Ball'	40-60cm	5L	Bushy	4/m ²	18No
	<i>Pittosporum tenuifolium</i> 'Tom Thumb'	40-60cm	5-7.5L	Bushy	4/m ²	15No
	<i>Rosmarinus off.</i> 'Miss Jessop's Upright'	30-40cm	3L	Bushy	4/m ²	20No
	<i>Salvia officinalis</i> 'Purpurascens'	20-30cm	3L	Branched	4/m ²	8No
	<i>Sarcococca hookerana humilis</i>	40-60cm	5L	Bushy	4/m ²	33No
	<i>Skimmia confusa</i> 'Kew Green'	40-60cm	5L	Bushy	4/m ²	6No
	<i>Skimmia japonica</i> 'Nymans'	40-60cm	10L	Bushy	4/m ²	9No
	<i>Skimmia japonica</i> 'Rubella'	40-60cm	10L	Bushy	4/m ²	7No
	<i>Skimmia japonica reevesiana</i>	60-80cm	10L	Bushy	4/m ²	8No
	<i>Spiraea japonica</i> 'Goldflame'	40-60cm	5L	Bushy	4/m ²	7No
	<i>Viburnum burkwoodii</i> 'Anne Russell'	40-60cm	5L	Bushy	4/m ²	28No
	<i>Viburnum davidii</i>	30-40cm	5L	Bushy	4/m ²	18No
	<i>Viburnum opulus</i> 'Compactum'	40-60cm	5L	Bushy	4/m ²	11No
	<i>Weigela</i> 'Bristol Ruby'	40-60cm	5L	Branched	4/m ²	25No
	<i>Weigela</i> 'Praecox Variegata'	40-60cm	5L	Bushy	4/m ²	8No

Bulbs	Species Name	Specification	Density	No.
	<i>Crocus chrysanthus</i> 'Snow Bunting'	topsize	20/m ²	15No
	<i>Galanthus nivalis</i>	topsize : to be in the green when planted	20/m ²	22No
	<i>Hyacinthoides non scripta</i>	9+ topsize	20/m ²	15No
	<i>Narcissus pseudonarcissus</i>	topsize	20/m ²	22No

Tree Pit Detail: Soft Landscape

The root flare of the newly planted tree shall be clearly visible at the soil surface and is not to be buried by excess soil or mulch

Stakes to be requisite length, pressure impregnated, debarked softwood 100mm square or diameter, driven into ground sufficient depth to provide full support

Root Rain Metro tree pit irrigation system, or similar

Backfill material is to be applied in layers 150mm in depth, ensuring that the tree is held upright

Once tree has been positioned the hessian and twine surrounding the roots is to be loosened. Wire cages are to be removed

Tree ties to be expandable rubber with spacer block, fixed to stake with heavy duty galvanised nails

1m diameter of decorative bark mulch to be applied to surface of tree pit, to a depth of 75mm

Backfill material to comprise of soil dug from excavated pits (if of sufficient quality) or to be backfilled with 600mm subsoil and 300mm of topsoil, in line with BS3882:2015 Specification for topsoil

Dimension of tree pit to be at least 75mm greater than the rootball. The depth of the pit shall be no deeper than the existing rootball and container depth

Base of tree pit to remain undisturbed unless there is evidence of poor drainage, soil smearing or panning in which case appropriate remediation measures will be required

Components as supplied from GreenBlue Urban or similar