



LIZARD

Landscape Design and Ecology

The Old Bank, 34 South Street, Tarring, Worthing, West Sussex, BN14 7LH

Bognor Regis Golf Club

Tree Inspection Report

Project Reference:	LLD1824
Prepared By:	GS
Checked By:	JJ
Position:	Principal
Date	10.12.2019
Revision:	00

TREE INSPECTION SCHEDULE - FINAL ISSUE - Rev00 - 10th December 2019

Tag No.	Species	Girth (Cm)	Height	Crown Radius	Age	Vigour	Condition	Comments	Actions Required	Priority
T 01	<i>Quercus robur</i> (Pedunculate Oak)	218	15.0 m	7.0 m	Mature	Moderate	Fair	The tree displays decay with 3 no. fungal fruiting bodies to the south-eastern aspect of the base. Hammer tests indicate a change in resonance between 0-20.0 cm height to the east, suggesting a possible area of decay or cavity. Lots of twiggy deadwood is noted with ~ 8 no. pieces of moderate deadwood, including a piece held over the carpark and some over the fence into the adjacent property. The tree's vigour is declining.	Remove/clear out deadwood. Re-survey within 1 year and consider undertaking detailed resistivity survey.	Moderate - Within 12 months
T 02	<i>Aesculus hippocastanum</i> (Horse Chestnut)	345	14.0 m	7.0 m	Mature	High	Fair	The bole divides to 3 no. stems at 1.5 m height. Lots of pruning scars are noted and occluding. Some surface rooting is noted but appears undamaged. The main union displays bark inclusion to the south between the ground and 1.0 m height; the union is damp. Several minor pieces of deadwood are noted. A section of the stem (15 x 30 cm) displays dead, flaking bark emanating from the main union. The heartwood behind is exposed with some reaction growth noted.	Staff to monitor annual leaf out to confirm vitality. Re-survey in 2 years.	Moderate - Within 12 months
T 03	<i>Fraxinus excelsior</i> (Ash)	300	18.0 m	8.0 m	Mature	High	Fair	Soil at the base is slightly banked; fungal fruiting bodies are noted to all aspects of the surrounding soil. The crown divides at 3.0 m height. The tree appears healthy overall; however, because of the potential for ash dieback the grounds staff should monitor and remove any limbs which die back.	Staff to monitor annual leaf out to confirm vitality. Remove any limbs which fail to leaf-out. Re-survey in 1 year for signs of dieback.	Moderate - Within 12 months
TG 04	<i>Fraxinus excelsior</i> (Ash)	200	17.0 m	7.0 m	Early Mature	High	Poor	3 no. trees, displaying possible dieback. Fungal fruiting bodies are noted to the south-eastern and western ground. The trees are dropping lots of minor and moderate deadwood. Because of the potential for dieback, the trees shall be subject to ongoing monitoring, with consideration to removal should significant dieback be observed.	Tree surgeon to visit in spring, remove all moderate and major deadwood and assess overall vitality of trees.	High - Within 6 months
T 05	<i>Quercus robur</i> (Pedunculate Oak)		16.0 m	7.0 m	Mature	High	Poor	The tree's stem sweeps north; bark is missing from c.50% of the southern aspect of the trunk. This section of trunk displays significant decay running 5-10cm deep into the heartwood, with a fungal fruiting body at 0.5 m height to the south-west. Some reaction growth is noted round the decay. A major limb between 6-10.0 m height to the north-east has snapped and displays decay. Moderate decayed deadwood is noted at 8.0 m height to the south with minor hanging deadwood at 6.0 m height to the south.	Remove all moderate and major deadwood. Reduce the decayed major limb to just above union. Reassess tree annually.	High - Within 6 months
T 06	<i>Quercus robur</i> (Pedunculate Oak)	270	12.0 m	6.0 m	Early Mature	High	Good	The tree displays heavy ivy and epicormic growth; the crown divides from 3.0 m height. Lots of twiggy deadwood is noted. A piece of moderate deadwood is present at 3.5 m height to the south-east and at 4.0 m height to the west.	Remove moderate deadwood	Moderate - Within 12 months
TG 07	<i>Betula pendula</i> (Silver Birch)	105	15.0 m	2.0 m	Early Mature	Low	Poor	A group of tall, narrow trees which have been shaded out and have largely died out.	Remove trees or remove all deadwood within 1 year	Moderate - Within 12 months
TG 08	<i>Pinus nigra</i> (Black Pine)	330	23.0 m	7.0 m	Mature	High	Fair	A group of locally dominant trees. Two trees divide to codominant leaders at 4.0 m height. The third divides to a dominant and subdominant leader at 0.5 m height. Lots of moderate and major snapped branches are noted. The central tree displays a major deadwood limb at 14.0 m height to the west. The western tree exhibits a 15.0 cm cavity at 2.0 m height to the north. The cavity is c. 20cm deep.	Shorten all deadwood to 1.0 m length.	Moderate - Within 12 months

LLD1824 - BOGNOR REGIS GOLF COURSE
TREE INSPECTION SCHEDULE - FINAL ISSUE - Rev00 - 10th December 2019

Tag No.	Species	Girth (Cm)	Height	Crown Radius	Age	Vigour	Condition	Comments	Actions Required	Priority
T 09	<i>Quercus robur</i> (Pedunculate Oak)	375	16.0 m	9.0 m	Mature	High	Fair	Growing on a stream bank, with buttressed roots. The stem divides to a dominant and subdominant leader at 2.0 m height. A major deadwood limb is noted to the centre of the crown at 7.0 m height. Lots of moderate deadwood is held to the south-east over the adjacent tee. Major deadwood is noted at 7.0 m height to the south-east.	Remove major deadwood, and all deadwood over tee.	High - Within 6 months
T 10	<i>Pinus sp.</i> (Pine)	80	12.0 m	1.0 m	Semi-Mature	Dead	Dead	A dead tree, with fungal fruiting bodies around the base	Remove	Moderate - Within 12 months
T 11	<i>Acer sp.</i> (Maple)	130	13.0 m	4.0 m	Semi-Mature	Dead	Dead	A dead tree. Most of the bark has fallen off. The crown is dead but still present.	Remove or reduce to 3.0m height.	High - Within 6 months
T 12	<i>Cupressus x leylandii</i> (Leyland Cypress)	183	15.0 m	3.0 m	Semi-Mature	Low	Fair	The tree displays moderate dieback south over the adjacent garden. A small fungal fruiting body is noted at the base to the north-east.	Remove dead growth over 25mm diameter.	Low - At the owner's/manager's discretion
T 13	<i>Pinus nigra</i> (Black Pine)		21.0 m	7.0 m	Mature		Good	Major deadwood is noted to the south-east at 15.0 m height; 7.0 m height to the south-east and 10.0 m height to the south-east.	Remove deadwood	Low - At the owner's/manager's discretion
TG 14	<i>Prunus sp.</i> (Cherry sp.)	90	15.0 m	1.0 m	Semi-Mature	Dead	Dead	Three dead stems, two smaller and one larger.	Remove	High - Within 6 months
T 15	<i>Prunus sp.</i> (Cherry sp.)	85	13.0 m	2.5 m	Semi-Mature	Low	Fair	The tree is very sparse with all growth held north and east.	Reassess in 1 year. Remove if dead	Moderate - Within 12 months
TG 16	<i>Cupressus x leylandii</i> (Leyland Cypress)	140	16.0 m	3.0 m	Semi-Mature	Low	Fair	A line of sparse trees; the tagged tree's top is largely dead as is that of the adjacent tree.	Remove all deadwood over 25mm diameter. Reduce the dead tops by c.5.0 m.	Moderate - Within 12 months
T 17	<i>Quercus robur</i> (Pedunculate Oak)		18.0 m	9.0 m	Mature	Low	Poor	The tree exhibits significant decline, with most of the crown dead. The tree is covered in heavy ivy growth. A wound of 30 x 10cm is noted at the base; reaction wood is noted indicating decay.	Reduce all deadwood over 50mm to 1.0 m length or less. Re-assess tree in 1 year.	High - Within 6 months

LLD1824 - BOGNOR REGIS GOLF COURSE
TREE INSPECTION SCHEDULE - FINAL ISSUE - Rev00 - 10th December 2019

Tag No.	Species	Girth (Cm)	Height	Crown Radius	Age	Vigour	Condition	Comments	Actions Required	Priority
TG 18	<i>Pinus nigra</i> (Black Pine)	300	18.0 m	8.0 m	Mature	High	Good	Group consisting of one standard tree and one which is codominant from 2.0 m height. Lots of moderate internal deadwood is noted. The codominant tree displays a wound of 30cm x 1.0 m high at the base; reaction wood is growing but heartwood decay is noted.	Remove deadwood over 50mm diameter.	Low - At the owner's manager's discretion
T 19	<i>Salix sp.</i> (Willow sp.)	170	18.0 m	8.0 m	Mature	High	Good	Growing on a bank. An old stump is noted at the base. The bole divides to codominant leaders at 1.0 m height. A major limb at 4.0 m height to the south has snapped and rests on the ground.	Remove failed limb and all deadwood over 50mm.	Moderate - Within 12 months
T 20	<i>Salix sp.</i> (Willow sp.)	260	13.0 m	8.0 m	Mature	High	Poor	The tree divides to three stems at 1.0 m height. Numerous woodpecker holes and decaying knotholes are noted. C. 6 no. pieces of moderate deadwood are present within the crown.	Remove moderate deadwood. Monitor every two years and reduce canopy if dieback is noted.	Moderate - Within 12 months
TG 21	<i>Fraxinus excelsior</i> (Ash)	210	16.0 m	8.0 m	Early Mature	High	Good	Trees of good form displaying lots of moderate deadwood.	Remove deadwood.	Low - At the owner's manager's discretion
T 22	<i>Fraxinus excelsior</i> (Ash)	87	14.0 m	3.0 m	Semi-Mature	High	Fair	The tree displays significant damage to the southern aspect of the stem. Moderate deadwood is noted at 4.0 m height and 9.0 m height to the east.	Remove deadwood, and reassess in 2 years.	Low - At the owner's manager's discretion
T 23	<i>Fraxinus excelsior</i> (Ash)	211	16.0 m	8.0 m	Mature	High	Fair	The bole divides to a dominant and two subdominant leaders from 1.5 m height. The main union displays a bark inclusion of c.40cm. The main unions are all tension unions. Lots of moderate deadwood is noted within the crown.	Remove deadwood, and reassess in 2 years.	Low - At the owner's manager's discretion
TG 24	<i>Pinus nigra</i> (Black Pine)	380	20.0 m	8.0 m	Mature	Moderate	Fair	Growing on the edge of the fairway. Lots of major deadwood is noted.	Shorten major deadwood to 1.0 m length or less. Remove moderate deadwood.	Moderate - Within 12 months
T 25	<i>Populus sp.</i> (Poplar sp.)	320	13.0 m	9.0 m	Mature	High	Fair	Moderate deadwood is noted at 5.0 m height over fairway no. 8; a moderate hazard beam is noted at 4.5 m height to the north.	Remove deadwood.	Moderate - Within 12 months
T 26	<i>Pinus sylvestris</i> (Scot's Pine)	155	8.0 m	9.0 m	Early Mature	High	Good	The stem divides to codominant leaders at 1.5 m height. Lots of minor and moderate deadwood are noted within the crown.	Remove deadwood.	Moderate - Within 12 months
T 27	<i>Pinus nigra</i> (Black Pine)	365	17.0 m	8.0 m	Mature	High	Good	Two very large primary scaffolds divide off at 1.0 m and 2.0 m height. A small seam is noted at the base to the south-east. Lots of moderate deadwood is noted. A major failed limb at 10.0 m height is resting on the ground	Reduce deadwood to 1.0 m length or less	Moderate - Within 12 months

LLD1824 - BOGNOR REGIS GOLF COURSE
TREE INSPECTION SCHEDULE - FINAL ISSUE - Rev00 - 10th December 2019

Tag No.	Species	Girth (Cm)	Height	Crown Radius	Age	Vigour	Condition	Comments	Actions Required	Priority
T 28	<i>Salix sp.</i> (Willow sp.)	375	15.0 m	7.0 m	Mature	High	Good	Major deadwood is noted at 7.0 m height to the north over fairway no. 14.	Remove deadwood.	Moderate - Within 12 months
T 29	<i>Fraxinus excelsior</i> (Ash)	290	16.0 m	6.0 m	Mature	Moderate	Fair	Moderate deadwood is noted over tee no. 12 and near green no. 11.	Remove deadwood.	Moderate - Within 12 months
T 30	<i>Fraxinus excelsior</i> (Ash)	242	17.0 m	5.0 m	Mature	Moderate	Fair	The tree is growing on a bank and formed of two stems. Previous heavy reduction works are noted. A woodpecker hole is noted to 12.0 m height to the south-west.	Monitor vigour of tree every 2 years.	Low - At the owner's/manager's discretion
T 31	<i>Fraxinus excelsior</i> (Ash)	248	16.0 m	7.0 m	Mature	Moderate	Fair	The tree is growing on a bank and formed of two stems. Moderate deadwood is noted over adjacent bunker.	Remove deadwood.	Low - At the owner's/manager's discretion
T 32	<i>Fraxinus excelsior</i> (Ash)	141	16.0 m	4.0 m	Semi-Mature	Moderate	Poor	The tree leans to the east and holds moderate deadwood.	Grounds staff to monitor overall condition annually and report to arboriculturalist if condition is noted to alter.	Moderate - Within 12 months
T 33	<i>Crataegus monogyna</i> (Hawthorn)		7.0 m	3.0 m	Semi-Mature	Low	Poor	Dead or dying tree.	Remove	Low - At the owner's/manager's discretion
T 34	<i>Quercus robur</i> (Pedunculate Oak)	165	12.0 m	6.0 m	Early Mature	High	Good	Moderate deadwood is noted at 3.0 m and 5.0 m height to the south.	Remove deadwood.	Moderate - Within 12 months
TG 35	<i>Salix sp.</i> (Willow sp.)	200	15.0 m	7.0 m	Early Mature	High	Fair	Trees of varying forms with minor deadwood to all crowns.	Remove deadwood.	Low - At the owner's/manager's discretion
T 36	<i>Prunus sp.</i> (Cherry sp.)	150	10.0 m	6.0 m	Early Mature	High	Fair	Moderate deadwood is noted to the west (c. 5 no. pieces).	Remove deadwood.	Moderate - Within 12 months
TG 37	<i>Pinus nigra</i> (Black Pine)	385	17.0 m	6.0 m	Mature	Moderate	Fair	Major deadwood is noted at 4.0 m height to the north-west; 3.0 m height to the south.	Remove deadwood.	Moderate - Within 12 months

LLD1824 - BOGNOR REGIS GOLF COURSE
 TREE INSPECTION SCHEDULE - FINAL ISSUE - Rev00 - 10th December 2019

Tag No.	Species	Girth (Cm)	Height	Crown Radius	Age	Vigour	Condition	Comments	Actions Required	Priority
T 38	<i>Pinus nigra</i> (Black Pine)	420	22.0 m	9.0 m	Mature	High	Good	Tree is of good form and has been pruned to the east away from the new housing estate. Several moderate dead limbs are present and still hold dead foliage. 2 no. moderate deadwood limbs are present at 10.0 m height to the south.	Remove Dead Limbs and deadwood.	Moderate - Within 12 months
T 39	<i>Pinus nigra</i> (Black Pine)	440	22.0 m	8.0 m	Mature	High	Good	2 no. moderate deadwood pieces are noted at 9.0 m height to the south. 2 no. major deadwood limbs are noted at 3.0 m and 6.0 m height to the north-west. A moderate hanging limb is noted at 5.0 m height to the north-west. A further moderate deadwood limb is noted at 15.0 m height to the east.	Remove all moderate and major deadwood.	Low - At the owner's/manager's discretion
T 40	<i>Prunus sp.</i> (Cherry sp.)	160	15.0 m	4.0 m	Mature	High	Fair	The tree divides to codominant leaders at 2.0 m height. The southern leader displays a major wound at 4.5 m height to the east. Minor deadwood is present within the crown.	Grounds staff to monitor tree annually and consult arboriculturalist should appearance of wound alter or larger limbs show decline.	Moderate - Within 12 months
T 41	<i>Pinus sylvestris</i> (Scot's Pine)	115	9.0 m	4.0 m	Mature	High	Fair	5 no. pieces of moderate deadwood are noted within the crown.	Remove Deadwood	Low - At the owner's/manager's discretion
T 42	<i>Pinus sylvestris</i> (Scot's Pine)	250	20.0 m	3.0 m	Mature	Low	Fair	The stem divides to codominant leaders at 5.0 m height. Some moderate, and one piece of major deadwood are noted over the fence.	Clear out Deadwood	Low - At the owner's/manager's discretion
T 43	<i>Pinus nigra</i> (Black Pine)	350	22.0 m	8.0 m	Mature	High	Good	Moderate and major deadwood (c. 5 no. pieces) are noted over the golf course, with several other pieces noted over the adjacent garage.	Remove Deadwood	Moderate - Within 12 months
T 44	<i>Pinus sylvestris</i> (Scot's Pine)	110	15.0 m	2.0 m	Semi-Mature	Dead	Dead	The tree is dead, clad in heavy ivy with a slight lean east towards adjacent houses.	Remove	High - Within 6 months
T 45	<i>Pinus sylvestris</i> (Scot's Pine)	185	14.0 m	6.0 m	Early Mature	High	Fair	The tree displays c/ 5 no. pieces of moderate deadwood held to the east and west.	Remove Deadwood	Moderate - Within 12 months
T 46	<i>Prunus sp.</i> (Cherry sp.)	178	13.0 m	6.0 m	Mature	High	Fair	The main union divides at 1.8 m height; a bramble is growing within suggesting dampness and possible decay. Major root damage is occluding but the heartwood displays decay. Moderate deadwood is noted at 3.0 m height to the west.	Re inspect and shorten if determined. Remove Deadwood	Moderate - Within 12 months

TREE INSPECTION SCHEDULE - FINAL ISSUE - Rev00 - 10th December 2019

Tag No.	Species	Girth (Cm)	Height	Crown Radius	Age	Vigour	Condition	Comments	Actions Required	Priority
T 47	<i>Fraxinus excelsior</i> (Ash)	190	13.0 m	5.0 m	Early Mature	High	Good	Tree of good form, with c. 6 no. pieces of moderate deadwood and lots of minor deadwood within the crown. Fungal fruiting bodies are noted c.0.5 m from the base.	Remove moderate deadwood; re-inspect tree at leaf-out in 2020 and update recommendations based on tree's vigour.	High - Within 5 months
T 48	<i>Catalpa bignonioides</i> (Indian Bean Tree)		14.0 m	6.0 m	Mature	High	Fair	A major wound of 15cm wide x 70cm long is noted at the base; the wound is occluding; however, fungal fruiting bodies noted to the base to the north and south indicate decay to the rootplate. 2 no. cavities of c. 8cm diameter are noted to the stem. A major tear-out is noted at 2.0 m height to the west. Lots of twiggly deadwood is noted.	Staff to monitor tree's vigour and consult arboriculturalist should appearance of wound alter or larger limbs show decline. Photos to be taken of any new fungal fruiting bodies.	Moderate - Within 12 months
T 49	<i>Aesculus hippocastanum</i> (Horse Chestnut)	105	7.0 m	2.0 m	Semi-Mature	Dead	Dead	The tree is dead and decayed with fungal fruiting bodies noted to the stem.	Remove	Moderate - Within 12 months
T 50	<i>Quercus robur</i> (Pedunculate Oak)	135	14.0 m	5.0 m	Early Mature	High	Good	3 no. pieces of moderate deadwood, and lots of twiggly deadwood are noted.	Remove Deadwood	Low - At the owner's manager's discretion
T 51	<i>Quercus robur</i> (Pedunculate Oak)	100	14.0 m	5.0 m	Semi-Mature	High	Good	1 no. piece of moderate deadwood is noted to the north.	Remove Deadwood	Low - At the owner's manager's discretion
T 52	<i>Fraxinus excelsior</i> (Ash)	173	15.0 m	8.0 m	Semi-Mature	Moderate	Poor	A clump of trees growing on the boundary. The trees appear of poor overall form; inspection was limited.	Inspect in Spring for Deadwood.	Moderate - Within 12 months
T 53	<i>Unknown</i>	60	5.0 m	2.0 m	Young	Dead	Dead	Unknown dead and decayed tree.	Remove	Moderate - Within 12 months
T 54	<i>Salix cinerea</i> (Grey Willow)	160	13.0 m	6.0 m	Mature	High	Good	Lots of minor internal deadwood is noted.	Remove Deadwood	Low - At the owner's manager's discretion

LLD1824 - BOGNOR REGIS GOLF COURSE
TREE INSPECTION SCHEDULE - FINAL ISSUE - Rev00 - 10th December 2019

Tag No.	Species	Girth (Cm)	Height	Crown Radius	Age	Vigour	Condition	Comments	Actions Required	Priority
T 55	<i>Acer campestre</i> (Field Maple)	141	3.0 m	7.0 m	Mature	High	Fair	The tree grows on a stream bank and leans south-east over adjacent property.	Grounds staff to monitor tree's overall lean at least every six months & notify arboriculturalist if the angle appears altered or ground heave is noted.	High - Within 6 months
T 56	<i>Quercus robur</i> (Pedunculate Oak)	250	15.0 m	5.0 m	Early Mature	Dead	Dead	Dead tree covered in heavy ivy.	Remove tree, or reduce to safe height.	Moderate - Within 12 months
T 57	<i>Pinus sylvestris</i> (Scot's Pine)	170	15.0 m	5.0 m	Early Mature	Moderate	Fair	Tree displays lots of moderate deadwood; with a piece of major deadwood noted to the centre of the tree at 2.0 m height.	Remove Deadwood	Moderate - Within 12 months
T 58	<i>Pinus nigra</i> (Black Pine)	300	12.0 m	8.0 m	Early Mature	Moderate	Fair	The tree displays lots of moderate lower deadwood.	Remove or reduce all deadwood over 25mm diameter.	Moderate - Within 12 months
T 59	<i>Pinus nigra</i> (Black Pine)	140	24.0 m	10.0 m	Mature	High	Fair	Concrete is noted becoming included into the base. The lower crown holds c. 7 no. pieces of major deadwood and the upper crown 3 no. pieces.	Remove Major Deadwood	Moderate - Within 12 months
T 60	<i>Pinus nigra</i> (Black Pine)	285	25.0 m	5.0 m	Mature	High	Good	A major hazard beam is noted at 13.0 m height to the north; the limb is currently hung up in the crown. A moderate hazard beam is noted at 15.0 m height to the east. Major deadwood is noted at 11.0 m height to the north.	Remove deadwood and hazard beams.	High - Within 6 months
TL 61	<i>Pinus nigra</i> ; <i>Pinus sylvestris</i> (Black Pine; Scot's Pine)	300	23.0 m	8.0 m	Mature	High	Good	A line of 8 no. mature trees all displaying lots of moderate and major deadwood. Tree (6) from the north displays a major tear-out to the north and 2 no. pieces of major hanging deadwood. The tree (8) displays a major hazard beam, which currently appears stable. Tree number (9) displays 2 no. major hung up failures to the east.	Remove Major and Moderate Deadwood. Remove hung up branches.	Very High - Within 30 days
TL 62	<i>Pinus sylvestris</i> (Scot's Pine)	165	13.0 m	5.0 m	Semi-Mature	Moderate	Fair	A line of trees, 3 of which are twin stems. All trees displays moderate deadwood. The northern tree displays some major deadwood.	Remove Deadwood	Low - At the owner's/manager's discretion
T 63	<i>Cupressus x leylandii</i> (Leyland Cypress)	155	17.0 m	5.0 m	Mature	Low	Poor	The top half of the tree is dead. All live growth is held to the west.	Reduce top to first live branch.	Low - At the owner's/manager's discretion

LLD1824 - BOGNOR REGIS GOLF COURSE
TREE INSPECTION SCHEDULE - FINAL ISSUE - Rev00 - 10th December 2019

Tag No.	Species	Girth (Cm)	Height	Crown Radius	Age	Vigour	Condition	Comments	Actions Required	Priority
T 64	<i>Pinus nigra</i> (Black Pine)	354	22.0 m	8.0 m	Mature	Moderate	Fair	Moderate deadwood is noted in the crown and is typical for the species.	Remove Deadwood	Low - At the owner's/manager's discretion
T 65	<i>Prunus sp.</i> (Cherry sp.)	124	8.0 m	5.0 m	Semi-Mature	Low	Poor	The stem is codominant from 0.5 m height. The western leader displays bark damage and flaking bark between 1.0-2.0 m height; the top is dead between 4.0-6.0 m height and fungal fruiting bodies are noted to the south-west. The eastern tree's leader is dead.	Remove eastern leader Remove dead top to the western tree. Consider replacement of both trees.	High - Within 6 months
T 66	<i>Prunus sp.</i> (Cherry sp.)	140	9.0 m	6.0 m	Early Mature	V	Fair	The tree consists of 5 no. main leaders; the southern leader displays major decay between 2.0-3.0 m height. Lots of moderate deadwood is noted.	Remove Southern Leader & Deadwood	Low - At the owner's/manager's discretion
T 67	<i>Prunus sp.</i> (Cherry sp.)	165	8.0 m	6.0 m	Early Mature	High	Poor	The stem divides to codominant leaders at 1.5 m height; the eastern leader displays major decay and fungal fruiting bodies, with dieback to the south-east.	Remove Deadwood. Monitor tree's overall condition annually. Consult the arboriculturalist should condition alter.	Moderate - Within 12 months
T 68	<i>Prunus sp.</i> (Cherry sp.)	145	9.0 m	5.0 m	Early Mature	High	Fair	The tree displays several wounds with significant decay and fungal fruiting bodies. Root damage is noted but does not appear to have affected vitality.	Monitor tree's overall condition annually. Consult the arboriculturalist should condition alter.	Moderate - Within 12 months
T 69	<i>Fraxinus excelsior</i> (Ash)	100	16.0 m	6.0 m	Semi-Mature	Moderate	Fair	Moderate hung up stems are noted to the east at 5.0 m height and the north at 6.0 m height.	Remove hung up branches.	Low - At the owner's/manager's discretion
T 70	<i>Pinus nigra</i> (Black Pine)	390	23.0 m	7.0 m	Mature	Moderate	Fair	3 no. pieces of major deadwood are noted within the crown.	Remove Deadwood	Moderate - Within 12 months
T 71	<i>Pinus nigra</i> (Black Pine)	365	23.0 m	9.0 m	Mature	High	Fair	A major limb has snapped at 12.0 m height, has snapped a lower limb at 8.0 m height and both now rest on the ground from 8.0 m height. Now removed.	Remove snapped limbs. Now removed.	Very High - Within 30 days
TL 72	<i>Pinus nigra</i> (Black Pine)	350	23.0 m	9.0 m	Mature	High	Fair	Mature trees, most of which divides to 2-3 no. stems between 2.0-4.0 m height. Lots of moderate deadwood is noted and typical for the species.	Remove Deadwood	Low - At the owner's/manager's discretion

LLD1824 - BOGNOR REGIS GOLF COURSE
 TREE INSPECTION SCHEDULE - FINAL ISSUE - Rev00 - 10th December 2019

Tag No.	Species	Girth (Cm)	Height	Crown Radius	Age	Vigour	Condition	Comments	Actions Required	Priority
T 73	<i>Pinus sylvestris</i> (Scot's Pine)	161	18.0 m	6.0 m	Early Mature	Moderate	Fair	Lots of minor deadwood is noted, as well as 1 no. moderate hanging branch at 10.0 m height to the north.	Remove Deadwood	Low - At the owner's/manager's discretion
T 74	<i>Quercus rubra</i> (Red Oak)	197	19.0 m	6.0 m	Early Mature	Moderate	Fair	Moderate deadwood is noted throughout the crown.	Remove Deadwood	Low - At the owner's/manager's discretion
T 75	<i>Cupressus x leylandii</i> (Leyland Cypress)	300	20.0 m	5.0 m	Mature	Moderate	Poor	The southern tree has partially failed at 9.0 m height. Lots of snapped branches and epicormic growths are noted.	Remove deadwood and snapped branches.	Low - At the owner's/manager's discretion
TL 76	<i>Pinus nigra</i> (Black Pine)	375	23.0 m	8.0 m	Mature	High	Good	Four trees, all with lots of moderate deadwood as typical for the species.	Remove Deadwood	Low - At the owner's/manager's discretion
T 77	<i>Salix fragilis</i> (Crack Willow)	300	16.0 m	8.0 m	Mature	High	Poor	Several main stems have failed to the north and south. These are now hung up low in crown and against ground.	Remove Failed Stems	Low - At the owner's/manager's discretion
TL 78	<i>Pinus nigra</i> (Black Pine)	300	20.0 m	9.0 m	Mature	High	Good	Typical moderate deadwood noted in crown.	Remove Deadwood	Low - At the owner's/manager's discretion
T 79	<i>Pinus sylvestris</i> (Scot's Pine)	120	10.0 m	5.0 m	Semi-Mature	High	Good	Moderate deadwood x c.6 to the west.	Remove Deadwood	Low - At the owner's/manager's discretion
TG 80	<i>Pinus sylvestris</i> (Scot's Pine)	120	9.0 m	4.0 m	Semi-Mature	High	Poor	Moderate deadwood x 6 at c.4.0m height.	Remove Deadwood	Low - At the owner's/manager's discretion
T 81	<i>Cedrus libani</i> (Cedar of Lebanon)	100	9.0 m	4.0 m	Semi-Mature	Low	Poor	Almost dead with only 1 small live branch at the top.	Remove all deadwood	Low - At the owner's/manager's discretion

Tag No.	Species	Girth (Cm)	Height	Crown Radius	Age	Vigour	Condition	Comments	Actions Required	Priority
T 82	<i>Salix fragilis</i> (Crack Willow)	144	13.0 m	5.0 m	Mature	Moderate	Poor	Major wound at base largely occluded. Subdominant stem dead. Moderate deadwood noted at 15.0 m height to the east and west.	Remove dead stem and deadwood.	Moderate - Within 12 months
T 83	<i>Salix sp.</i> (Willow sp.)	85	14.0 m	4.0 m	Semi-Mature	Moderate	Poor	Codominant stems from 4.0 m height. Basal Damage noted. 1 major piece of deadwood of 2.0 m length noted at 4.0 m height to the north. 3 no. pieces of moderate deadwood noted at 4.0 m height to the east.	Remove Deadwood	Moderate - Within 12 months
T 84	<i>Salix fragilis</i> (Crack Willow)	200	23.0 m	5.0 m	Early Mature	High	Fair	Moderate deadwood at 20.0m height to the east.	Remove Deadwood	Moderate - Within 12 months
T 85	<i>Salix fragilis</i> (Crack Willow)	141	19.0 m	5.0 m	Early Mature	High	Poor	Two trees, both with a codominant stem snapped at 5.0 m height to the north, now leaning on the ground.	Remove failed stems.	High - Within 6 months
T 86	<i>Salix sp.</i> (Willow sp.)	141	12.0 m	3.0 m	Early Mature	Dead	Dead	Dead tree with 1 no. standing stem and another which has fallen on T 87.	Remove	High - Within 6 months
T 87	<i>Salix fragilis</i> (Crack Willow)	140	23.0 m	6.0 m	Early Mature	High	Good	Moderate limb at 9.0 m height to the south has been snapped by T 86.	Remove snapped limb.	High - Within 6 months
T 88	<i>Pinus nigra</i> (Black Pine)	350	22.0 m	8.0 m	Mature	High	Good	Major failed hazard beams are noted to the south at 14.0 m height; to the north-east at 10.0 m height and at 12.0 m height to the west. 1 no. major limb has split to the west at 12.0 m height.	Remove hazard beams and split limb.	Very High - Within 30 days
T 89	<i>Pinus nigra</i> (Black Pine)	260	20.0 m	7.0 m	EM	High	Good	A moderate hanging branch is noted at 4.0 m height to the west. A major snapped limb is noted at 6.0 m height to the south and now rests on the ground.	Remove hanging branch and snapped limb.	High - Within 6 months
T 90	<i>Pinus nigra</i> (Black Pine)	250	22.0 m	7.0 m	EM	Moderate	Fair	Lots of moderate to major lower failures are noted, resulting in a high crown.	Remove Deadwood	Moderate - Within 12 months
T 91	<i>Populus sp.</i> (Poplar sp.)	370	23.0 m	8.0 m	Over-Mature	Moderate	Poor	A major cavity is noted at the base to the north-west, of c. 1.0 m height, 60cm depth and 30cm width. The cavity is occluding but is largely hollow. A major occluded tear-out is noted at 13.0 m height to the east.	Shorten all major limbs by 3.0-4.0 m to reduce load on main stem.	Moderate - Within 12 months

LLD1824 - BOGNOR REGIS GOLF COURSE
TREE INSPECTION SCHEDULE - FINAL ISSUE - Rev00 - 10th December 2019

Tag No.	Species	Girth (Cm)	Height	Crown Radius	Age	Vigour	Condition	Comments	Actions Required	Priority
T 92	<i>Pinus nigra</i> (Black Pine)	320	22.0 m	7.0 m	Mature	Moderate	Poor	3 no. very large failed stems are noted between south and west at 5.0 m height. The entire second stem has died.	Shorten dead limbs to 1.0 m length. Remove dead stem.	High - Within 5 months
T 93	<i>Pinus sylvestris</i> (Scot's Pine)	100	15.0 m	4.0 m	Semi-Mature	Moderate	Fair	A dead subdominant leader of 200mm diameter divides off at 1.0 m height. Moderate deadwood is noted high in the crown.	Remove deadwood & dead leader.	Moderate - Within 12 months
T 94	<i>Pinus sylvestris</i> (Scot's Pine)	110	12.0 m	4.0 m	Semi-Mature	High	Fair	Three trees. Moderate deadwood is noted to all trees. The southern tree is dead; the central tree displays major deadwood at 3.0 m height to the west.	Remove deadwood. Remove central tree.	Moderate - Within 12 months
T 95	<i>Pinus sylvestris</i> (Scot's Pine)	95	15.0 m	3.0 m	Semi-Mature	Moderate	Fair	Lots of moderate deadwood is noted.	Remove Deadwood	Moderate - Within 12 months
T 96	<i>Prunus sp.</i> (Cherry sp.)	170	11.0 m	5.0 m	Mature	High	Poor	The tree is codominant from the base. A major limb is held west over the path; a scar of 2.0 m length is noted to the limb.	Removed scarred limb.	Moderate - Within 12 months
T 97	<i>Prunus sp.</i> (Cherry sp.)	110	12.0 m	5.0 m	Early Mature	Moderate	Poor	Lots of moderate deadwood is noted.	Remove Deadwood	Moderate - Within 12 months
T 98	<i>Pinus nigra</i> (Black Pine)	300	24.0 m	8.0 m	Mature	High	Good	Lots of moderate to major deadwood is noted lower in the crown as typical.	Remove/shorten deadwood.	Moderate - Within 12 months
T 99	<i>Pinus sylvestris</i> (Scot's Pine)	140	10.0 m	5.0 m	Semi-Mature	Moderate	Fair	C>6 no. pieces of moderate deadwood are noted to the crown.	Remove/shorten deadwood.	Low - At the owner's manager's discretion
T 100	<i>Pinus nigra</i> (Black Pine)	250	16.0 m	7.0 m	Early Mature	Moderate	Fair	C.10 no. pieces of moderate deadwood are noted to the crown.	Remove/shorten deadwood.	Moderate - Within 12 months

LLD1824 - BOGNOR REGIS GOLF COURSE
TREE INSPECTION SCHEDULE - FINAL ISSUE - Rev00 - 10th December 2019

Tag No.	Species	Girth (Cm)	Height	Crown Radius	Age	Vigour	Condition	Comments	Actions Required	Priority
T 101	<i>Pinus sylvestris</i> (Scot's Pine)	190	14.0 m	8.0 m	Early Mature	High	Fair	The stem divides to codominant leaders at 1.5 m height. 1 no leader displays woodpecker holes and has snapped at 6.0 m height. Moderate deadwood and a snapped limb are noted at 4.0 m height to the north-east.	Remove deadwood to c.50cm above woodpecker holes. Monitor tree's overall condition annually and consult the arboriculturalist should any further decline be noted.	Low - At the owner's/manager's discretion
T 102	<i>Pinus sylvestris</i> (Scot's Pine)	120	14.0 m	8.0 m	Early Mature	Moderate	Fair	A group of three trees, all displaying moderate deadwood.	Remove Deadwood	Low - At the owner's/manager's discretion
T 103	<i>Pinus nigra</i> (Black Pine)	400	22.0 m	9.0 m	Mature	High	Good	Lots of internal major deadwood is noted. At 15.0 m height to the north, a moderate hanging branch on a major limb is forming into a hazard beam.	Remove deadwood. Remove moderate hanging branch or shorten by 50%.	High - Within 6 months
T 104	<i>Pinus nigra</i> (Black Pine)	495	22.0 m	8.0 m	Mature	High	Fair	The tree displays moderate deadwood, with several major failed limbs already shortened. 1 no. moderate hanging branch is noted at 6.0 m height to the north-west. A major hanging branch is noted at 10.0 m height to the north-west.	Remove deadwood.	Moderate - Within 12 months
T 105	<i>Pinus nigra</i> (Black Pine)	160	21.0 m	7.0 m	Early Mature	Moderate	Fair	Four trees all displaying moderate-major deadwood within the lower crowns.	Remove deadwood.	Moderate - Within 12 months
T 106	<i>Pinus nigra</i> (Black Pine)	370	22.0 m	8.0 m	Mature	High	Fair	Two trees, both of which have several major failed limbs. Most of these are already decayed and shortened. 1 no. moderate hanging branch is noted.	Remove deadwood.	Moderate - Within 12 months
T 107	<i>Salix sp.</i> (Willow sp.)	300	8.0 m	9.0 m	Over-Mature		Dead	The stem has failed at 2.0 m height; the large crown is now resting on the ground. The tree has snapped several limbs of the adjacent pine tree.	Remove failed section. Leave stump to regrow to smaller veteran tree. Remove damaged limbs from adjacent pine tree.	High - Within 6 months
T 108	<i>Pinus sylvestris</i> (Scot's Pine)	140	11.0 m	5.0 m	Semi-Mature	Moderate	Poor	The tree displays dense ivy growth; 4 no. pieces of moderate deadwood are noted, with 1 no. piece near to the path.	Remove deadwood.	Moderate - Within 12 months

Tag No.	Species	Girth (Cm)	Height	Crown Radius	Age	Vigour	Condition	Comments	Actions Required	Priority
T 109	<i>Pinus nigra</i> (Black Pine)	300	17.0 m	7.0 m	Early Mature	High	Fair	A major snapped limb is recorded at 5.0 m height to the south. Limb now removed. Lots of moderate deadwood remains in the crown.	Snapped limb removed. Remove deadwood.	Low - At the owner's manager's discretion
T 110	<i>Pinus sp.</i> (Pine)	360	14.0 m	0.0 m	Semi-Mature	Dead	Dead	Dead tree, with no bark after 3.0 m height.	Remove tree.	High - Within 6 months
T 111	<i>Pinus nigra</i> (Black Pine)	360	23.0 m	8.0 m	Mature	High	Good	Tree displays c. 4 no. pieces of moderate deadwood; one piece at 6.0 m height to the east appears unstable.	Remove deadwood.	Moderate - Within 12 months
T 112	<i>Pinus sylvestris</i> (Scot's Pine)	135	13.0 m	4.0 m	Early Mature	Low	Poor	A largely dead moderate hanging branch is noted over the fairway at 4.0 m height. Lots of moderate to major deadwood is noted.	Remove hanging branch and deadwood.	High - Within 6 months
T 113	<i>Pinus sylvestris</i> (Scot's Pine)	95	11.0 m	3.0 m	Semi-Mature	Low	Poor	The tree displays a dead subdominant leader at 6 no. pieces of moderate deadwood.	Remove deadwood.	High - Within 6 months
T 114	<i>Prunus sp.</i> (Cherry sp.)	130	15.0 m	5.0 m	Early Mature	Moderate	Poor	A major stem wound of 60x20cm is noted at 2.0 m height. 3 no. pieces of moderate deadwood are noted higher in the crown.	Remove deadwood.	Moderate - Within 12 months
T 115	<i>Pinus nigra</i> (Black Pine)	300	23.0 m	9.0 m	Mature	High	Good	The tree displays typical moderate deadwood. A major hazard beam is noted at 15.0 m height to the fairway; the beam has damaged a major limb beneath.	Remove hazard beam and damaged limb beneath.	Very High - Within 30 days
T 116	<i>Salix sp.</i> (Willow sp.)	400		8.0 m	Mature	High	Good	A moderate snapped hanging limb is noted at 6.0 m height to the south-west. Moderate deadwood is noted at 6.0 m height to the north.	Remove hanging limb and deadwood.	Low - At the owner's manager's discretion
T 117	<i>Salix sp.</i> (Willow sp.)	500	20.0 m	9.0 m	Mature	High		The tree divides on a compression union from the base. The main union is largely decayed. The main growth leans east over the fairway.	Tree's condition to be monitored by grounds staff at least 6-monthly; any change in the tree's state to be reported to the arboriculturalist. Tree to be re-inspected within 1 year, or subject to 4.0-5.0 m reduction to crown.	High - Within 6 months

LLD1824 - BOGNOR REGIS GOLF COURSE
TREE INSPECTION SCHEDULE - FINAL ISSUE - Rev00 - 10th December 2019

Tag No.	Species	Girth (Cm)	Height	Crown Radius	Age	Vigour	Condition	Comments	Actions Required	Priority
T 118	<i>Crataegus monogyna</i> (Hawthorn)	85	10.0 m	2.0 m	Semi-Mature	Dead	Dead	The tree is dead and decayed, leaning north-east.	Remove tree.	Low - At the owner's/manager's discretion
T 119	<i>Salix sp.</i> (Willow sp.)	365	22.0 m	8.0 m	Mature	High	Good	4 no. pieces of moderate deadwood are noted to the east.	Remove deadwood.	Low - At the owner's/manager's discretion
T 120	<i>Salix sp.</i> (Willow sp.)	349	22.0 m	8.0 m	Mature	High	Good	A major cavity of 20cm width is noted to the west between 0-2.0 m height. The cavity is obscured by ivy; it appears to be occluding but with significant decay present.	Remove Ivy, re-inspect within 1 year.	High - Within 6 months
T 121	<i>Salix sp.</i> (Willow sp.)	330	20.0 m	8.0 m	Mature	High	Fair	A major hazard beam is noted to the north-west at 3.5 m height. The limb appears to be entirely dead. Another hazard beam is noted at 7.0 m height to the north; this appears to still be alive.	Remove dead hazard beam and shorten live hazard beam to leave no more than 1.0 m beyond split.	High - Within 6 months
T 122	<i>Pinus nigra</i> (Black Pine)	300	21.0 m	9.0 m	Mature	Moderate	Fair	Major snapped limbs are noted within the crown; 4 no. pieces of major deadwood are present in the crown, with 1 no. piece hung up to the west.	Remove deadwood.	Moderate - Within 12 months
T 123	<i>Crataegus monogyna</i> (Hawthorn)	100	7.0 m	3.0 m	Mature	Low	Poor	Tree is largely dead, with a major limb fallen to the ground.	Remove deadwood.	Moderate - Within 12 months
T 124	<i>Malus sp.</i> (Apple sp.)	98	5.0 m	3.0 m	Semi-Mature	Low	Poor	The tree is almost dead with 3 no. moderate deadwood limbs and lots of dieback noted.	Remove deadwood. Tree to be monitored by grounds staff every 6 months, and removed should it die.	Low - At the owner's/manager's discretion
T 125	<i>Alnus incana</i> (Grey Alder)	130	9.0 m	4.0 m	Early Mature	High	Good	Moderate deadwood is noted over the track and a minor hanging branch is present to the south-east.	Remove hanging branch and deadwood.	Moderate - Within 12 months
T 126	<i>Fraxinus excelsior</i> (Ash)	145	13.0 m	6.0 m	Early Mature	Moderate	Good	3 no. pieces of moderate deadwood are noted to the north and west.	Remove deadwood.	Moderate - Within 12 months

LLD1824 - BOGNOR REGIS GOLF COURSE
TREE INSPECTION SCHEDULE - FINAL ISSUE - Rev00 - 10th December 2019

Tag No.	Species	Girth (Cm)	Height	Crown Radius	Age	Vigour	Condition	Comments	Actions Required	Priority
T 127	<i>Pinus sylvestris</i> (Scot's Pine)	115	12.0 m	4.0 m	Semi-Mature	Moderate	Fair	Lots of moderate deadwood is noted within the crown.	Remove deadwood.	Low - At the owner's/manager's discretion
T 128	<i>Salix sp.</i> (Willow sp.)	172	18.0 m	6.0 m	Early Mature	High	Fair	A rotten stump is noted to the base. Woodpecker holes are present to a subdominant stem. Major deadwood is noted at 6.0 m height.	Remove deadwood.	Moderate - Within 12 months
T 129	<i>Pinus nigra</i> (Black Pine)	424	22.0 m	9.0 m	Mature	High	Fair	A moderate hanging branch is noted at 7.0 m height to the east. 2 no. major deadwood limbs are noted; at 4.0 m height to the east and 3.0 m height to the south.	Remove deadwood.	Low - At the owner's/manager's discretion
T 130	<i>Pinus nigra</i> (Black Pine)	424	23.0 m	9.0 m	Mature	High	Fair	Tree displays 2 no. moderate hanging branches and 2 no. pieces of moderate deadwood to the south-east.	Remove hanging branch and deadwood.	Moderate - Within 12 months
T 131	<i>Crataegus monogyna</i> (Hawthorn)	127	8.0 m	5.0 m	Early Mature	Moderate	Fair	A dead limb of c.200mm diameter and 7.0 m length is noted within the crown.	Remove deadwood.	Moderate - Within 12 months
T 132	<i>Crataegus monogyna</i> (Hawthorn)	90	8.0 m	4.0 m	Early Mature	Moderate	Fair	Decay is noted at the base of the tree, growing on the ditch bank. The tree has failed and fallen over.	Remove tree.	High - Within 6 months
T 133	<i>Salix sp.</i> (Willow sp.)	124	22.0 m	4.0 m	Early Mature	Low	Poor	The tree is codominant from the base, displaying very low vigour and lots of moderate-major deadwood.	Reduce tree to c. 6.0 m height or remove all deadwood over 25mm diameter.	Moderate - Within 12 months
T 134	<i>Salix sp.</i> (Willow sp.)	140	20.0 m	5.0 m	Early Mature	Moderate	Poor	Lots of moderate deadwood is noted and caused by overshadowing from other trees.	Remove deadwood.	Moderate - Within 12 months
T 135	<i>Salix sp.</i> (Willow sp.)	176	18.0 m	6.0 m	Early Mature	Moderate	Poor	A major failure is noted at 4.0 m height to the east. C. 5no. Pieces of major deadwood are noted within the crown.	Remove deadwood and major failed limb.	Moderate - Within 12 months
T 136	<i>Pinus nigra</i> (Black Pine)	300	18.0 m	7.0 m	Early Mature	Low	Fair	A major deadwood limb is noted at 8.0 m height to the south and another at 9.0 m height to the west. Several moderate failures and major stubs, and lots of moderate deadwood are noted.	Remove Deadwood	Moderate - Within 12 months
T137	<i>Pinus nigra</i> (Black Pine)	350	22.0 m	9.0 m	Mature	High	Good	A major hanging branch is noted at 10.0 m height to the west.	Remove hanging branch.	High - Within 6 months

Scope of Survey:

To carry out a detailed specification identifying the following;

- *The Designated Area;*
- *Date of Inspection;*
- *Tree Number;*
- *Tree Species;*
- *Tree Height (m);*
- *Trunk Diameter;*
- *Crown Radius;*
- *Vigour;*
- *Age;*
- *Surrounding Features;*
- *Condition;*
- *Action;*
- *Priority.*

Survey Schedule

Surveys undertaken in October-November 2019.

Tree Inspection – Explanation Key

Tree Ref No. – A unique number identifying each tree on an accompanying site plan.

Species – Tree Species – Recorded as a common and Latin name for species.

Height – Approximate tree height above ground level expressed in metres.

(Groups of trees will be surveyed with the average height given. Where accurate heights are required these can be obtained with optical instruments.)

SD – Stem Diameter

The tree trunk stem diameter measured at 1.5 m above ground level in millimetres.

(On sloping ground this is 1.5 m above ground level. Where two or more stems are present below 1.5 m the tree will be surveyed immediately above the root flare.)

Crown Spread

The approximate extent of the spread of branches in the crown taken from the tree trunk to outer edge of general crown of individual trees or the canopy spread of the multiple trees and groups.

Measured as an average or largest branch as appropriate

(The figure is the distance of the general crown line. In certain cases, an exceptional or etiolated branch may extend beyond the stand figure.)

Life Stage

	Life Stage	Definitions
Y	Young	Recently planted or established tree that could be transplanted with the correct equipment.
E/M	Semi-mature	An established tree, but with some growth to make before reaching its potential maximum size. A tree within its first third of life span.
S/M	Early mature	A tree reaching its ultimate potential height, whose growth rate is slowing down but if healthy, will still increase in stem diameter and crown spread. A tree in its second third of life span.
M	Mature	A mature specimen with limited potential for any significant increase in size, even if healthy. A tree within its final third of life span.
O/M	Over-mature	A senescent (<i>declining/degradation</i>) or moribund specimen of low vigour within its final third of expected life span. Possibly containing sufficient structural defects with safety and/or duty of care implications.
V	Veteran	Specimen exhibiting features of biological, cultural or aesthetic value that are characteristic of, but not exclusive to, individual surviving beyond the typical age range for the specimen concerned.
D	Dead	The tree is dead and cannot be clarified as a veteran tree. Its age up till death is of no significance.

Physiological Condition

	Condition	Definition
G	Good	Generally in good health typical of the species needing little, if any attention. Few minor defects of little overall significance such as physical damage or suppressed branches. Showing no adverse risk of failure/defects.
F	Fair	A tree or trees of minor but rectifiable defects or in the early stages of stress, from which it may recover. Showing minor signs of deterioration. This could include a major defect in its early life stage, or multiple minor defects. A tree that may require work to remove or improve a defect.
P	Poor	A tree or trees with major structural and physiological defects or stressed such that it would be a risk to retain in its current or future known situation. Unlikely to return to a good condition given time or remedial work.
D	Dead	A tree or trees no longer alive. However, this could also apply to those trees that are dying and will be unlikely to recover, or are becoming or have become dangerous.

Vigour

	Condition	Definition
H	High	In good health, with new extension growth within the current growing season, normal leaf formation and a dense crown. Any dieback is isolated or caused by external factors such as shading.
M	Moderate	A tree or trees of generally good health and recent growth. No major faults in growth pattern but more sparse than typical, slightly stunted growth, smaller leaves or minor dieback.
L	Low	A tree or trees with live growth still present, but little recent growth, sparse canopy, very small or malformed leaves, or significant dieback.
D	Dead	A tree or trees no longer alive. However, this could also apply to those trees that are dying and will be unlikely to recover, or are becoming or have become dangerous.

Structural Condition

The structural condition is defined by the presence of any decay pathogens and/or physical defects and problems following inspection of the root and buttress area, trunk, branches, both primary and secondary and crown including twigs, leaves and buds.

Recommendations (*Remedial Action*)

In order to identify priorities and assist in tree management recommended works are categorized according to the perceived level of urgency that the recommended treatment requires.

Prioritisation considers:

- Significance of any identified defect such as the presence of any decay and/or physical defect based on root and buttress area, trunk, scaffold limbs and crown
- Tree size, or tree part considered likely to fail.
- Nature of target area vulnerable to direct impact from tree or part, considered likely to fail and apparent frequency of target area usage.
- Apparent imminence of failure of the identified tree or part

Included are any recommendations for further investigation of suspected defects that require more detailed assessment, decay deflection, ivy removal and other obstruction or potential for wildlife habitat.

Arboricultural works are specified and should be carried out in accordance within the guidelines of the British Standard **BS3998: 2010 'Recommendations for Tree Works'**

Work Priority

Based on the collection of data above, the management recommendations are categorised by priority in accordance with the below table.

Category	Priority	Response
A	Urgent	Within 24 hours – Call client from site to discuss
B	Very High	Within 30 days
C	High	Within 6 months
D	Moderate	Within 12 months
E	Low	Work to be carried out as and when at the owners/managers discretion

Inspection Frequency

A period of time specified in months and/or years that this tree should undergo a full and detailed inspection as could also be determined in the above recommendations and work priority.

Dead wood

Dead wood	Definition / Size
Minor	Material up to 5 cm in diameter.
Moderate	Dead wood 5 cm to 10 cm in diameter.
Major	Dead wood 10 cm in diameter and above.

Tree Inspection – General Notes

Reinspection Frequency – Unless otherwise specified, the recommendations within this report are based on a re-inspection frequency of no longer than 2 years; i.e. within the summer of 2021. Any trees requiring works outside of this timeframe have not been recorded.

Minor defects – Unless works are specified within the re-inspection timeframe, trees with minor defects have not been recorded. Therefore, absence of a tree from this report does not guarantee the absence of defects within the tree.

Woodland and Tree Belts – In woodland areas or dense tree belts, only trees with defects liable to cause significant harm in the immediate future are recorded; minor dead wood has generally not been recorded in these areas, as well as larger deadwood away from paths. Most trees are assumed to have defects within these areas and the inspection seeks to prioritise actions. As such this report is not a definitive record of all defects within these areas, or a silvicultural management plan but rather a list of highest priorities for action to safeguard wellbeing of users of the site.

Ongoing / Cyclical Tree Surgery Works – Ongoing or cyclical works including thinning; coppicing; pollarding; hedge trimming; crown reduction / lifting for amenity reasons; and removal of sucker / epicormic growth have not been included within this report unless required for safety reasons or further inspection.

Fungal Fruiting Bodies – Surveys were undertaken in May and June; a time when many fungal fruiting bodies have yet to emerge and when last season's bodies were in advance decay. As such, the presence or likely absence of fungal infection within trees can only be assumed on the basis of the tree's overall vigour or visible external signs of fungal infection.