

REASONS FOR PROPOSED TREE WORK

T1 Cherry between 35 & 37 Gateway Lodge

Reduce the longest, declining branch ends back to sound wood – current height is 6.5m with an expected finished height of 5.5m

Insert a single section of rod bracing through the lower stem to reduce the risk of the included union failing

The upper crown is beginning to decline and to reduce the risk of the decline advancing down the stem sections, the specification is intended to prune out the declining branch ends back to sound wood.

The tree has multiple include unions, the largest being where the stems bifurcate close to ground level. The insertion of a rod brace will restrict movement that could exacerbate the problem.

SH1 Bay tree adjacent to pedestrian gate and the Barbers

Trim top to previous level – approximately 2m

The Bay has now been reduced to an acceptable size and the above specification is intended to encourage further regrowth so that a more 'bush' like structure can be achieved.