


Dave Mayall
74 Outerwyke Road
Bognor Regis
West Sussex



AFA Consulting Ltd
44 Finians Field
Barns Green
Horsham
West Sussex
RH13 0NQ



General Tree Assessment (Summary)

Tree Ref	Species	H (m)	Spr (m)	Maturity	Condition	Action Recommendations	Hours	Priority	Done	Inspected
----------	---------	-------	---------	----------	-----------	------------------------	-------	----------	------	-----------

T1	Monterey Cypress	16	8	OM	Fair	See Comment :: Unspecified		1 year	No	04-Nov-21
----	------------------	----	---	----	------	----------------------------	--	--------	----	-----------

Comment: A large and prominent tree providing good visual amenity and wildlife value but also displays visible biomechanical defects which are prone to failure and require remediation pruning and management. The northern canopy hangs low over adjacent footpath and road and should be lifted to 3.5m and 5.5m respectively in accordance with the Highways Act. The southern radial spread is overlong and prone to shedding. To mitigate any likelihood of failure the northern radial spread should be reduced by 2.5m to leave a spread of 6.5m. The western canopy is fouling overhead utility lines and should be reduced by 1.5m to abate the nuisance and leave a radial spread of 5.5m. The upper canopy is displaying decline (likely attributed to drought stress or root compaction). The overall canopy height should be reduced by 2m to leave a height of 13.8m. There are several dead and hung up limbs which are prone to failure and should also be removed.

Age Classification:	NP Newly planted	EM Early Mature	Condition:	Overall unless specified as -	C Crown
	Y Young	M Mature			S Stem
	SM Semi-mature	OM Over Mature			B Basal area