



General

To supply and install 1 sliding gate and automation. Gate to provide increased security and convenience. Also supply and install a single pedestrian gate to similar design

Gates and supports

To supply and install flat topped single tracked sliding gate frame only and all required supports. Approx 5000mm open width x 1800mm high gate. All visible steel galvanized. Option of powder-coating in most RAL colours. Gate frame ready for cladding in options timber or further finishes by others. Ground track beam supplied ready for set up by us. Pedestrian approx 850mm wide x 1800 high (tbc) gate to have option of Locinox latch/deadlock with eurocylinder. Option of pedestrian gate closing device.

Vehicle gate automation

To supply and install sliding gate automation and required command and safety devices, detailed below:

Entry

Digital keypad. Radio receiver standard for remotes (4)

Exit

As above. Digital keypad

Safety

To help prevent accidental closure of the gate onto vehicles or objects still within the entrance, some form(s) of safety devices must be used. 1 set of **safety photocells** will be installed to the front of the gates. All installations are carried out to **EN** machine directive regulations and will include safety edges where appropriate. In this case, front and rear of gate frame.

Locking

The sliding gate will automatically lock when stopped. A key will override the mechanism, in the event of a power failure.

Power supply

A 230v 13A supply will be required, by others

Civils

All groundwork, concreting and final finish by others. We will supply sketches etc for them to carry this out. Final finish of the drive by others

Entryphone

Option to install a wired BPT telephone entry system. Cable to house to have duct supplied to house to run our cable in. Duct run by others. Cable then run externally to position TBC.

Prices

Gates and Supports

Vehicle gate supports as described, unclad	£2570.00
Vehicle gate clad with option of 150x25 TGV home grown cedar face side only. Rear side clad add £650 + Vat	£980.00

Automatic Gate Systems Ltd. - 23 North Road - Bosham - West Sussex - PO18 8NL
01243 574454 - 0870 458 1624 - www.automaticgates.co.uk - sales@automaticgates.co.uk
registered in England no 5520529

