



IAE Top Shot Goal End 'Striker' 7.2m wide shooting wall with recessed goal mount



IAE Top Shot Ballcourt fencing:

- Compliant with BS EN 15312:2007
- Recessed fixings
- Impact and Kick Tested
- Assessed for finger/limb entrapment
- Hot Dip Galvanised to BS EN ISO 1461
- Polyester Powder Coated



Soccer Store 12 x 6ft Mini Soccer Steel Socketed Football Goal posts (net optional)

Prosafe single leaf hydraulic self closing pedestrian access gate 1.2m wide in red for partially sighted users

Prosafe double leaf combination maintenance gate 3m wide c/w hydraulic self closer on one leaf in red for partially sighted users



Thermoplastic line markings for basketball (white) and 5-a-side football (yellow) 50mm wide

IAE Top Shot Ballcourt access gate 2.15m high, 1.2m wide in red for partially sighted users

6mm open textured macadam surfacing course laid over an open textured macadam binding course

Macadam surfacing to be laid over a stone foundation and geotextile membrane

Surfacing to be defined with PCC edging

IAE Top Shot Ballcourt fencing 3.2m height supplied Hot Galvanised to BS EN ISO 1461 and Polyester Powder Coated in dark green

Mesh infill to fencing 50mmx41mm steel grid framed top and bottom with square hollow section

1m wide run off area between the extent of the pitch and the fencing

IAE Top Shot Goal End 'Striker' includes recessed goal and mounted basketball hoop

5-a-side pitch
32.5m x 20m

MUGA
37m x 18.5m

Soccer Store 12 x 6ft Mini Soccer Steel Socketed Football Goals SKU: 2960

Bow top fencing 1m high in black encloses the pitch by joining up to MUGA fence line

Do not scale hard copies of this drawing or interrogate CAD versions, only stated dimensions and coordinates are to be relied upon

MUGA, Blakes Mead - Felpham

Landscape Plan

Barratt Homes - Southampton

ARUN DISTRICT COUNCIL FP/85/19/DOC

5456

Revision B
1:100 at A1

EM

5th August 2013