

- A

Grass matting 'ecosmart' surfacing provides a safer surface to the play equipment and prevents wear
- B

Mounding between 0.5m - 1.25m in height to a gradient of 1:3 where possible created using spoil on site
- C

Premium Grade turf to area
- D

Ornamental tree planting 12-14cm girth
- E

Single species hedge to fence line beds to be dressed with 50mm depth bark mulch
- F

Block paving to entrances and seating with keyblock edging
- G

Play boulders 600-900mm diameter as play feature on mound
- H

Railway sleepers 2.4m length, 0.2m wide as a balancing feature to cross mounds
- I

Powder coated bow top fencing 1.2m high in black encloses the play space
- J

Self closing pedestrian access gate 1.2m wide in red for partially sighted users
- K

Maintenance access gate 3m wide including self closing pedestrian access gate 1.2m wide in red for partially sighted users

Do not scale hard copies of this drawing or interrogate CAD versions, only stated dimensions and coordinates are to be relied upon

Signage to the play space to include the following notifications -

- the area is solely for the use of children
- adults are not allowed unless accompanied by children
- dogs are excluded
- the name and telephone number of the operator of the facility should be detailed to report any incident or damage to the play equipment
- location of the nearest public telephone

N.B. All natural play features and play equipment to comply with and be in accordance with the provisions of BS EN 1176 - playground equipment and surfacing and BS EN 1177 - impact absorbing playground surfacing.

